


## ADDENDUM No. 1

**TO:** ALL BIDDERS  
**PROJECT:** Blacktail WMA North & West boundary Fence  
FWP #599302  
**DATE:** June 6, 2012  
**FROM:** Dan Stinson, Project Manager



**== !NOTE! THIS ADDENDUM INCLUDES A REVISED PROPOSAL FORM! ==**

**Acknowledge receipt of this addendum by inserting its number and date in the Proposal Form and on the Bid Envelope. Failure to do so may subject bidder to disqualification.**

This Addendum forms a part of the Contract Documents. Clarification and/or modifications area as follows:

- 1) Change** - Replace original Proposal Form found on page 12 and 13 of the Project book is to be replaced in it's entirety by the Revised Proposal form at the end of this Addendum.
- 2) Clarification** – Locations of fence corners on the southwest corner of the job will be located by the Project manager prior to the start of construction.
- 3) Change** – Original Base Bid Item 12 is divided in to Base Bid Items 12 and 13.

**New Item 12** is one 12' steel farm gate with two single panel braces and two posts behind the gate to block vehicular use. This is to be provided and installed adjacent to cattleguard location as shown in Addendum drawing following.

**New Item 13** is clean & repair cattleguard and set new steel pipe entry gate provided by owner.

a) Cattleguard pit is assumed to have serviceable timbers. Timbers will be evaluated after excavation of pit. Any required replacement of timbers would be considered as a Change Order at that time.

b) Cattleguard will require new wings, as the current cattleguard does not have wings.

c) Steel pipe entry gate in this item is described on page 10 of 11 of drawings This gate will be provided on-site by the owner and is to be set adjacent to the cattleguard as shown in Addendum drawing following.

**4) Addition** - In Technical Specifications (page 111), in Section 02810 Fencing Page 9 of 10, Part 3 EXECUTION, Section 3.3 EXISTING FENCE REMOVAL, a new paragraph D is added and the current paragraph D is renumbered paragraph E.

Revised Section 3.3 will read as follows:

### 3.3 EXISTING FENCE REMOVAL

- A. All existing fence along the new fenceline shall be dismantled and removed unless specified under MATERIAL SALVAGE below. The **contractor is responsible for maintaining the integrity of the fence** to retain livestock at all times. Steel posts south of the North Section Line of Section 33 along the west boundary shall be removed and disposed of.
- B. Jackleg fence along the west boundary shall be removed, dismantled and stacked neatly at a location designated near the West Entry.
- C. Wood posts south of the North Section Line of Section 33 shall be cut off at the ground and the cut posts stacked with the removed jackleg fence materials at the designated location near the West Entry.

[new paragraph]

- D. Any jackleg fence along the north boundary is to have the nails or screws removed in whatever manner the contractor chooses. Nails may be individually removed, sections of jacks may be cut out to remove nails with those sections removed, jacks may be removed intact, rails may be removed intact or rail ends with nails may be cut off and removed. The method of removing the nails will be at the discretion of the contractor with approval of the Project manager.

Remaining wood pieces without nails are to be cut in to approximately 4' or shorter lengths and neatly stacked in small piles on the owner's property, at several nearby locations designated by the Project Manager.

#### ~~D~~:E. Material Salvage

Steel posts and woven wire north of the North Section Line of Section 33 on to the east end of the project shall be removed and salvaged. Steel fence posts shall be stacked neatly at locations designated by the Project Manager. Woven wire shall be rolled and tied and stacked neatly at locations designated by the Project Manager.

**5) Clarification** - In the General Conditions, there is NO "Buy American" Provision.

**END OF ADDENDUM NO. 1**

# ADDENDUM No.1 West End Entry Area Detail Clarification



Provide and install  
new cattleguard wings

Set Entry Pipe Gate  
provided by owner.

Existing Cattleguard  
Clean out pit and confirm  
existing support timbers  
are sound.

New 12' Steel Farm Gate

BLACKTAIL ROAD

## KEY

Existing fence to  
be removed

New fence

D. Stinson

Drawn by: \_\_\_\_\_

Date: \_\_\_\_\_

Revised by: \_\_\_\_\_

Date: \_\_\_\_\_

Approved by: \_\_\_\_\_

Date: \_\_\_\_\_



Montana Fish,  
Wildlife & Parks

North & West Fence Replacement

Blacktail WMA —ADDENDUM No. 1— FWP# 599302

Checked by: \_\_\_\_\_

Date: \_\_\_\_\_

Approved by: \_\_\_\_\_

Date: \_\_\_\_\_

Approved by: \_\_\_\_\_

Date: \_\_\_\_\_

**PROPOSAL**  
**= Revised June 7, 2012 =**

Montana Fish, Wildlife & Parks  
Design and Construction Section  
PO Box 200701, 600 North Park Avenue  
Helena, Montana 59620-0701

FWP Project #: 599302

The undersigned, having familiarized himself with the conditions of the work and the contract documents as prepared by FWP, agrees to furnish all labor, materials, equipment, and services necessary to complete all general construction work, as bid herein, for a project entitled **Blacktail Wildlife Management Area, West & North Boundary Fence Replacement, Beaverhead County, Montana** in accordance with the Contract Documents including all Addenda. Bidder agrees to perform all work described below at the price shown as follows:

**BASE BID**

Item #	Description	Estimated Quantity	Unit Measure	Unit Price	Extension
1	Mobilization / Demobilization	1	LS	\$	\$
2	Four wire fence with steel posts and wood brace posts as per specifications.	45,950	Lin.Ft.	\$	\$
3	Four wire gate	5	Each	\$	\$
4	Stream crossing	3	Each	\$	\$
5	Deadman anchors	24	Each	\$	\$
6	Drainage Channel Crossings	4	Each	\$	\$
7	Existing fence removal	29,800	Lin.Ft.	\$	\$
8	Jackleg fence removal	1,235	Lin.Ft.	\$	\$
9	Single Panel brace	90	Each	\$	\$
10	Double Panel brace	17	Each	\$	\$
11	Four Panel corner brace	9	Each	\$	\$
12	New 12' steel farm gate with 2 brace panels	1	Each	\$	\$
13	Clean & repair cattleguard, supply and install wings and set new steel pipe entry gate provided by owner	1	Each	\$	\$
				<b>TOTAL</b>	<b>\$</b>

**BASE BID**

AND /100 DOLLARS ( \$ )

**ALTERNATE BID #1**

Item #	Description	Estimated Quantity	Unit Measure	Unit Price	Extension
AA1	Heavy two-rail fence	160	Lin.Ft.	\$	\$
				<b>TOTAL</b>	\$

**ALTERNATE BID #1**

\_\_\_\_\_ **AND** \_\_\_\_\_ /100 DOLLARS ( \$ \_\_\_\_\_ )

Contractor certifies that he is a duly and regularly licensed contractor registered with the Montana Department of Labor and Industry:

FIRM NAME: \_\_\_\_\_

TELEPHONE #: \_\_\_\_\_ FAX #: \_\_\_\_\_

BY: \_\_\_\_\_

SIGNATURE

REGISTRATION # : \_\_\_\_\_

BUSINESS ADDRESS: \_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

E-mail Address: \_\_\_\_\_

This bidder acknowledges receipt of the following addenda:

ADDENDUM NO. \_\_\_\_\_ DATED \_\_\_\_\_

ADDENDUM NO. \_\_\_\_\_ DATED \_\_\_\_\_

0ADDENDUM NO. \_\_\_\_\_ DATED \_\_\_\_\_