

Miles City Hatchery Pond Liner Repair FWP# 7113103 ADDENDUM NO. 2

TO: All Plan Holders on Record

FROM: Kenneth Phillips, P.E.

DATE: August 3, 2012

Acknowledge receipt of this addendum by inserting its number and date in the Proposal Form and on the Bid Envelope. Failure to do so may subject bidder to disqualification.

The following clarifications or modifications are to be incorporated into the bid documents for the Miles City Hatchery Pond Liner Repair.

- 1. Modification -Plan set Add sheet 1A/1 to the set of plans. This plan represents the work to be performed under the Additive Alternate No. 1.
- 2. Modification Sheet 3, add note; there is a two inch Sch 40 PVC airline that is adjacent to the kettle approximately two feet from top of liner that is not shown on the plans. Contractor has the option to neatly cut the pipe to below the working grade temporarily cap the pipe and then after grading extend pipe back out with a coupler. Contractor is to seal around pipe with a boot. See attached sheet marked Air line Details.
- 3. Modification Plan Set, Sheet 4, Notes for Pond 18, Add at the end of note A. Contractor shall provide salvaged liner to Owner.
- 4. Modification Bid Proposal Replace Proposal in original bid set with revised proposal included with this addendum. This proposal reflects adding Additive Alternate No. 1, Pond 31 repairs.
- 5. Modification Specification Section 02230, Part 1.3.C. Add note 2. Owner will engage testing firm to establish initial compaction testing to establish roller patterns for upper key and road compaction. CONTRACTOR is responsible to coordinate the testing. Owner may follow up with additional testing but if test fail contractor will be responsible for retesting until compaction is achieved.

- 6. Clarification Specification Section 02375, part 3.3, G Since the cellular confinement system is on a side slope, contractor and owner will discuss best practices to achieve compaction during initial compaction process to prevent damage to the system. Approved methods would be hoe bucket tamping or hoe mounted roller compactor or equal.
- 7. Clarification Specification Section 02276, Part 3.2.1 Add; all vegetative matter shall be removed from area of liner installation down to the roots and disposed of offsite.
- 8. Informational General Work Sequencing. Ponds 28, 27, 26 & 23 are suspected to be in somewhat saturated conditions as they are just being drained. It is highly recommended that the contractor uncover this work at the very start of project to allow soils to dry to a more suitable moisture condition.

All other contract requirements remain unchanged. End of addendum.

Attachments



PROPOSAL

Miles City Fish Hatchery Pond Liner Repair (Revised)

FWP# 7113103

Montana Fish, Wildlife & Parks Design and Construction Section PO Box 200701 600 North Park Avenue Helena, Montana 59620-0701

The undersigned, having familiarized himself with the conditions of the work and the contract documents as prepared <u>Design & Construction Section</u>; P.O. Box 200701 <u>Helena Montana 59620-0701</u>; <u>Phone 406 841-4006</u>, agrees to furnish all labor, materials, equipment, and services necessary to complete all general construction work, as bid herein, for a project entitled <u>Miles City Fish Hatchery Pond Liner Repairs</u> in accordance with the Contract Documents including all Addenda. The bidder agrees to perform all the work described below at the price shown as follows:


Base Bid:

| Item | Description | Estimated | Unit | Unit | Amount |
|------|--|-----------|---------|-------|--------|
| # | | Quantity | Measure | Price | |
| 1 | Mobilization/Demobilization | 1 | LS | LS | |
| 2 | Replace portion of liner pond 18 | 1256 | SY | | |
| 3 | Replace portion of liner pond 20 | 1233 | SY | | |
| 4 | Repair end slump on pond 20 | 1 | LS | LS | |
| 5 | Repair end slump and portion of liner on pond 23 | 1 | LS | LS | |
| 6 | Repair end slump pond and portion of liner pond 26 | 1 | LS | LS | |
| 7 | Repair end slump pond 27 | 1 | LS | LS | |
| 8 | Repair end slump pond 28 | 1 | LS | LS | |
| 9 | Misc liner tear repair | 100 | LF | | |
| | • | Total: \$ | | | |

| BASE | BID: | | | |
|-------------|---|------------------------|-----------------|------------|
| | AND /100 DC | OLLARS (\$ | | <u>)</u> . |
| ADDI | ΓΙ VE ALTERNATE #1 : | | | |
| Item # | Description | Estimated Quantity | Unit Measure | Unit Pri |
| 1 | Pond 31 replace end liner, repair slump on end and side as described on Addendum #2 | LS | LS | |
| | | Total: \$_ | | |
| | | | | |
| <u>ADDI</u> | ΓΙVE ALTERNATE # 1: | | | |
| | | | | |
| | ertifies that he is a duly and regularly lice na Department of Labor and Industry: | insed contractor regis | stered with th | e |
| FIRM | NAME: | | | - |
| TELE | PHONE #: F. | AX#: | | _ |
| BY: _ | | | | _ |
| REGIS | TRATION # : | | | |
| BUSIN | IESS ADDRESS: | | | |
| | | | | |
| E-MA | IL ADRESS: | | | |
| This b | idder acknowledges receipt of the following | lowing addenda: | | |
| ADDE | NDUM NO DATED | | | |
| ADDE | NDUM NO DATED | | | |

ADDENDUM NO. _____ DATED

Amount




Road & Pond Xsection (nts)

Notes this Sheet


A. Contractor to protect existing airline piping during bank stabilization. Contract may leave pipe as is or may cut and recouple pipe as described in addendum.

B. Contractor to install manufacturer's approved boot around piping after liner installation.



End View (nts)

| | DATE: | APPROVED BY: D | DATE: | APPROVED BY: | | DATE: | CHECKED BY: |
|-------------|-------|----------------|-------|--------------|--------|-------|-------------|
| ```` ``E | DATE: | APPROVED BY: D | DATE: | REVISED BY: | | DATE: | DRAWN BY: |
| S | | | | | 8/2012 | | K Phillips |





May 17, 2012

Mr. Kenneth Phillips, P.E. MT FWP Design & Construction PO Box 200701 Helena, MT 59620

RE: Miles City Hatchery
Pioneer Technical Services Project No. 16636

Dear Mr. Phillips,

On May 10th, a sample from the Miles City Hatchery Project was delivered to our ASTM/AASHTO accredited materials testing laboratory. The sample was referenced as 'Miles City Liner' and given Lab No. 12616. The testing request was:

- Standard Test Method for Particle-Size Analysis of Soils (ASTM D422);
- Liquid Limit, Plastic Limit and Plasticity Index of Soils (ASTM D4318);
- Proctor Moisture/Density Relationships (ASTM D698 Method A);
- Standard Test Method for pH of Soils (MT 232); and,
- Standard Test Method for Water-Soluble Sulfate in Soil (MT 232).

Table 1 – Corrosivity Testing Results

| Lab No. | pH (s.u.) | Soluble Sulfate (%) |
|---------|--------------|---------------------|
| 12616 | 8.4 | 0.1679 |

The grain size distribution chart, Atterberg limits chart, USDA textural classification chart and the Proctor curve are included with this report. We thank you for using Pioneer Technical Services for your geotechnical and materials testing requirements. If you have any questions regarding these results, please contact Todd Lorenzen or Paul Bushnell at (406) 443-6053.

Sincerely,

PIONEER TECHNICAL SERVICES, INC.

Todd Lorenzen, P.E.


Senior Geotechnical Engineer

Paul Bushnell

Materials Testing Supervisor

Fax (406) 782-5866

Fax (406) 545-4658



| GRAIN | <u>I SIZE</u> | - mm. |
|-------|---------------|-------|
| | | |

| 0/ .2" | % G | ravel | | % Sand | i e | % Fines | |
|--------|--------|-------|--------|--------|------|---------|------|
| % +3" | Coarse | Fine | Coarse | Medium | Fine | Silt | Clay |
| 0 | 4 | 4 | 1 | 1 | 6 | 41 | 43 |

| SIEVE | PERCENT | SPEC.* | PASS? |
|-------|---------|---------|--------|
| SIZE | FINER | PERCENT | (X=NO) |
| 3 | 100 | | |
| 2 | 99 | | |
| 1.5 | 98 | | |
| 1 | 96 | | |
| .75 | 96 | | |
| .5 | 94 | | |
| .375 | 93 | | |
| #4 | 92 | | |
| #10 | 91 | | |
| #20 | 90 | | |
| #40 | 90 | | |
| #60 | 89 | | |
| #100 | 88 | | |
| #200 | 84 | | |
| | | | |
| | | | |
| | | | |

| | Material Description | on |
|---|--|---|
| fat clay with sar | - | |
| | | |
| | Atterberg Limits | |
| PL= 16 | LL= 58 | PI= 42 |
| D ₉₀ = 0.4005 D ₅₀ = 0.0087 D ₁₀ = | Coefficients D85= 0.0851 D30= 0.0013 Cu= | D ₆₀ = 0.0195 D ₁₅ = C _c = |
| USCS= CH | Classification AASHT | O= A-7-6(36) |
| | Remarks | |
| | | |
| | | |

Source of Sample: Miles City Liner **Sample Number:** 12616


Client: MT FWP Design & Construction

Project: Miles City Hatchery

Project No: 16636 **Figure**

Date:

⁽no specification provided)



| | MATERIAL DESCRIPTION | LL | PL | PI | %<#40 | %<#200 | USCS |
|---|----------------------|----|----|----|-------|--------|------|
| • | fat clay with sand | 58 | 16 | 42 | 90 | 84 | СН |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| Ī | | | | | | | |

| Duningt No | 16626 | Cliente | MT FWD D | Damanka |
|-------------|-------|---------|------------------------------|-----------|
| Project No. | 10030 | Cilent: | MT FWP Design & Construction | ∥Remarks: |


Project: Miles City Hatchery

● Source of Sample: Miles City Liner Sample Number: 12616



Figure

USDA Soil Classification




| | | | | SOIL D | ATA | | |
|---|------------------|--------|-------|---------------|-------------------|----------------|-----------------|
| | Source | Sample | Depth | Percentages F | rom Material Pass | Classification | |
| | Source | No. | | Sand | Silt | Clay | Ciassification |
| • | Miles City Liner | 12616 | | 13 | 49 | 37 | Silty clay loam |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |



Client: MT FWP Design & Construction

Project: Miles City Hatchery

Project No.: 16636 Figure



Test specification: ASTM D 698-07 Method A Standard ASTM D 4718-87 Oversize Corr. Applied to Each Test Point

| Elev/ | Classif | ication | Nat. | Sp.G. | | PI | % > | % < |
|-------|---------|-----------|--------|-------|----|----|-----|--------|
| Depth | USCS | AASHTO | Moist. | Sp.G. | LL | PI | #4 | No.200 |
| | СН | A-7-6(36) | | | 58 | 42 | 8 | 84 |

| ROCK CORRECTED TEST RESULTS | UNCORRECTED | MATERIAL DESCRIPTION |
|---------------------------------|-------------|----------------------|
| Maximum dry density = 108.8 pcf | 105.6 pcf | fat clay with sand |
| Optimum moisture = 15.1 % | 16.3 % | |

Project: Miles City Hatchery

O Source of Sample: Miles City Liner Sample Number: 12616



Figure


Remarks:



Pond 31 side view



Pond 31 end view




Remove existing cobbles from on top of existing liner.

Salvage existing cobbles to owner. Stockpile adjacent to pond 30

Remove termination strips tieing liner to concrete kettle and liner from

Dig out vegetation dispose offsite. ends only and dispose this liner offsite.



Notes for pond 31

A. Remove sandbags (shown in photo) from slope and dispose. Cut Liner at 150 foot mark to allow for folding down.


Ē

as described on sheet 3. Fold down liner, regrade slope and install geoconfinement system

Transition slope to existing ground and then re-weld liner.

Rekey top of liner and restore roadway.

Refer to Section A-A and preperation notes. Remove liner entirely from end cutting at existing corners. Reinstall existing termination strips. Install new liner and weld to existing liner at corners Regrade and install Geoconfinement system as described Rekey top and bottom and restore roadway.



| DATE: | DATE: |
|--------------|--------------|
| APPROVED BY: | APPROVED BY: |
| DATE: | DATE: |
| | |

KPHILLIPS
DRAWN BY:

DATE:

REVISED BY:

8/2012

CHECKED BY:

DATE:

APPROVED BY:

