

ADDENDUM NO. 2

TO: ALL BIDDERS OF RECORD

PROJECT: NEWLAN CREEK RESERVOIR FAS SITE IMPROVEMENTS

FWP PROJECT #: 7113714

DATE: August 14, 2012

FROM: Bardell Mangum, FWP Project Manager

Acknowledge receipt of this addendum by inserting its number and date in the Proposal Form and on the Bid Envelope. Failure to do so may subject bidder to disqualification.

This Addendum forms a part of the Contract Documents. Clarification and/or modifications are as follows:

MODIFICATION:

1. Revise Section 02230.Part 1.3.A to read:

In-place field density tests for quality assurance are at **Owners** expense meeting AASHTO T238 (ASTM D2922) and AASHTO T239 (ASTM D3017), Nuclear Densometer Methods. Quality assurance field density testing frequency is once per compacted lift, or as directed by Engineer.

Retesting of failing areas is at the expense of the Contractor

CLARIFICATION:

1. Per the Instructions to Bidders section 4.12 fax modifications will be accepted. Refer to Instructions to Bidders in the project manual for further information.