

## ADDENDUM #1

### Missouri Headwaters State Park Site Improvements Project Project #7096417

August 24, 2012

Bidders for the above listed project are hereby notified that the following changes have been made to the bid documents:

1. *Replace **SPECIAL PROVISION #11, field density testing frequencies**, as follows:*

New Gravel Section and Gravel Section with Geogrid: 1 test per 100 sy of gravel, test each lift separately, (minimum of 1 test per isolated area of gravel placed).

3" Gravel Section and Variable Depth Gravel Section: 1 test per 500 sy of gravel, test each lift separately, (minimum of 1 test per isolated area of gravel placed).

2. *Modify **Drawing Sheet C4** as follows:*

*Replace note referring to Crushed Top Surfacing with the following: "Resurface Existing Gravel with 3" of Road Mix, See Typical Section."*

3. *Modify **Drawing Sheet C5** as follows:*

*Add Construction Note #13:*

Sod will be removed from all areas being topsoiled and graded when the depth of topsoil being placed exceeds 2".

4. *Modify **Drawing Sheet C5** as follows:*

*Add Construction Note #14:*

All new landscaping rocks within the base bid and each alternate shall match the existing rock within each site (Campground, Ling Rock Parking and Boat Launch Parking).

However the rock can vary between sites. For example, a Contractor has the option to remove all rock from the Boat Launch area to use as new rock in the Ling Rock Parking and Campground sites. The replacement rock in the Boat Launch area can then be completely different from the existing quarried limestone found throughout the project.

  
Jeffrey L. Larson, P.E.

PLEASE ACKNOWLEDGE RECEIPT OF THIS ADDENDUM ON THE DESIGNATED PLACE IN THE PROPOSAL **AND ON THE FACE OF THE ENVELOPE.**