ADDENDUM #1

Pee Wee Point Campground Improvements
near Decker, Montana
FWP #7096502

March 26, 2013

Bidders for the above listed project are hereby notified that the following changes have been made to the bid documents:

1. *Add the following to the* **NOTICE TO BIDDERS**, *located directly following the table of contents:*

   Do not mail bids using the post office box address; they will likely not be delivered in time. Use the physical address as follows:

   600 North Park Avenue
   Helena, Montana 59601

   Fed Ex or UPS delivery is strongly recommended.

2. *Add the following to* **INSTRUCTION TO BIDDERS, section 8.5** *as follows:*

   The State of Wyoming does enforce 5% bidding preference over non-resident Contractors. As a result, a 5% preference will be given to all Montana Contractors over Wyoming Contractors on this project. To determine the lowest responsible bidder all bids from Wyoming owned Contactors will be multiplied by 1.05 before they are compared to Montana resident Contractors.

3. *Replace the* **Proposal** *in its entirety including Bid Sheets. The new proposal is attached and* ***must be submitted as a part of Bid/Proposal****.*

4. *Replace* **Technical Specification 15/200 PLUMBING, Part 1, Section 3.B** *as follows:*

   All piping, fixtures, and accessories shall be installed in strict accordance with the laws and regulations of the State of Montana and Bighorn County.

5. *Add the following section to* **Technical Specification 15/200 PLUMBING** *as follows:*

The Contractor shall obtain a plumbing permit from the State of Montana and use a licensed plumber for all plumbing work inside the pump building and within 2-feet of the pump building foundation.

6. *Add to the* **Drawings, Sheet C7, Construction Notes** *the following note:*

   15. Due to its inferior bearing capacity, scoria rock will not be allowed for use in gravel products on this project.

7. *Add to the* **Drawings, Sheet C7, Construction Notes** *the following note:*

   16. Any damage to existing asphalt surfaces caused by the Contractor's construction activities shall be repaired by the Contractor to the satisfaction of the Owner.

8. *Add to the* **Drawings, Sheet C7, Construction Notes** *the following note:*

   17. Topsoil shall be striped, stockpiled, and replaced along electrical trench alignments. This does not apply to areas that are existing gravel or will be graveled as a part of this project.

9. *Add to the* **Special Provisions, Section 23.E.4, MEASUREMENT AND PAYMENT** *the following:*

   The work under the Demolition Bid item does <u>not</u> include any work associated existing gravel called out to be salvaged and stockpiled. This work is covered under a separate bid item.

10. *Add the following* **Special Provision**:

    27. Fish, Wildlife and Parks staff working at the Tongue River Reservoir State Park may be available to answer general questions only, however they have no authority to direct the work. Any questions about changes to the work, interpreting the contract documents or other questions that may impact the outcome of the project shall be directed to the Project Engineer. The Contractor shall be responsible for any additional work required to the correct issues that are the result of not obtaining approval for changes or interpretation of the contract documents through the Project Engineer.

11. *Add the following* **Special Provision***:*

28. Gravel products for use on the project may be hauled to the State Park and stockpiled in a location that can be directly accessed from the County Road prior to the Notice to Proceed, in the month of August. The location of the designated stock pile area will be south of the County Road at a location to be determined by FWP staff. Both the stockpile area and access roads shall be completely reclaimed as a part of project completion. Reclamation will include the removal of any excess gravel materials, fine grading and topsoil repair, and hydraulic seeding per the MPW specification 02/920.

Jeffrey L. Larson, P.E.

PLEASE ACKNOWLEDGE RECEIPT OF THIS ADDENDUM ON THE DESIGNATED PLACE IN THE BID FORM **AND ON THE FACE OF THE ENVELOPE**.

PROPOSAL

FWP# 7096502

Montana Fish, Wildlife & Parks
Design and Construction Section
PO Box 200701
600 North Park Avenue
Helena, Montana 59620-0701

The undersigned, having familiarized himself with the conditions of the work and the contract documents as prepared by **Larson Civil Engineering**; **28 Antler Avenue; Clancy, Montana 59634**, agrees to furnish all labor, materials, equipment, and services necessary to complete all general construction work, as bid herein, for a project entitled **Pee Wee Point Campground Improvements** in accordance with the Contract Documents including all Addenda. The bidder agrees to perform all the work described below at the price shown as follows:

Base Bid

Item #	Description	Estimated Quantity	Unit Measure	Unit Price	Amount
Pee Wee Point South:					
1	Mobilization, Insurance and Bonding	1	LS		
2	New Camp Pad Preparation	628	SY		
3	New Camp Pad Gravel Section	628	SY		
4	Remove and Replace Gravel Road Surfacing	1007	LF		
5	ADA Camp Pad	2	EA		
6	Handicapped Sign	2	EA		
7	New Concrete Curb Stop	4	EA		
8	Remove and Reset Concrete Curb Stop	2	EA		
9	Remove and Reset Picnic Table	2	EA		
10	Remove and Reset Fire Pit	2	EA		
11	Remove and Reset Sign	1	EA		
12	New Picnic Table	2	EA		
13	New ADA Fire Pit	2	EA		
14	Barrier Rocks	75	EA		

15	1” HDPE Water Piping	252	LF		
16	1” Curb Stop	2	EA		
17	1” Stop/Drain Valve	2	EA		
18	RV Water Hookup	2	EA		
19	Campground Water Hydrant	1	EA		
20	4” SCH 40 PVC Sewer Piping	256	LF		
21	Sewer Cleanout	6	EA		
22	Septic Tank/Dose Vault	1	EA		
23	Pumps and Controls	1	LS		
24	2” Schedule 40 PVC Force Main	511	LF		
25	Drainfield Chambers and Piping	228	LF		
26	RV Sewer Hookup	2	EA		
27	6” Conduit	302	LF		
28	Topsoil, Seed and Mulch	1	LS		
29	Elevated Pad for Electrical Service	2	EA		
30	Electrical Improvements	1	LS		
Pee Wee Point North:					
31	Mobilization, Insurance and Bonding	1	LS		
32	Site Excavation, Embankment and Grading	1	LS		
33	Demolition	1	LS		
34	Salvage and Stockpile Existing Gravel	600	CY		
35	Existing Road and Parking Area Crushed Top Surfacing	5022	SY		
36	New Camp Pad Gravel Section	4123	SY		
37	New Road and Parking Area Gravel Section	3500	SY		
38	Resurface Camping Area with Salvaged Crushed Top Surfacing	2533	SY		
39	New Gravel Path Section	83	SY		
40	ADA Camp Pad	2	EA		

41	New Concrete Curb Stop	29	EA		
42	Remove and Reset Concrete Curb Stop	12	EA		
43	Remove and Reset Picnic Table	14	EA		
44	Remove and Reset Fire Pit	14	EA		
45	Remove and Reset Sign	1	EA		
46	New Picnic Table	5	EA		
47	New Fire Pit	3	EA		
48	New ADA Fire Pit	2	EA		
49	Barrier Rocks	4	EA		
50	2000 Gallon FRP Cistern	1	LS		
51	Pump Building Modifications	1	LS		
52	1” HDPE Water Piping	307	LF		
53	1” Curb Stop	3	EA		
54	1” Stop/Drain Valve	3	EA		
55	RV Water Hookup	2	EA		
56	Campground Water Hydrant	1	EA		
57	4” SCH 40 PVC Sewer Piping	109	LF		
58	Sewer Cleanout	5	EA		
59	Septic Tank/Dose Vault	1	EA		
60	Pumps and Controls	1	LS		
61	2” Schedule 40 PVC Force Main	263	LF		
62	Drainfield Chambers and Piping	136	LF		
63	RV Sewer Hookup	2	EA		
64	Latrine	1	EA		
65	6” Conduit	187	LF		
66	15”x 21” Arch CMP with FETS	108	LF		
67	Relocate Kiosk, Pay Box and Signs	1	LS		
68	Handicapped Sign	2	EA		

69	Relocate Rectangular Wood Barrier Post	13	EA		
70	Import Topsoil	940	CY		
71	Topsoil, Seed and Mulch	1	LS		
72	Straw Wattle	1340	LF		
73	Electrical Improvements	1	LS		
				Total: $_____	

TOTAL BASE BID: _____

_____

_____ AND /100 DOLLARS ($_____).

And certifies that he is a duly and regularly licensed contractor registered with the Montana Department of Labor and Industry:

FIRM NAME: _____

TELEPHONE #: _____ FAX#: _____

BY: _____

REGISTRATION # : _____

BUSINESS ADDRESS: _____

_____

E-MAIL ADRESS: _____

This bidder acknowledges receipt of the following addenda:

ADDENDUM NO. _____ DATED

ADDENDUM NO. _____ DATED

ADDENDUM NO. _____ DATED