SPECIFICATIONS FOR WORK

SPECIAL PROVISIONS

Contents:

- 1. Project Description
- 2. Project Related Contracts
- 3. Site Inspection
- 4. Soils Information
- 5. Project Representative, Inspections, and Testing
- 6. Engineering Interpretations
- 7. Rejected Work
- 8. Utilities
- 9. Construction Safety
- 10. Construction Limits and Areas of Disturbance
- 11. Protection of Adjacent Improvements
- 12. Tree Protection and Preservation
- 13. Construction Surveys
- 14. Material Sources and Construction Water
- 15. Materials Salvage and Disposal
- 16. Stored Materials
- 17. Staging and Stockpiling Areas
- 18. Security
- 19. Cleanup
- 20. Access During Construction
- 21. Construction Traffic Control
- 22. Sanitary Facilities
- 23. Record Drawings
- 24. Proposal Item Descriptions and Estimated Quantities

1. PROJECT DESCRIPTION

The Project involves construction work associated with Bailey Reservoir Fishing Access Site (FAS) Site Improvements, Fish, Wildlife & Parks (FWP) project #7113720, located in Hill County, MT as identified in the project drawings. The project generally includes new parking area and access road construction involving clearing and grubbing, excavation/embankment construction, gravel base course and surfacing, conserved topsoil placement, boat ramp development, concrete parking pad and sidewalk, fence installation, and incidentals.

2. PROJECT RELATED CONTACTS

Project contacts are designated as follows:

Owner: Montana FWP Project Representative: Bardell Mangum, PLA

1420 E. Sixth Ave. PO Box 200701

Helena, MT 59620-0701 Helena, MT 59620-0701

406-841-4012 (wk) 406-431-4062 (cell) 406-841-4004 (fax)

FWP Project Manager

600 N. Park Ave.

3. SITE INSPECTION

All Bidders should satisfy themselves as to the construction conditions by personal examination of the site described in this document. Bidders are encouraged to make any investigation necessary to assess the nature of the construction and the difficulties to be encountered.

4. SOILS INFORMATION

Geotechnical investigation work has not been done for this Project. It is the responsibility of the Contractor to conduct all investigations and determine the soil type and digging conditions that may be encountered with this Project prior to bid preparation.

5. PROJECT REPRESENTATIVE, INSPECTIONS, AND TESTING

The Contractor's work will be periodically tested and observed to insure compliance with the Contract Documents. Complete payment will not be made until the Contractor has demonstrated that the work is complete and has been performed as required. If the Project Representative detects a discrepancy between the work and the requirements of the Contract Documents at any time, up to and including final inspection, such work will not be completely paid for until the Contractor has corrected the deficiency.

The Project Representative will periodically monitor the construction of work to determine if the work is being performed in accordance with the contract requirements. The Project Representative does not have the authority or means to control the Contractor's methods of construction. It is, therefore, the Contractor's responsibility to utilize all methods, equipment, manpower, and other

means necessary to assure that the work is installed in compliance with the Drawings and Specifications, and laws and regulations applicable to the work. Any discrepancies noted shall be brought to the Contractor's attention, who shall immediately correct the discrepancy. Failure of the Project Representative to detect a discrepancy will not relieve the Contractor of his ultimate responsibility to perform the work as required.

The Contractor shall inspect the work as it is being performed. Any deviation from the Contract requirements shall be immediately corrected. Prior to any scheduled observation by the Project Representative, the Contractor shall again inspect the work and certify to the Project Representative that he has inspected the work and it meets the requirements of the Contract Documents. All buried work items shall be inspected by the Project Representative prior to backfilling, or may not be considered for payment.

The work will be subject to review by the Project Representative. The results of all such observations shall be directed to the Contractor only through the Project Representative.

- 5.1 <u>Services Provided by the Contractor</u>. The Contractor shall provide the following services:
 - a. Any field surveys to establish locations, elevations, and alignments as stipulated on the Plans. FWP reserves the right to set preliminary construction staking for the project. The Contractor is responsible to notify FWP for any construction staking discrepancies.
 - b. Preparation and certification of all required shop drawings and submittals as described in the General Conditions.
 - c. All tests requiring the services of a laboratory to determine compliance with the Contract Documents shall be performed by an independent commercial testing laboratory acceptable to the Project Representative. The laboratory shall be staffed with experienced technicians properly equipped, and fully qualified to perform the tests in accordance with the specified standards.
 - f. The Contractor shall provide the Project Representative with a written schedule indicating dates for specific testing and inspection services to be performed. The schedule shall be updated as required to give the Project Representative at least one week's advance notice. The Contractor shall notify the Project Representative immediately of any change or shall be subject to pay Project Representativeing fees as herein defined.
- 5.2 <u>Services Provided by the Owner</u>. The Owner shall provide the following services at no cost to the Contractor except as required for retests as defined in the Contract Documents.
 - a. The Project Representative may check compaction of backfill and surfacing courses using Proctor information supplied by the Contractor. These tests are to determine if compaction requirements are being fulfilled in accordance with the Contract

Documents. It is ultimately the responsibility of the Contractor to insure that this level of compaction is constant and met in all locations.

6. ENGINEERING INTERPRETATIONS

Timely Engineering decisions on construction activities or results have an important bearing on the Contractor's schedule. When engineering interpretation affects a plan design or specifications change, it should be realized that more than 24 hours may be required to gain the necessary Owner participation in the decision process including time for formal change order preparation as required.

7. REJECTED WORK

Any defective work or nonconforming materials or equipment that may be discovered at any time prior to the expiration of the warranty period, shall be removed and replaced with work or materials which shall conform to the provisions of the Contract Documents. Any material condemned or rejected shall be removed at once from the project site. Failure on the part of the Project Representative to condemn or reject bad or inferior work or to note nonconforming materials or equipment on the Contractors submittals shall not be construed to imply acceptance of such work. The Owner shall reserve and retain all its rights and remedies at law against the Contractor and its Surety for correction of any and all latent defects discovered after the guarantee period.

The Project Representative will have the authority to reject work which does not conform to the Contract Documents and will provide the Owner with a list of defective work and nonconforming materials or equipment. The Owner will then promptly provide the Contractor with the list of defective work on nonconforming materials or equipment.

8. UTILITIES

The exact locations of existing underground utilities that may conflict with the work are not precisely known. It shall be the Contractor's responsibility to contact the owners of the respective utilities and arrange for field location services. **One Call Locators, 1-800-424-5555**

- 8.1 <u>Notification</u>. The Contractor shall contact, in writing, all public and private utility companies that may have utilities that may be encountered during excavation. The notification includes the following information:
 - a. The nature of the work that the Contractor will be performing.
 - b. The time, date and location that the Contractor will be performing work that may conflict with the utility.
 - c. The nature of work that the utility will be required to perform such as moving a power pole, supporting a pole or underground cable, etc.
 - d. Requests for field location and identification of utilities.

A copy of the letter of notification shall be provided to the Project Representative. During the course of construction, the Contractor shall keep the utility companies notified of any change in schedule or nature of work that differs from the original notification.

- 8.2 <u>Identification</u>. All utilities that may conflict with the work shall be the Contractor's responsibility to locate before any excavation is performed. Field markings provided by the utilities shall be preserved by the Contractor until actual excavation commences. All utility locations on the Drawings should be considered approximate and should be verified in the field by the Contractor. The Contractor shall also be responsible for locating all utilities that are not located on the Drawings.
- 8.3 <u>Removal or Relocation of Utilities</u>. All electric power, street lighting, gas, telephone, and television utilities that require relocation will be the responsibility of the utility owner. A request for extending the specified contract time will be considered if utility owners cause delays.
- 8.4 <u>Public Utilities</u>. Water, sewer, storm drainage, and other utilities owned and operated by the public entities shall, unless otherwise specifically requested by the utility owner, be removed, relocated, supported or adjusted as required by the Contractor at the Contractor's expense. All such work shall be in accordance with these Specifications, or the Owner's Standard Specifications or written instructions when the work involved is not covered by these Specifications.
- 8.5 Other Utilities. Utilities owned and operated by private individuals, railroads, school districts, associations, or other entities not covered in these Special Provisions shall, unless otherwise specifically requested by the utility owner, be removed, relocated, supported or adjusted as required by the Contractor at the Contractor's expense. All work shall be in accordance with the utility owner's directions, or by methods recognized as being the standard of the industry when directions are not given by the owner of the utility.
- 8.6 Damage to Utilities and Private Property. The Contractor shall protect all utilities and private property and shall be solely responsible for any damage resulting from his construction activities. The Contractor shall hold the Owner and Project Representative harmless from all actions resulting from his failure to properly protect utilities and private property. All damage to utilities shall be repaired at the Contractor's expense to the full satisfaction of the owner of the damaged utility or property. The Contractor shall provide the Owner with a letter from the owner of the damaged utility or property stating that it has been repaired to the utility owner's full satisfaction.
- 8.7 <u>Structures</u>. The Contractor shall exercise every precaution to prevent damage to existing buildings or structures in the vicinity of his work. In the event of such damages, he shall repair them to the satisfaction of the owner of the damaged

structure at no cost to the Owner.

- 8.8 Overhead Utilities. The Contractor shall use extreme caution to avoid a conflict, contact, or damage to overhead utilities, such as power lines, streetlights, telephone lines, television lines, poles, or other appurtenances during the course of construction of this project.
- 8.9 <u>Buried Gas Lines</u>. The Contractor shall provide some means of overhead support for buried gas lines exposed during trenching to prevent rupture in case of trench caving.
- 8.10 Pavement Removal. Where trench excavation or structure excavation requires the removal of curb and gutter, concrete sidewalks, or asphalt or concrete pavement, the pavement or concrete shall be cut in a straight line parallel to the edge of the excavation by use of a spade-bitted air hammer, concrete saw, colter wheel, or similar approved equipment to obtain a straight, square clean break. Pavement cuts shall be 2 feet wider than the actual trench opening.
- 8.11 Survey Markers and Monuments. The Contractor shall use every care and precaution to protect and not disturb any survey marker or monuments, such as those that might be located at lot or block corners, property pins, intersection of street monuments or addition line demarcation. Such protection includes markings with flagged high lath and close supervision. No monuments shall be disturbed without prior approval of the Project Representative. Any survey marker or monument disturbed by the Contractor during the construction of the project shall be replaced at no cost to the Owner by a licensed land surveyor.
- 8.12 <u>Temporary Utilities</u>. The Contractor shall provide all temporary electrical, lighting, telephone, heating, cooling, ventilating, water, sanitary, fire protection, and other utilities and services necessary for the performance of the work. All fees, charges, and other costs associated therewith shall be paid for by the Contractor.

The Contract Plans may show utility locations based on limited field observation and information provided to the Project Representative by others. **The Project Representative cannot guarantee their accuracy.** The Contractor shall immediately notify the Project Representative of any discrepancies with utility locations as shown on the Contract Drawings and/or their bury depths that may in any way affect the intent of construction as scoped in these specifications.

There will be no separate payment for exploratory excavation required to locate underground utilities.

9. CONSTRUCTION SAFETY

The Contractor shall be solely and completely responsible for conditions of the jobsite, including

Special Provisions Page 6 safety of all persons (including employees) and property during performance of the work. This requirement shall apply continuously and not be limited to normal working hours. Safety provisions shall conform to U.S. Department of Labor (OSHA), and all other applicable federal, state, county, and local laws, ordinances, codes, and regulations. Where any of these are in conflict, the more stringent requirement shall be followed. The Contractor's failure to thoroughly familiarize himself with the aforementioned safety provisions shall not relieve him from compliance with the obligations and penalties set forth therein.

10. CONSTRUCTION LIMITS AND AREAS OF DISTURBANCE

- 10.1 Construction Limits. Where construction easements or property lines, are not specifically called out on the Plan Drawings, limit the construction disturbance to 10 feet when measured from the edge of the slope stake grading, or to the adjacent property line, whichever is less. Disturbance and equipment access beyond this limit is not allowed without the written approval of both the Project Representative and the owner of the affected property. If so approved, disturbance beyond construction limits shall meet all requirements imposed by the landowner; this includes existing roads used and/or improved as well as the construction of new access roads. Special construction, reclamation, or post-construction road ripping or other closure provisions required by the landowner on access roads beyond the construction limits shall be performed by the Contractor at no additional cost to the Owner.
- 10.2 <u>Areas of Disturbances</u>. Approved areas of disturbance are those areas disturbed by construction activities within the construction limits and along designated or approved access routes. Such areas may require reclamation and revegetation operations, including grading to the original contours, top soiling with salvaged or imported topsoil, seeding, fertilizing, and mulching as specified herein. Other areas that are disturbed by the Contractor's activities outside of the limits noted above will be considered as site damage or unapproved areas of disturbance subject to Repair and Replacement Quality as specified in the General Conditions. This includes areas selected by the Contractor outside the defined construction limits for mobilization, offices, equipment, or material storage.

11. PROTECTION OF ADJACENT IMPROVEMENTS

Retain and protect all adjacent improvements not called for removal on the drawings. Restore all damaged items to pre-existing condition.

12. TREE PROTECTION AND PRESERVATION

The Contractor and the Owner shall individually inspect all trees within the project construction limits prior to construction. The Owner shall determine which trees are to be removed and which trees are to be preserved. Construction of the grading, utilities and various roadway facilities must not, in the opinion of the Project Representative, significantly damage the trees root system or hinder it's chances for survival. Reasonable variations from the plans, as determined by the Project Representative, may be employed to ensure the survival of trees.

13. CONSTRUCTION SURVEYS

The Contractor will be responsible for all layout and construction staking utilizing the Project Representative's existing control and coordinate data for the project. Dimensions and elevations indicated in layout of work shall be verified by the Contractor. Discrepancies between Drawings, Specifications, and existing conditions shall be referred to the Project Representative for adjustment before work is performed. The Project Representative may set location and grade stakes prior to construction; however, it is ultimately the responsibility of the Contractor to check and verify all construction staking for the project.

Existing survey control (horizontal and vertical) has been set for use in the design and ultimately the construction of these improvements. A listing of the coordinates and vertical elevation for each of these control points may be included in the project drawings.

The Contractor will be responsible for preserving and protecting the survey control until proper referencing by the Contractor has been completed. Any survey control obliterated, removed, or otherwise lost during construction will be replaced at the Contractor's expense.

Contractor shall be aware of property pins and survey monuments. Damage to these pins will require replacement of such by a registered land surveyor at no cost to the owner.

The Contractor is responsible for the location and elevation of all the construction contemplated by the Contract Documents.

The Contractor shall provide construction staking from the Owner's layouts and the control points. Contractor's construction staking includes at a minimum:

- 1. Slope stakes located at critical points as determined by the Project Representative.
- 2. Blue tops every longitudinally and transversely for subgrade and crushed base to verify finish grading of course.
- 3. Location and grade stakes for drainage features and retaining walls.
- 4. Location stakes for roadside safety items, permanent and temporary traffic control, and misc. items as determined by the Project Representative.

Prior to commencing work, the Contractor shall carefully compare and check all drawings, each with the other that in any way affects the location or elevation of the work to be executed by him, and should any discrepancy be found, he shall immediately report the same to the Project Representative for verification and adjustment. Any duplication of work made necessary by failure or neglect on his part to comply with this function shall be done at his sole expense.

Original field notes, computations and other records take by the Contractor for the purpose of quantity and progress surveys shall be furnished promptly to the Project Representative and shall be used to the extent necessary in determining the proper amount of payment due to the Contractor.

Special Provisions Page 8 These field notes, computations and other records shall be neat and orderly. Field notes shall be complete and in a standard format approved by the Project Representative. Unless waived in each specific case, all quantity surveys made by the Contractor shall be made under the direct supervision of the Project Representative.

14. MATERIAL SOURCES AND CONSTRUCTION WATER

The Contractor shall be responsible for locating all necessary material sources, including aggregates, earthen borrow and water necessary to complete the work. The Contractor shall be responsible for meeting all transportation and environmental regulations as well as paying any royalties. The Contractor shall provide the Project Representative with written approvals of landowners from whom materials are to be obtained prior to approval.

The Contractor may use materials from any source, providing the materials have been tested through representative samples and will meet the Specifications.

Water for compaction efforts shall be supplied by the Contractor.

15. MATERIALS SALVAGE AND DISPOSAL

If the Owner requests to salvage material removed from the project, notify the Owner within 24 hours prior to delivery at a specific location approved by the Owner.

Haul and waste all excavated material to a legal site and obey all state, county, and local disposal restrictions and regulations.

16. STORED MATERIALS

Contractor shall use an approved storage area for materials. Materials and/or equipment purchased by the Contractor may be paid for on a monthly basis providing invoices for said materials and equipment are presented to the Project Representative, and such materials have been approved through the submittal process are stored and insured.

17. STAGING AND STOCKPILING AREA

Contractor shall use staging and stockpiling sites for temporary traffic control devices and equipment as approved by the Owner. Contract drawings may show approved staging and stockpiling locations. Notify Owner within 24 hours for approval of staging and stockpiling sites not shown on the contract drawings.

18. SECURITY

Special Provisions Page 9 The Contractor shall provide all security measures necessary to assure the protection of equipment, materials in storage, completed work, and the project in general.

19. CLEANUP

Cleanup for each item of work shall be <u>fully</u> completed and accepted before the item is considered final. If the Contractor fails to perform cleanup within a timely manner the Owner reserves the right to shut down construction activities.

20. ACCESS DURING CONSTRUCTION

Provide access to all public and private roadways and approaches along the project throughout the construction period.

21. CONSTRUCTION TRAFFIC CONTROL

The contractor is responsible for providing safe construction and work zones within the project limits by implementing the rules, regulations, and practices of the <u>Manual on Uniform Traffic Control</u> Devices, current edition.

22. SANITARY FACILITIES

On-site toilet facilities for employees of Contractor and Subcontractors shall be provided and maintained in a sanitary condition.

23. RECORD DRAWINGS

The Contractor's Superintendent shall maintain at the project site, a "Record Set of Drawings" showing field changes, as-built elevations, unusual conditions encountered during construction, and such other data as required to provide the Owner with an accurate "as constructed" set of record drawings. The Contractor shall furnish the "Record Set" to the Project Representative following the Final Inspection of the Project.

The Contractor's final estimate and final payment will not be processed until the "Record Set" of drawings are received and approved by the Project Representative.

24. PROPOSAL ITEM DESCRIPTIONS AND ESTIMATED QUANTITIES

BASE BID

- 1. Mobilization/Demobilization/Erosion Control BMP's:
 - * Description: This bid item includes all equipment, labor and associated work necessary for the transporting of equipment to and from the work site to construct the project to the lines and grades as noted in the specifications and drawings. This bid item also includes the installation, maintenance, and post-construction removal of temporary and/or permanent erosion control devices and Best

Management Practices (BMP's) as designated in the specifications and project drawings or as directed by the Project Representative.

- * Estimated Quantity:
- 100 linear feet (Erosion control straw wattle)
- 1500 square feet (Erosion control blanket)

2. Floating Turbidity Curtain:

- * <u>Description</u>: This bid item includes all equipment, labor and associated work for the installation and placement of a floating turbidity curtain to the lines and grades as noted in the specifications and drawings.
- * Estimated Quantity:
 - 90 linear feet

3. Excavation and Embankment:

- * <u>Description</u>: This bid item includes all equipment, labor and associated work for the excavation, transporting on-site or imported excavation for embankment-in-place, compacting, and disposal of excess material encountered within the construction limits necessary to construct the road, ramp and parking area to the lines and grades as noted in the specifications and drawings.
- * Estimated Quantity:
 - Excavation 630 cubic yards
 - Embankment 0 cubic yards (Imported)

4. 3" Minus Crushed Subbase Course, 6" Depth:

- * <u>Description</u>: This bid item includes all equipment, labor and associated work for the placement, grading, and compaction of crushed base course material to the lines and grades as noted in the specifications and drawings.
- * Estimated Quantity:
 - 1,419 cubic yards
 - 9,228 square yards

5. 3/4" Minus Crushed Base Course, 4" Depth:

- * <u>Description</u>: This bid item includes all equipment, labor and associated work for the placement, grading, and compaction of crushed base course material to the lines and grades as noted in the specifications and drawings.
- * Estimated Quantity:
 - 338 cubic yards (includes gravel pathway and picnic shelter leveling)
 - 3,072 square yards (includes gravel pathway and picnic shelter leveling)

6. 18" HDPE Culvert w/ Galvanized FETS:

- * <u>Description</u>: This bid item includes all equipment, labor and associated work for the installation and placement of 18" HDPE culvert w/ galvanized Flared End Terminal Sections (FETS) at each end to the lines and grades as noted in the specifications and drawings.
- * Estimated Quantity:

- 50 linear feet
- 4 FETS

7. <u>Cast-in-Place Concrete ADA Parking Slab</u>:

- * <u>Description</u>: This bid item includes all equipment, labor and associated work for the installation and placement of cast-in-place concrete ADA parking slab to the lines and grades as noted in the specifications and drawings.
- * Estimated Quantity:
 - 486 square feet (structural concrete)
 - 6 cubic yards (gravel leveling course)

8. Cast-in-Place Concrete Sidewalk:

- * <u>Description</u>: This bid item includes all equipment, labor and associated work for the installation and placement of cast-in-place concrete sidewalk to the lines and grades as noted in the specifications and drawings.
- * Estimated Quantity:
 - 61 square feet (structural concrete)
 - 1 cubic yard (gravel leveling course)

9. Cast-in-Place Concrete Boat Ramp:

- * <u>Description</u>: This bid item includes all equipment, labor and associated work for the installation and placement of a cast-in-place concrete ramp to the lines and grades as noted in the specifications and drawings.
- * Estimated Quantity:
 - 630 square feet (6" concrete mat)
 - 13 cubic yards (gravel leveling course)

10. Push-in-Slab Concrete Boat Ramp:

- * <u>Description</u>: This bid item includes all equipment, labor and associated work for the installation and placement of a push-in slab concrete ramp to the lines and grades as noted in the specifications and drawings.
- * Estimated Quantity:
 - 210 square feet (6" concrete mat)
 - 5 cubic yards (gravel leveling course)
 - 7 cubic yards (riprap)
 - 3 W6 x 20, 16' Length Steel I-Beams

11. Concrete Curb Stops:

- * <u>Description</u>: This bid item includes all equipment, labor and associated work for the installation and placement of pre-cast concrete curb stops to the lines and grades as noted in the specifications and drawings.
- * Estimated Quantity:
 - 10 each
- 12. <u>Single Post Sign Installation (FWP supplied sign panels)</u>:

- * Description: This bid item includes all equipment, labor and associated work for the installation and placement of sign posts and panels to the lines and grades as noted in the specifications and drawings. FWP will supply all sign panels for the project.
- * Estimated Quantity:
 - 2 each

13. Double Post Sign Installation (FWP supplied sign panels):

- * <u>Description</u>: This bid item includes all equipment, labor and associated work for the installation and placement of sign posts and panels to the lines and grades as noted in the specifications and drawings. FWP will supply all sign panels for the project.
- * Estimated Quantity:
 - 2 each

14. <u>Barrier Post Installation (Owner Furnished)</u>:

- * <u>Description</u>: This bid item includes all equipment, labor and associated work for the transportation, installation and placement of repurposed guardrail posts (Owner furnished) and steel cable (Contractor furnished) for use as barriers to the lines and grades as noted in the specifications and drawings or as directed by the Project Manager.
- * Estimated Quantity:
 - Barrier Posts 38 each
 - Steel Cable 325 linear feet

15. Revegetation:

- * <u>Description</u>: This bid item includes all equipment, labor and associated work for revegetation including conserved topsoil placement, fertilizing, seeding, and mulching as noted in the specifications and drawings.
- * Estimated Quantity:
 - 0.5 Acres

16. Vault Latrine, Concrete Ramp and Memorial Sculpture Removal:

* <u>Description</u>: This bid item includes all equipment, labor and associated work for removal and disposal of existing vault latrine, concrete boat ramp and memorial sculpture including excavation, preparation, backfilling, and grading as noted in the specifications and drawings.

17. Latrine Installation (Owner Furnished):

* <u>Description</u>: This bid item includes all equipment, labor and associated work for latrine installation (Owner furnished) including excavation, preparation, backfilling, and grading as noted in the specifications and drawings.

SPECIFICATIONS FOR WORK

TECHNICAL PROVISIONS

Incorporation of Montana Public Works Technical Specifications.

The Technical Specifications as found in Montana Public Works Standard Specifications (MPWSS), Sixth Edition, April 2010 and/or current Addendums or Revisions; are hereby incorporated by reference and made a part of this Contract:

Incorporation of Montana Fish, Wildlife & Parks Technical Specifications and Modifications to MPW Technical Specifications.

In addition to the MPWSS Technical Specifications are the following Montana Fish, Wildlife & Parks Technical Specifications (modifications to MPWSS Technical Specifications).

Summary of Work
Field Engineering
Mobilization/Demobilization
Final Cleanup
Erosion and Sediment Control
Floating Turbidity Curtain
Removal of Existing Pavement, Concrete Curb, Sidewalk, Driveway
and/or Structures
Street Excavation, Backfill, and Compaction
Sub Base Course
Crushed Base Course
Gravel Leveling Course
Riprap
Revegetation
Signing
Structural Concrete
Push-In-Slab Concrete Boat Ramp
Curb Stops
Wood Post and Steel Cable Barriers
Pre-Cast Concrete Vault Latrine

SUMMARY OF WORK

All applicable portions of this specification section in the MPWSS shall apply with the following additions, deletions and/or modifications.

PART 1 GENERAL

1.5 OWNER-FURNISHED ITEMS

Add the following:

B. Owner furnished items include treated wood barrier posts. Contractor is responsible for transporting materials to the project location. Posts are located at the Montana Fish Wildlife and Parks Region 4 Headquarters, 4600 Giant Springs Road, Great Falls, MT. Contact Ray Swartz, Region 4 Regional Fishing Access Site Maintenance Supervisor, at (406) 454-5856 prior to removing materials.

FIELD ENGINEERING

All applicable portions of this specification section in the MPWSS shall apply with the following additions, deletions and/or modifications.

PART 3 EXECUTION

1.1 CONSTRUCTION SURVEY

- A. Perform all survey, staking, recording of data, and calculations as necessary to construct the project to the lines and grades as noted in the drawings and specifications. Reset stakes as many times as necessary to construct the work.
- B. Set slope stakes and grade stakes at 50' intervals on tangent sections and at 25' on horizontal curves. Set slope stakes at PC and PT locations as well as the begin and end of project stationing. Limit grade stake tolerances to +/-0.1'.

PART 4 MEASUREMENT AND PAYMENT

Add the following:

A. Construction Surveying is incidental to the work and no separate payment is made for this item.

MOBILIZATION/DEMOBILIZATION

Added Section.

PART 1 GENERAL

1.1 DESCRIPTION

- A. This item shall consist of the prepatory work and operations necessary performed by the Contractor for the movement of personnel, equipment, supplies, and incidentals to and from the work site. The work includes those actions necessary for obtaining necessary permits required for mobilization; for the establishment of all offices and facilities necessary to work on the project; for premiums on contract bonds; for insurance for the contract; and for other work on the various items on the project site. Mobilization costs for subcontracted work shall be considered to be included.
- B. Contractor's cost for administration, bonding, insurance, and site documents shall be included in mobilization and shall not be paid as a separate item.
- C. All equipment moved to the project sites shall be in good mechanical condition and free of fuel, oil, lubrication, or other fuel leaks. The Contractor shall immediately remove any equipment potentially or actually discharging environmentally damaging fluids.
- D. All equipment moved to the project sites shall be thoroughly cleaned before it is brought to the sites to prevent the introduction of weed seeds. Equipment removed fro the sites may not be returned to the sites again until it is thoroughly cleaned again.

PART 2 PRODUCTS – NOT USED

PART 3 EXECUTION – NOT USED

PART 4 MEASUREMENT AND PAYMENT

4.1 MEASUREMENT

A. There will be no direct measurement of this item.

4.2 PAYMENT

B. Partial payments for mobilization/demobilization will be made based on the lump sum bid price as follows:

- ➤ 25% of the amount bid for mobilization/demobilization when the Contractor has moved on-site and begun construction activities.
- > 50% of the amount bid for mobilization/demobilization when 25% of the contract amount (exclusive mobilization/demobilization) has been completed.
- > 75% of the amount bid for mobilization/demobilization when 50% of the contract amount (exclusive mobilization/demobilization) has been completed.
- ➤ 100% of the amount bid for mobilization/demobilization when 75% of the contract amount (exclusive mobilization/demobilization) has been completed.

FINAL CLEANUP

Added Section.

PART 1 GENERAL

1.1 DESCRIPTION

A. This work consists of final cleanup of the project site prior to final acceptance.

PART 2 PRODUCTS – NOT USED

PART 3 EXECUTION

3.1 CONTRACTOR RESPONSIBILITES

The contractor shall be responsible for final clean up at the end of the project to a level satisfactory to the owner. All construction debris, no mater how small, shall be collected and removed from the site. All wheel ruts shall be filled in and be leveled to match the adjacent grade and material. Re-seeding or re-sodding, or other re-surfacing may be necessary to repair any construction related impacts or damage.

All survey markings, stakes, temporary paint marks, flagging and other devices shall be removed regardless of who installed them. All excess pavement, concrete, gravel, soil, or other construction materials not intended for permanent use shall be removed.

All final slopes shall be dressed manually to remove woody debris, accumulated trash and oversized material. Any new slope or topsoil surfaces shall be hand raked to provide a uniform appearance. The contractor shall dress all gravel, pavement and concrete edges to eliminate abrupt edges and provide a smooth transition. All construction related temporary sediment control devices shall be removed as soon as practical.

PART 4 MEASUREMENT AND PAYMENT

4.1 PAYMENT

Unless specifically noted otherwise, all final cleanup work shall be incidental to other work items in the contract and no separate payment shall be made.

EROSION AND SEDIMENT CONTROL

Added Section.

PART 1 GENERAL

1.1 DESCRIPTION

A. This work consists of furnishing, constructing, and maintaining permanent and temporary erosion control and sediment control measures as shown on the project drawings and/or project related construction permits.

PART 2 PRODUCTS

2.1 GENERAL

A. Temporary and erosion control products utilized include but are not limited to backfill material; berms; brush barriers; erosion control blankets, bales, wattles, logs, rolls; erosion control culvert pipe; detention basins; fertilizer; geotextile; mulch; plastic lining; riprap; sandbags; seed; silt fence; and water.

2.2 EROSION CONTROL WATTLES

A. Where designated, provide a sediment retention product made from straw and coconut fiber reinforced with a 100% bio-degradable netting. Use wood stakes to secure sediment retention product in place, spacing per the manufacturer's recommendations. An acceptable product is *Sediment Stop*, manufactured by *North American Green*, or approved equal.

2.2 EROSION CONTROL BLANKETS

A. Where designated, provide a sediment retention product made from straw and coconut fiber reinforced with a 100% bio-degradable netting. Use wood stakes to secure sediment retention product in place, spacing per the manufacturer's recommendations. An acceptable product is *BioNet® S150BNTM*, manufactured by *North American Green*, or approved equal.

PART 3 EXECUTION

3.1 INSTALLATION

A. Provide permanent and temporary erosion control measures to minimize erosion and sedimentation during and after construction according to the contract erosion control plan, environmental permits, and as directed by the Project Representative. These erosion control measures shall be designed, implemented, and maintained by the

- Contractor in accordance with Best Management Practices (BMPs) to control erosion and sediment release from the work site.
- B. Install permanent and temporary erosion control measures according to the Storm Water Pollution Prevention Plan (SWPPP), if applicable, approved construction permits, and erosion control drawings.
- C. When erosion control measures are not functioning as intended, immediately take corrective action.

PART 4 MEASUREMENT AND PAYMENT

4.1 MEASUREMENT AND PAYMENT

A. All items in this section are incidental to the work and no separate payment is made for these items.

FLOATING TURBIDITY CURTAIN

Added Section.

PART 1 GENERAL

1.1 DESCRIPTION

A. This work consists of furnishing and installing a floating turbidity curtain to control sedimentation and suspended solids during underwater construction methods.

PART 2 PRODUCTS

2.1 GENERAL

- A. Provide a turbidity curtain with a geotextile material curtain, floatation boom, and anchorage system.
- B. Provide a woven geotextile material as approved for turbidity containment by manufacture's recommendations.
- C. An acceptable floating turbidity curtain product is *Layfield Turbidity Curtains*, or approved equal. www.layfield.com, (800) 796-6868

PART 3 EXECUTION

3.1 INSTALLATION

- A. Install turbidity curtain parallel to the shoreline around the construction area of disturbance. Turbidity curtain installation is required prior to any and all work below the ordinary high water mark.
- B. Extend the turbidity curtain to the lake bottom at all installation locations.
- C. Provide flexible flotation buoys for the top of the turbidity curtain.
- D. Provide an anchorage system consisting of load lines attached to the bottom of the turbidity curtain. Place anchors every 50' connected to the top of the floatation buoy.
- E. Inspect the turbidity curtain daily to ensure sedimentation is controlled and proper function of the erosion control BMP. Immediately correct turbidity curtain deficiencies before continuing with work. If turbidity curtain deficiencies are not

- corrected, the Contractor may be in violation with approved construction permits and may be issued a stop work order by the Project Represent
- F. Maintain turbidity curtain throughout all work activities until removal approval by the Project Representative. Allow sediment to settle or disperse for 12 hours after construction disturbance prior to removal.

PART 4 MEASUREMENT AND PAYMENT

4.1 GENERAL

A. Turbidity curtain will be measured and paid by the lump sum (LPSM) including all labor, equipment, materials, and incidentals required for the completion of the work.

REMOVAL OF EXISTING PAVEMENET, CONCRETE CURB, SIDEWALK, DRIVEWAY AND/OR STRUCTURES

All applicable portions of this specification section in the MPWSS shall apply with the following additions, deletions and/or modifications.

PART 3 EXECUTION

3.1 GENERAL

Add the following:

- D. Remove existing wooden latrine structure as shown in the project drawings or as directed by the Engineer. Remove vault to 6" below finished grade and backfill with on-site excavation and/or excess topsoil material to finish grade. Compact backfill by tamping with hand tools and/or mechanical equipment.
 - Dispose of all removed existing structural materials off the project site and obey all state, county, and local disposal restrictions and regulations.
- E. Remove and salvage to Owner existing steel memorial structure as shown in the project drawings or as directed by the Engineer. Transport off-site to be by Owner. Notify project representative 48 hours prior to removal. Remove steel and concrete base to 6" minimum below finished grade and backfill with on-site excavation and/or excess topsoil material to finish grade. Compact backfill by tamping with hand tools and/or mechanical equipment.

Dispose of all removed existing structural materials off the project site and obey all state, county, and local disposal restrictions and regulations.

PART 4 MEASUREMENT AND PAYMENT

Add the following:

- 4.5 VAULT LATRINE, CONCRETE RAMP AND MEMORIAL SCULPTURE REMOVAL
 - A. Payment will be measured and paid by the lump sum (LPSM) including complete compensation for all labor, equipment, materials and incidentals required for the completion of the work.

STREET EXCAVATION, BACKFILL AND COMPACTION

All applicable portions of this specification section in the MPWSS shall apply with the following additions, deletions and/or modifications.

PART 1 GENERAL

1.3 DENSITY CONTROL TESTING

A. FIELD DENSITY TESTING

Delete this section and add the following:

In-place field density tests for quality assurance are at Contractors expense meeting AASHTO T238 (ASTM D2922) and AASHTO T239 (ASTM D3017), Nuclear Densometer Methods. Quality assurance field density testing frequency is once per compacted lift, or as directed by Engineer.

Retesting of failing areas is at the expense of the Contractor.

B. LABORATORY MAXIMUM DENSITY and OPTIMUM MOISTURE

Delete this section and add the following:

Quality assurance tests will be made by the Contractors independent testing laboratory for each on-site natural soil or each source of off-site material, including borrow material, to determine the laboratory maximum density values and optimum compaction moisture content under AASHTO T99 or ASTM D698.

PART 3 EXECUTION

3.1 CLEARING AND GRUBBING

Add the following:

Obtain necessary burning permits if cleared and grubbed material is burned on site. All stumps within construction limits shall be grubbed under this contract.

3.4 EXCAVATION

Add the following:

Sheeting, Shoring, and Bracing: Except where trench banks are cut back on a stable slope, provide and maintain all sheeting, shoring, and bracing necessary to protect workers, and to protect adjoining grades and structures from caving, sliding, erosion or other damage in accordance with Occupational Safety and Health Standards (29 CFR Part 1926 – Construction Standards for Excavations), the Site Specific Health and Safety Plan, and other applicable codes and governing authorities.

PART 4 MEASUREMENT AND PAYMENT

4.1 METHOD OF MEASUREMENT AND PAYMENT

Delete this section and add the following:

A. CLEARING AND GRUBBING

1. Clearing and grubbing will not be measured for payment and is considered incidental to other work items in this Contract.

B. EXCAVATION AND EMBANKMENT

1. Excavation and embankment will be measured and paid by the lump sum (LPSM).

SUB BASE COURSE

All applicable portions of this specification section in the MPWSS shall apply with the following additions, deletions and/or modifications.

PART 1: GENERAL

1.3 DENSITY CONTROL TESTING

A. Field Density Testing

Delete this section and add the following:

- 1. Meet the quality control and quality assurance testing requirements in section 01400, Contractor Quality Control and Owner Quality Assurance.
- 2. In-place field density tests for quality assurance are at Contractor expense meeting AASHTO T191 (ASTM D1556) Sand Cone Method or AASHTO T310 (ASTM D6938) Nuclear Densometer Method. Quality assurance field density testing frequency will be performed as follows:

Compaction Testing	Location*	Frequency
Subgrade	None**	None**
Sub Base Course	Access Road (centerline)	4
	North Shore Road	2
	Filipowicz Memorial Parking	1
Crushed Base Course	Dam Crest Road (centerline)	1
	Ramp Area Parking	1

^{*} Station/Offset determined by Engineer

3. Retesting of failing areas is at Contractor expense.

^{**}Proof roll subgrade only for observation by Engineer prior to base course placement.

CRUSHED BASE COURSE

All applicable portions of this specification section in the MPWSS shall apply with the following additions, deletions and/or modifications.

PART 1: GENERAL

1.3 DENSITY CONTROL TESTING

A. Field Density Testing

Delete this section and add the following:

- 1. Meet the quality control and quality assurance testing requirements in section 01400, Contractor Quality Control and Owner Quality Assurance.
- 2. In-place field density tests for quality assurance are at Contractor expense meeting AASHTO T191 (ASTM D1556) Sand Cone Method or AASHTO T310 (ASTM D6938) Nuclear Densometer Method. Quality assurance field density testing frequency will be performed as follows:

Compaction Testing	Location*	Frequency
Subgrade	None**	None**
Sub Base Course	Access Road (centerline)	4
	North Shore Road	2
	Filipowicz Memorial Parking	1
Crushed Base Course	Dam Crest Road (centerline)	1
	Ramp Area Parking	1

^{*} Station/Offset determined by Engineer

3. Retesting of failing areas is at Contractor expense.

^{**}Proof roll subgrade only for observation by Engineer prior to base course placement.

GRAVEL LEVELING COURSE

Added Subsection.

PART 1 GENERAL

1.1 DESCRIPTION

B. This work also consists of placing clean, screened gap-graded gravel leveling course beneath push-in concrete boat ramp slab.

PART 2 PRODUCTS

2.1 GRAVEL LEVELING COURSE GRADATION

A. Furnish gravel leveling course that is crushed aggregate as shown in Table 1. The gravel leveling course must not contain other deleterious material, such as shale, alkali, mica, or soft flaky particles.

Table 1. Gravel Leveling Course Gradation

Sieve Size	Percent Passing
1"	100
3/4"	90-100
3/8"	20-55
No. 4	0-10
No. 8	0-5

PART 3 EXECUTION

3.1 PLACEMENT AND SPREADING

- A. Place material to specified depth as indicated on the project drawings. Deposit and spread the material in a uniform layer and screed to make a uniform surface at the specified boat ramp grade as indicated on the project drawings.
- B. Perform compaction efforts by mechanical tamping as approved by the Project Representative.

PART 4 MEASUREMENT AND PAYMENT

4.1 GRAVEL LEVELING COURSE

A. Gravel Leveling Course will not be measured for payment and is considered incidental to other work items in this Contract.

RIPRAP

Added Section.

PART 1 GENERAL

1.1 DESCRIPTION

A. This work consists of conserving and/or furnishing, placing, and finishing riprap rock placement at designated areas on the project drawings or as directed by the Project Representative.

PART 2 PRODUCTS

2.1 RIPRAP GRADATION

A. Furnish hard, durable, angular rock that is resistant to weathering and water action and free of organic or other unsuitable material. Do not use shale, rock with shale seams, or other fissle or fissured rock that may break into smaller pieces in the process of handling and placing. Incorporate the following gradation for riprap installations as shown in Table 1:

Table 1. Riprap Gradation

Percent of Rock by Mass	Approximate Cubic Dimension (inches)
20	20 to 24
40	15 to 20
30	6 to 15
10	0 to 6

PART 3 EXECUTION

3.1 GENERAL

- A. Place riprap to form a well-graded mass to its full thickness in operation to avoid displacing the underlying geotextile or other material. Do not place riprap material by methods that cause segregation or damage to the prepared surface. Place or rearrange individual rocks by mechanical or hand methods to obtain a dense uniform blanket with a reasonably smooth surface.
- B. Install conserved and/or imported riprap according to the project drawings or as directed by the Project Representative.

PART 4 MEASUREMENT AND PAYMENT

4.1 GENERAL

A. Riprap placement will not be measured for payment and is considered incidental to other work items in this Contract.

REVEGETATION

All applicable portions of this specification section in the MPWSS shall apply with the following additions, deletions and/or modifications.

PART 1 GENERAL

1.1 DESCRIPTION

Add following:

This work also includes conserving, placing, and finishing topsoil placement at designated areas on the project drawings or as directed by the Engineer.

PART 2 PRODUCTS

2.1 SEED

Add the following:

Utilize the following seed mix for all areas to be seeded.

Seed Name	% Pure Live Seed	Lbs. Per Acre
Western Wheatgrass	30	*
Bluebunch Wheatgrass	20	*
Hard Fescue	20	*
Slender Wheatgrass	15	*
Green Needlegrass	15	*

^{*} Drilled Rate = 25 lbs/acre, Broadcast and Hydroseed Rate = 50 lbs/acre

2.2 TOPSOIL

Add the following:

Utilize all salvaged topsoil conserved from clearing and grubbing operations to cover excavation and embankment slopes prior to fertilizing, seeding, or mulching.

2.4 FERTILIZER

Delete this Section.

PART 4 MEASUREMENT AND PAYMENT

4.1 GENERAL

Delete this section and add the following:

- A. Revegetation will be measured and paid by the lump sum (LPSM) including all labor, equipment, materials and incidentals required for the completion of the work.
- B. Placing conserved topsoil will not be measured for payment and is considered incidental to other work items in this Contract.

SIGNING

Added Section.

PART 1 GENERAL

1.1 DESCRIPTION

A. This work consists of furnishing and placement and/or removal and reset of signs and sign posts at designated areas on the project drawings or as directed by the Engineer. This work also consists of the mounting and complete installation of FWP supplied signing at designated areas on the project drawings or as directed by the Engineer.

PART 2 PRODUCTS

2.1 WOOD POSTS

A. Furnish posts from dry no. 1 grade Douglas fir, southern or Ponderosa pine, hemlock, spruce, or western larch conforming to AASHTO M 168. Treat the posts with water-borne preservative ACA, ACZA, or CCA according to AWPA Standard C14 except the minimum preservative retention is 0.40 pounds per cubic foot.

2.2 HARDWARE

A. Furnish galvanized steel or aluminum alloy material for lag screws, washers, clip angles, wood screws, shear plates, U-bolts, clamps, bolts, nuts, and other fasteners.

PART 3 EXECUTION

3.1 GENERAL

A. Sign locations may be changed to fit field conditions as approved by the Engineer. Determine sign support lengths measured from the top of the sign to bottom of the footing. Backfill signs supports and post by tamping with hand tools and/or mechanical equipment. Install sign supports according to the project drawings or as directed by the Engineer.

PART 4 MEASUREMENT AND PAYMENT

4.1 PAYMENT

A. Sign post and panel installation (FWP supplied sign panels) will be measured and paid for by the each (EACH).

STRUCTURAL CONCRETE

All applicable portions of this specification section in the MPWSS shall apply with the following additions, deletions and/or modifications.

PART 1 GENERAL

1.1 DESCRIPTION

Add the following:

B. FWP will provide a grooving tool(s) for producing a grooved finish on the concrete surface. The tool(s) provided by FWP shall be returned cleaned. The finishing tool surfaces shall be free of hardened concrete and in good condition. A cleaning cost of \$250.00 will be retained if the tool(s) are returned not cleaned or poorly cleaned. Additional costs for repair or replacement of damaged tools may also be retained.

PART 2 PRODUCT

2.1 CLASSIFICATION

Add the following to Subsection A.1:

1. Use M-4000 concrete for all concrete.

PART 3 EXECUTION

3.4 PLACING CONCRETE

A. Delete the last sentence.

Add the following:

B. Provide written and/or verbal communication notice to the Project Manager three (3) working days, excluding Saturday and Sunday, prior to any project concrete pour, regardless of pour quantity. For clarification, all written communication notices have to received in the FWP Design and Construction Office per this requirement. Failure to provide notification will result in a deduct of pour quantity from the associated bid item. Lump sum bid items will be deducted based on the concrete placed percentage.

3.4A CONCRETE V-GROOVE FINISHING

A. Required Accuracy

- 1. The Contractor shall construct all specified work as shown on the project drawings within the specified tolerances, shown in Table 1. The following are reasonable tolerances that allow for a maximum specified deviation which may occur in the field during construction. Deviations beyond any values listed below may result in reduction in payment, or rejection, in part due to poor aesthetics, loss of functionality, or does not meet desired design criteria.
- 2. If the Contractor fails to meet specified tolerances, that portion of the work area, as specified below, may be reduced in payment or rejected, removed and replaced in accordance with General Conditions, ARTICLE 12 UNCOVERING AND CORRECTION OF WORK.

Table 1. V-Groove Finish Tolerances

Criteria	Tolerance
V-Groove Angle Orientation	10 degrees
V-Groove Depth	0.25"
V-Groove Connections (End to	0.5"
End Alignment)	

B. Concrete V-Groove Finish

- 1. Provide a v-groove finish on all ramp surfaces as shown in the project drawings or directed by the Project Representative. Provide adequate laborers to begin concrete v-groove finish during concrete placement. Timing of v-grooving finish is critical.
- 2. Factors that may influence the v-groove finish and concrete performance include air content, water content, add-mixtures and strength. Some Contractors delay starting the finish, or may have a tendency to add water to the concrete surface, in order to achieve a "perfect" ramp finish. This must be avoided, as significant amounts of water in the surface layer will result in weak strength of the v-grooves, which at best contain less quantity of large aggreagate due to the nature of the finish process. Refer to the Technical Specifications for other influential factors including, but not limited to: mix design, mixing and placement time, weather, correct placement of rebar, and correct thickness of ramp.

C. V-Groove Rating Score

1. The following rating score shall be used to determine allowable tolerances for all v-groove concrete finishes. The Project Representative shall make the final determination on any deficient or unacceptable area, determine the rating score, and conduct measurements as deemed necessary for evaluation. Three

(3) v-grooving evaluation criteria will be considered in determining the rating score including: appearance; angle orientation; and depth. A criteria rating score will be assigned for each based on the V-Groove Rating System, shown in Table 2. An overall, or final, rating score is made by averaging the three criteria rating scores. Finalrating scores will be rounded to the nearest whole number.

Rating Score

- 1 Unacceptable, Contractor shall replace that portion of the ramp.
- 2 Poor, Reduction of 50% in payment for that portion of the ramp, or Contractor shall replace that portion of the ramp.
- 3 Fair, Minimum acceptance range.
- 4 Good.
- 5 Excellent, Letter of commendation to Contractor.

Table 2. V-Groove Evaluation Rating System

Evaluation Criteria	Criteria	Area	Score
V-Groove Appearance	Shallow, Uneven, Rough, Torn	40+ sf	-5
(top or bottom of groove)	Rounded, Flat, Semi-Rough	80+ sf	0
	Sharp, Crisp, Clean, Smooth		5
V-Groove Angle Orientation	0-5 or >56 degrees	40+ sf	1
	6-10 or 51-55 degrees	40+ sf	2
	11-15 or 46-50 degrees	80+ sf	3
	16-24 or 41-34 degrees	80+ sf	4
	25-35 degrees		5
V-Groove Depth	0.00" to 0.20"	40+ sf	1
	0.21" to 0.40"	40+ sf	2
	0.41" to 0.50"	80+ sf	3
	0.51" to 0.60"	80+ sf	4
	0.61" to 0.75"		5

3.4 TESTING

A. 3. Compression Tests

Add the following to subsection a.:

Mold a minimum of three (3) field cure cylinders (6-inch diameter), for each day of concrete placement. Follow requirements for field curing and strength testing found in this section.

PART 4 MEASUREMENT AND PAYMENT

4.1 GENERAL

Delete this section and add the following:

- A. Cast-in-Place Concrete Boat Ramp will be measured and paid for by the square foot (SF) in place including all labor, equipment, materials, and incidentals required for the completion of the work.
- B. Cast-in-Place Concrete ADA Parking Slab will be measured and paid for by the square foot (SF) in place including all labor, equipment, materials, and incidental required for the completion of the work.
- C. Cast-in-Place Concrete Sidewalk will be measured and paid for by the square foot (SF) in place including all labor, equipment, materials, and incidental required for the completion of the work.

PUSH-IN-SLAB CONCRETE BOAT RAMP

Added Section.

PART 1 GENERAL

1.1 DESCRIPTION

A. This work consists of furnishing and installing a submerged concrete push-in-slab boat ramp surface.

PART 2 PRODUCTS

2.1 GENERAL

- A. Refer to Section 03310 for structural concrete materials and ramp surface finish.
- B. Refer to Section 03210 for reinforcing steel materials.
- C. Rail System
 - 1. Furnish new material consisting of W6x20 steel beams or approved equal to support push-in slab during installation.

PART 3 EXECUTION

3.1 INSTALLATION

A. Casting

- 1. Push-in-slab shall be placed on approximately a matching grade to that of the final grade of the ramp. Imported embankment material my be necessary to construct the push-in slab at the matching ramp grade, as well as provide a cushion for mechanical pushing equipment.
- 2. Push-in-slabs shall be placed on a layer of compacted aggregate (4 inch minimum thickness) and shall be allowed to cure for a minimum of 14 days prior to movement. Provide a smooth surface to reduce friction forces during push-in slab movement (i.e. plastic sheeting).
- 3. Push-in-slabs shall be built to a size that can be handled by the Contractor's equipment, preferably one slab per site. Each slab shall be constructed to a length that can be controlled and placed in the desired position.

4. Remove all imported embankment from the ramp surface after the push-in slab is in place. Cleanliness of the ramp surface must be approved by the Project Representative, prior to final acceptance.

B. Rail System

- 1. Rails shall be placed at the grade specified in the plans. Space steel beams longitudinally as shown on the project drawings. Beams shall have adequate cross braces to insure beams remain parallel as slab is pushed over beams.
- 2. Six inches (6") of clean, screened crushed 34" gravel leveling course shall be placed around the railing system and screeded to top of rail system prior to push-in slab installation. See Section 02235.

PART 4 MEASUREMENT AND PAYMENT

4.1 GENERAL

A. Push-In-Slab Concrete Boat Ramp including excavation, preparation, rail system installation will be measured and paid for by the square foot (SF) in place including all labor, equipment, materials, and incidental required for the completion of the work.

CURB STOPS

Added Section.

PART 1 GENERAL

1.1 DESCRIPTION

A. This work consists of furnishing and placement of curb stops at designated areas on the project drawings or as directed by the Project Representative. This work also includes removing and resetting existing curb stops as directed by the Project Representative.

PART 2 PRODUCTS

1.1 CURB STOPS

A. Furnish pre-fabricated concrete curb stops (84" min. length) as designated on the project drawings or as directed by the Project Representative.

PART 3 EXECUTION

3.1 GENERAL

A. Install curb stops at locations as designated on the project drawings or as directed by the Project Representative. Furnish and place No. 5 rebar measuring 3 feet in length to hold curb stops in place. Drive rebar flush with the top of each curb stop.

PART 4 MEASUREMENT AND PAYMENT

4.1 PAYMENT

A. Curb stops will be measured and paid for by the each (EACH).

WOOD POST AND STEEL CABLE BARRIERS

Added Section.

PART 1 GENERAL

1.1 DESCRIPTION

A. This work consists of transporting and installing repurposed treated wood guardrail posts (provided by owner) and steel barrier cable and incidentals to the lines and grades as designated in the project drawings and specifications or as directed by the Project Representative.

PART 2 PRODUCTS

2.1 REPURPOSED WOOD POSTS

- A. Repurposed treated wood barrier posts to be furnished by owner. Contractor is responsible for transportation to project site from Montana Fish, Wildlife and Parks (FWP) Region 4 Headquarters, 4600 Giant Springs Road, Great Falls, MT 59405. Contact Ray Swartz, FWP Region 4 FAS Maintenance Supervisor at (406) 454-5856 at a minimum of 72 hours prior to anticipated pickup time to coordinate loading.
- B. Posts which exhibit signs of excessive decay or cracking shall be brought to the attention of the Project Representative and shall not be installed.

2.2 CABLE

A. Furnish 5/16" galvanized aircraft cable.

2.2 HARDWARE

A. Furnish (2) galvanized cable clamps at each end of cable.

PART 3 EXECUTION

3.1 INSTALLATION

- **A.** Embed all wood posts at a spacing of 10' O.C. and at a minimum depth of 2 feet. Assure posts are plumb and are of equal height (approximately 3'). Assure pre-drilled holes are aligned properly for continuous cable installation.
- **B.** Secure galvanized aircraft cable to wood posts through pre-drilled holes. Ensure cable is tight and with minimum deflection but not so tight as to pull posts from plumb orientation. Secure each end with loop around last post and (2) minimum galvanized cable clamps.

PART 4 MEASUREMENT AND PAYMENT

4.1 MEASUREMENT AND PAYMENT

A. Wood posts w/galvanized aircraft cable will be measured and paid by the number of posts placed (EACH) including all labor, equipment, materials and incidentals required for the completion of the work.

PRE-CAST CONCRETE VAULT LATRINE

Added Section.

PART 1 GENERAL

1.1 DESCRIPTION

A. This work consists of site preparation (excavation and leveling), backfilling and compaction, and landscaping for Fishing Access Site (FAS) pre-cast concrete vault latrines at designated areas on the project drawings or as directed by the Project Representative.

PART 2 PRODUCTS

2.1 MATERIALS

- A. Pre-Cast Concrete Vault Latrine.
 - 1. Montana Department of Fish, Wildlife and Parks will supply the latrine through Flathead Concrete, Kalispell, MT. The contractor shall coordinate the delivery with Flathead Concrete. The contractor is advised to contact **Flathead Concrete (406) 752-4259,** as soon as a schedule is established to insure delivery in a timely manner.
- B. Gravel Bedding for Latrine.
 - 1. See Gravel Leveling Course, Subsection 02236

PART 3 EXECUTION

3.1 GENERAL

Each latrine location shall be staked in the field by the Project Representative. Refer to the project drawings for pre-cast concrete vault toilet installation locations, details, and dimensions.

3.2 EXCAVATION

Excavate for the installation of the toilet vault to a depth that will allow the structure site to be free draining after installation is completed. Salvage conserved topsoil.

3.3 FINISH FLOOR ELEVATION

Finish floor elevation shall be a minimum of 4 to 6 inches above natural grade measured at the front entrance.

3.4 COMPACTION OF EARTH UNDER TOILET VAULTS

Prior to installation of the toilet building, compact the natural ground underlying the vault with a minimum of three passes with a whacker-type mechanical tamper or equivalent approved by the Project Representative.

3.5 INSTALLATION OF GRAVEL BEDDING UNDER TOILET VAULTS

Install 12 inches of compacted gravel bedding material for leveling course. Compact leveling course with one pass with a whacker-type mechanical tamper or equivalent approved by the Project Representative. Grade level course so there will be no high spots in middle of vault bottom. Finished leveling course shall not vary more than 0.01 foot for the four corners of the vault.

3.6 BACKFILL AND DISPOSAL OF DEBRIS

Backfill around structures, including under exterior slab. Use excavated material for backfill except that rocks larger than six inches in maximum dimension shall not be placed within six inches of exterior of vault walls. Stumps, roots, brush, and other vegetation shall be removed from the site and disposed of in a legal manner by the contractor.

3.7 COMPACTION UNDER ENTRANCE SLAB

Fill under entrance slab shall have excavated material placed in six-inch loose lifts, and compacted with a minimum of two passes with a whacker-type mechanical compactor or equivalent approved by the Project Representative.

3.8 FILL AROUND LATRINES AND SLAB

Spread excess excavated material from vault around structure. Final backfill surface shall be flush with the top of the front slab. Allowance shall be made for the depth of the topsoil. Grade backfill away from structure at maximum slope of five percent unless otherwise noted in the plans or specs or approved by the Project Representative.

3.9 LANDSCAPING

Spread conserved topsoil as final 2" layer after rough grading is completed. Areas disturbed by excavation, backfilling, and stockpiling of excavated materials shall be hand raked to removed exposed rocks over one-inch in maximum dimension. Oversize rocks removed from the surface shall be disposed of off-site or with the approval of the Project Representative used as fill in other items in the contract.

3.10 HIDDEN GROUND CONDITION

If the contractor uncovers bedrock, boulders too big to remove, ground water or other unexpected conditions, he shall immediately contact the Project Representative for instructions.

3.11 TEMPORARY FENCING

- A. All excavations left open overnight shall be fenced with polyethylene plastic safety fence, orange color, 48" high, and 4" maximum mesh openings. Fencing shall be secured to steel posts on the side away from the excavation unless otherwise approved in advance by the Project Representative.
 - 1. The bottom of the fence shall generally follow the contour of the ground.
 - 2. Maximum spacing of the steel posts shall be ten feet.
- B. No excavations will be left open more than seven days unless otherwise approved by the Project Representative.

PART 4 MEASUREMENT AND PAYMENT

4.1 GENERAL

A. FAS Latrine Installations will be measured and paid for by the Lump Sum (LPSM) including all labor, equipment, materials, and incidentals required for the completion of the work.