ADDENDUM NO. 1

TO: ALL BIDDERS OF RECORD

PROJECT: SITE IMPROVEMENTS

RIVER JUNCTION FISHING ACCESS SITE

FWP#: 7113704

DATE: April 3, 2014

FROM: Mark McNearney, Project Manager



Acknowledge receipt of this addendum by inserting its number and date in the Proposal Form and on the Bid Envelope. Failure to do so may subject bidder to disqualification.

This Addendum forms a part of the Contract Documents. Clarification and/or Modifications are as follows:

- 1) <u>Clarification</u> Reminder To Contractors: All Unit Prices must be filled in on the Bid Proposal/Form for a valid bid (18-2-303 MCA).
- 1) Modification **Revised Bid Opening Date**:

The Bid Opening date has been extended 3 weeks. Sealed Bids will be received up to and including <u>3:00 PM</u> on <u>May 1, 2014</u>, and will be publicly opened and read aloud in the offices of the Design and Construction Bureau, 1522 9th Avenue, P.O Box 200701, Helena, MT 59620-0701.

2) <u>Modification</u> – Specifications for Work, Technical Provisions:

Add the following Section:

SECTION 02241

BARRIER ROCKS

PART 1 GENERAL

- 1.1 DESCRIPTION
- A. This work consists of furnishing and placing barrier rocks at designated areas on the project drawings or as directed by the Engineer.

PART 2 PRODUCTS

2.1 GENERAL

- A. Furnish hard, durable, angular barrier rock that is resistant to weathering and water action and free of organic or other unsuitable material. Do not use shale, rock with shale seams, or other fissured rock that may break into smaller pieces in the process of handling and placing.
- B. Furnish barrier rocks that approximately measure 8 cubic feet (2.5-3.5 feet in nominal diameter as measured on the long axis). Embed barrier rocks 1/3 of the diameter below finished or existing grade. Backfill around embedded barrier rocks by tamping with hand tools and/or mechanical equipment. Space barrier rocks at 5 feet clearance as measured from edge to edge.

PART 3 EXECUTION

- 3.1 GENERAL
- A. Install barrier rocks according to the project drawings or as directed by the Engineer.

PART 4 MEASUREMENT AND PAYMENT

- 4.1 PAYMENT
- A. Barrier rock placement will be measured and paid for by the each (EACH).

END OF SECTION 02241