Montana Fish, Wildlife & Parks

SPECIFICATIONS FOR WORK SPECIAL PROVISIONS

Contents:

- 1. Project Description
- 2. Project Related Contracts
- 3. Site Inspection
- 4. Soils Information
- 5. Project Representative, Inspections, and Testing
- 6. Engineering Interpretations
- 7. Rejected Work
- 8. Utilities
- 9. Construction Safety
- 10. Construction Limits and Areas of Disturbance
- 11. Decontaminate Construction Equipment
- 12. Tree Protection and Preservation
- 13. Construction Surveys
- 14. Material Sources and Construction Water
- 15. Materials Salvage and Disposal
- 16. Stored Materials
- 17. Staging and Stockpiling Areas
- 18. Security
- 19. Cleanup
- 20. Access During Construction
- 21. Construction Traffic Control
- 22. Sanitary Facilities
- 23. Contract Closeout
- 24. Measurement and Payment

1. PROJECT DESCRIPTION

The Project involves construction work associated with:

West Shore State Park Entrance Station Fish, Wildlife & Parks (FWP) project # 7136405 Located in Lake County, MT

The project generally consists of; road widening, excavation and embankment, construction of a "stick framed" entrance station, electrical and telephone line installation, asphalt paving, and concrete bollards.

2. PROJECT RELATED CONTACTS

Project contacts are designated as follows:

Owner: Montana FWP

1420 E. Sixth Ave. PO Box 200701

Helena, MT 59620-0701

FWP Project Representative: Kelly Williams, P.E.

FWP Project Manager

1522 9th Avenue Helena, MT 59620 406-841-4002 (wk) 406-438-2737 (cell) 406-841-4004 (fax)

3. SITE INSPECTION

All Bidders should satisfy themselves as to the construction conditions by personal examination of the site described in this document. Bidders are encouraged to make any investigations necessary to assess the nature of the construction and the difficulties to be encountered, see General Conditions, Article 3.

4. SOILS INFORMATION

Geotechnical investigation work has not been done for this Project. It is the responsibility of the Bidders to conduct all investigations and determine the soil type and digging conditions that may be encountered with this Project prior to bid preparation, see General Conditions, Article 3.

5. PROJECT REPRESENTATIVE, INSPECTIONS, AND TESTING

The Contractor's work will be periodically tested and observed to insure compliance with

the Contract Documents. Complete payment will not be made until the Contractor has demonstrated that the work is complete and has been performed as required. If the Project Representative detects a discrepancy between the work and the requirements of the Contract Documents at any time, up to and including final inspection, such work will not be completely paid for until the Contractor has corrected the deficiency, see General Conditions, Article 9.

The Project Representative will periodically monitor the construction of work to determine if the work is being performed in accordance with the contract requirements. The Project Representative does not have the authority or means to control the Contractor's methods of construction. It is, therefore, the Contractor's responsibility to utilize all methods, equipment, personnel, and other means necessary to assure that the work is installed in compliance with the Drawings and Specifications, and laws and regulations applicable to the work. Any discrepancies noted shall be brought to the Contractor's attention, who shall immediately correct the discrepancy. Failure of the Project Representative to detect a discrepancy will not relieve the Contractor of his ultimate responsibility to perform the work as required, see General Conditions, Article 3.

The Contractor shall inspect the work as it is being performed. Any deviation from the Contract requirements shall be immediately corrected. Prior to any scheduled observation by the Project Representative, the Contractor shall again inspect the work and certify to the Project Representative that he has inspected the work and it meets the requirements of the Contract Documents. The Project Representative may require uncovering of work to verify the work was installed according to the contract documents, see General Conditions, Article 12.

The work will be subject to review by the Project Representative. The results of all such observations, and all contract administration, shall be directed to the Contractor only through the Project Representative.

- 5.1 <u>Services Required by the Contractor</u>. The Contractor shall provide the following services:
 - a. Any field surveys to establish locations, elevations, and alignments as stipulated on the Contract Documents. FWP reserves the right to set preliminary construction staking for the project. The Contractor is responsible to notify FWP for any construction staking discrepancies.
 - b. Preparation and certification of all required shop drawings and submittals as described in the General Conditions, Article 3.
 - c. All testing requiring the services of a laboratory to determine compliance with the Contract Documents shall be performed by an independent commercial testing laboratory acceptable to the Project Representative. The laboratory shall be staffed with experienced technicians properly equipped, and fully qualified to perform the tests in accordance with the specified standards.

- d. Preparation and submittal of a construction schedule, including submittals, see General Conditions, Article 3. The schedule shall be updated as required, as defined in the Contract Documents.
- e. All Quality Control testing as required by the Contractor's internal policies.
- f. All Quality Assurance testing and/or re-testing as stated in the Contract Documents, see General Conditions, Article 13.
- 5.2 <u>Services Provided by the Owner</u>. The Owner shall provide the following services at no cost to the Contractor except as required for retests as defined in the Contract Documents.
 - a. The Project Representative may check compaction of backfill and surfacing courses using laboratory testing submittal information supplied by the Contractor. These tests are to determine if compaction requirements are being fulfilled in accordance with the Contract Documents. It is ultimately the responsibility of the Contractor to insure that this level of compaction is constant and met in all locations.
 - b. Any additional Quality Assurance testing deemed appropriate by the Owner, at the Owner's expense.

6. ENGINEERING INTERPRETATIONS

Timely Engineering decisions on construction activities or results have an important bearing on the Contractor's schedule. When engineering interpretation affects a plan design or specifications change, it should be realized that more than 24 hours may be required to gain the necessary Owner participation in the decision process including time for formal work directive, or change order preparation as required.

7. REJECTED WORK

Any defective work or nonconforming materials or equipment that may be discovered at any time prior to the expiration of the warranty period, shall be removed and replaced with work or materials conforming to the provisions of the Contract Documents, see General Conditions, Article 12. Failure on the part of the Project Representative to condemn or reject bad or inferior work, or to note nonconforming materials or equipment on the Contractors submittals, shall not be construed to imply acceptance of such work. The Owner shall reserve and retain all its rights and remedies at law against the Contractor and its Surety for correction of any and all latent defects discovered after the guarantee period (MCA 27-2-208).

Only the Project Representative will have the authority to reject work which does not conform to the Contract Documents.

8. UTILITIES

The exact locations of existing utilities that may conflict with the work are not precisely known. It shall be the Contractor's responsibility to contact the owners of the respective utilities and arrange for field location services. **One Call Locators, 1-800-424-5555**

The Contract Documents may show utility locations based on limited field observation and information provided to the Project Representative by others. **The Project Representative cannot guarantee their accuracy.** The Contractor shall immediately notify the Project Representative of any discrepancies with utility locations as shown on the Contract Drawings and/or their bury depths that may in any way affect the intent of construction as scoped in these specifications.

There will be no separate payment for exploratory excavation required to locate underground utilities.

- 8.1 <u>Notification</u>. The Contractor shall contact, in writing, all public and private utility companies that may have utilities encountered during excavation. The notification includes the following information:
 - a. The nature of the work that the Contractor will be performing.
 - b. The time, date and location that the Contractor will be performing work that may conflict with the utility.
 - c. The nature of work that the utility will be required to perform such as moving a power pole, supporting a pole or underground cable, etc.
 - d. Requests for field location and identification of utilities.

A copy of the letter of notification shall be provided to the Project Representative. During the course of construction, the Contractor shall keep the utility companies notified of any change in schedule, or nature of work that differs from the original notification.

8.2 <u>Identification</u>. All utilities that may conflict with the work shall be the Contractor's responsibility to locate before any excavation is performed. Field markings provided by the utility companies shall be preserved by the Contractor until actual excavation commences. All utility locations on the Drawings should be considered approximate and should be verified in the field by the Contractor. The Contractor shall also be responsible for locating all utilities that are not located on the Drawings.

Utilities are depicted on the Contract Documents in accordance with their achieved "Quality Levels," as defined in the American Society of Civil Engineer's Document, ASCE 38, "Standard Guideline for the Collection and Depiction of Existing Subsurface Utility Data." Reliance upon these data for risk management purposes during bidding does not relieve the Contractor, or Utility Owner from following all applicable utility damage prevention statutes, policies, and/or procedures during construction. It is important that the

Contractor investigates and understands the scope of work between the project Owner and Engineer regarding scope of limits of the utility investigations leading to these utility depictions. Definitions of Quality Levels are described as follows:

- a. "QUALITY LEVEL A" (QLA): LOCATING THROUGH EXCAVATION. QLA data are highly accurate and are obtained by surveying an exposed utility. As such, both horizontal and vertical data are recorded. Survey accuracies are typically set at 15mm (1/2inch) vertically, and to project survey standards horizontally (typically the same as for topography features), although these survey accuracies and precisions are generally left to the owner to specify in a scope of work. In addition to the applicable standard of care and any other additional standards imposed by commercial indemnity clauses, the accuracy of these location data is also typically guaranteed. Other data typically characterized include material type, surface elevation, utility size/capacity, outside dimensions, and configurations, soil type, and utility condition.
- b. "QUALITY LEVEL B" (QLB): DESIGNATING. QLB information is obtained through the application of appropriate surface geophysical methods to identify the existence and approximate horizontal location of utilities (a utility's "designation") within the project limits, followed by survey, mapping, and professional review of that designation. Underground utilities are identified by interpretation of received signals generated either actively or passively, and through correlating these received signals with visible objects (QLC) and record data (QLD) to determine function. Designated utilities that can't be identified are labeled as "unknowns." Although approximate has no accuracy associated with it, generally the locations are within inches rather than feet. The more utility congested the area or the deeper the utilities, the less likely it is that the designations will achieve that accuracy. These designations are then surveyed to project accuracies and precisions, typically third-order accuracy similar to other topography features. Note that surveying existing one-call marks does not lead to QLB data, since the genesis of the marks was not under the direct responsible charge of the professional certifying the QLB depictions, and one-call generally does not address unknown utilities, privately owned utilities, utilities without records, abandoned utilities, and so on. Nor does the professional have knowledge of the field technician's qualifications, training, and level of effort.
- c. "QUALITY LEVEL C" (QLC): SURFACE VISIBLE FEATURE SURVEY. QLC builds upon the QLD information by adding an independent detailed topography site survey for surface-visible appurtenances of subsurface utilities including but not limited to fire hydrants, valves, risers, and manholes. Professional judgment is

used to correlate the QLD data to the surveyed features, thus increasing the reliability of both utility location and existence. It is a function of the professional to determine when records and features do not agree and resolve discrepancies. This may be accomplished by depiction of a utility line at quality level D, effectively bypassing or disregarding (but still depicting) a surveyed structure of unknown origin. Additional resolution may result from consultation with utility owners.

- d. "QUALITY LEVEL D" (QLD): EXISTING RECORDS RESEARCH. QLD is the most basic level of information. Information is obtained from the review and documentation of existing utility records, verbal accounts, and/or one-call markings (to determine the existence of major active utilities and their approximate locations).
- 8.3 Removal or Relocation of Utilities. All electric power, street lighting, gas, telephone, and television utilities that require relocation will be the responsibility of the utility owner. A request for extending the specified contract time will be considered if utility owners cause delays.
- 8.4 <u>Public Utilities</u>. Water, sewer, storm drainage, and other utilities owned and operated by the public entities shall, unless otherwise specifically requested by the utility owner, be removed, relocated, supported or adjusted as required by the Contractor at the Contractor's expense. All such work shall be in accordance with these Contract Documents, or the Owner's Standard Specifications or written instructions when the work involved is not covered by these Specifications.
- 8.5 Other Utilities. Utilities owned and operated by private individuals, railroads, school districts, associations, or other entities not covered in these Special Provisions shall, unless otherwise specifically requested by the utility owner, be removed, relocated, supported or adjusted as required by the Contractor at the Contractor's expense. All work shall be in accordance with the utility owner's directions, or by methods recognized as being the standard of the industry when directions are not given by the owner of the utility.
- 8.6 <u>Damage to Utilities and Private Property</u>. The Contractor shall protect all utilities and private property and shall be solely responsible for any damage resulting from his construction activities. The Contractor shall hold the Owner and Project Representative harmless from all actions resulting from his failure to properly protect utilities and private property. All damage to utilities shall be repaired at the Contractor's expense to the full satisfaction of the owner of the damaged utility or property. The Contractor shall provide the Owner with a letter from the owner of the damaged utility or property stating that it has been repaired to the utility owner's full satisfaction.
- 8.7 <u>Structures</u>. The Contractor shall exercise every precaution to prevent

- damage to existing buildings or structures in the vicinity of his work. In the event of such damages, he shall repair them to the satisfaction of the owner of the damaged structure at no cost to the Owner.
- 8.8 Overhead Utilities. The Contractor shall use extreme caution to avoid a conflict, contact, or damage to overhead utilities, such as power lines, streetlights, telephone lines, television lines, poles, or other appurtenances during the course of construction of this project.
- 8.9 <u>Buried Gas Lines</u>. The Contractor shall provide some means of overhead support for buried gas lines exposed during trenching to prevent rupture in case of trench caving.
- 8.10 Pavement Removal. Where trench excavation or structure excavation requires the removal of curb and gutter, concrete sidewalks, or asphalt or concrete pavement, the pavement or concrete shall be cut in a straight line parallel to the edge of the excavation by use of a spade-bitted air hammer, concrete saw, colter wheel, or similar approved equipment to obtain a straight, square clean break. Pavement cuts shall be 2 feet wider than the actual trench opening.
- 8.11 Survey Markers and Monuments. The Contractor shall use every care and precaution to protect and not disturb any survey marker or monuments, such as those that might be located at lot or block corners, property pins, intersection of street monuments or addition line demarcation. Such protection includes markings with flagged high lath and close supervision. No monuments shall be disturbed without prior approval of the Project Representative. Any survey marker or monument disturbed by the Contractor during the construction of the project shall be replaced at no cost to the Owner by a licensed land surveyor.
- 8.12 <u>Temporary Utilities</u>. The Contractor shall provide all temporary electrical, lighting, telephone, heating, cooling, ventilating, water, sanitary, fire protection, and other utilities and services necessary for the performance of the work. All fees, charges, and other costs associated therewith shall be paid for by the Contractor.

9. CONSTRUCTION SAFETY

The Contractor shall be solely and completely responsible for conditions of the jobsite, including safety of all persons (including employees and subcontractors) and property during performance of the work. This requirement shall apply continuously and not be limited to normal working hours. Safety provisions shall conform to U.S. Department of Labor (OSHA), and all other applicable federal, state, county, and local laws, ordinances,

Special Provisions Page 8 codes, and regulations. Where any of these are in conflict, the more stringent requirement shall be followed. The Contractor's failure to thoroughly familiarize himself with the aforementioned safety provisions shall not relieve them from compliance with the obligations and penalties set forth therein, see General Conditions, Article 10.

10. CONSTRUCTION LIMITS AND AREAS OF DISTURBANCE

- 10.1 Construction Limits. Where construction easements or property lines, are not specifically called out on the Contract Documents, limit the construction disturbance to ten (10) feet, when measured from the edge of the slope stake grading, or to the adjacent property line, whichever is less. Disturbance and equipment access beyond this limit is not allowed without the written approval of both the Project Representative and the Owner of the affected property. If so approved, disturbance beyond construction limits shall meet all requirements imposed by the landowner; this includes existing roads used and/or improved as well as the construction of new access roads. Special construction, reclamation, or post-construction reclamation or other closure provisions required by the landowner on access roads beyond the construction limits shall be performed by the Contractor at no additional cost to the Owner.
- Areas of Disturbances. Approved areas of disturbance are those areas disturbed by construction activities within the construction limits and along designated or approved access routes. Such areas may require reclamation and revegetation operations, including grading to the original contours, top soiling with salvaged or imported topsoil, seeding, fertilizing, and mulching as specified herein. Other areas that are disturbed by the Contractor's activities outside of the limits noted above will be considered as site damage or unapproved areas of disturbance, see General Conditions, Articles 3 and 10. This includes areas selected by the Contractor outside the defined construction limits for mobilization, offices, equipment, or material storage.

11. DECONTAMINATE CONSTRUCTION EQUIPMENT

Power wash all construction equipment entering the project site to prevent the spread of noxious weeds and aquatic invasive species. This applies to all FWP projects, whether or not individual construction permits specifically address cleaning of equipment.

12. TREE PROTECTION AND PRESERVATION

The Contractor and the Owner shall individually inspect all trees within the project construction limits prior to construction. The Owner shall determine which trees are to be removed and which trees are to be preserved. Construction of the grading, utilities and various roadway facilities must not significantly damage the trees root system or hinder it's chances for survival. Reasonable variations from the Contract Documents, as directed by the Project Representative, may be employed to ensure the survival of trees.

13. CONSTRUCTION SURVEYS

The Contractor will be responsible for all layout and construction staking utilizing the Project Representative's existing control and coordinate data for the project. Dimensions and elevations indicated in layout of work shall be verified by the Contractor. Discrepancies between Drawings, Specifications, and existing conditions shall be referred to the Project Representative for adjustment before work is performed. The Project Representative may set location and grade stakes prior to construction; however, it is ultimately the responsibility of the Contractor to check and verify all construction staking for the project.

Existing survey control (horizontal and vertical) has been set for use in the design and ultimately the construction of these improvements. A listing of the coordinates and vertical elevation for each of these control points may be included in the project drawings.

The Contractor will be responsible for preserving and protecting the survey control until proper referencing by the Contractor has been completed. Any survey control obliterated, removed, or otherwise lost during construction will be replaced at the Contractor's expense.

Contractor shall be aware of property pins and survey monuments. Damage to these pins will require replacement of such by a registered land surveyor at no cost to the owner.

The Contractor shall provide construction staking from the Contractor's layouts and the control points. Contractor's construction staking includes at a minimum:

- 1. Slope stakes located at critical points as determined by the Project Representative.
- 2. Blue tops every longitudinally and transversely for subgrade and crushed base to verify finish grading of course.
- 3. Location and grade stakes for drainage features and retaining walls.
- 4. Location stakes for roadside safety items, permanent and temporary traffic control, and misc. items as determined by the Project Representative.

Original field notes, computations and other records take by the Contractor for the purpose of quantity and progress surveys shall be furnished promptly to the Project Representative and shall be used to the extent necessary in determining the proper amount of payment due to the Contractor.

14. MATERIAL SOURCES AND CONSTRUCTION WATER

Special Provisions Page 10 The Contractor shall be responsible for locating all necessary material sources, including aggregates, earthen borrow and water necessary to complete the work. The Contractor shall be responsible for meeting all transportation and environmental regulations as well as paying any royalties. The Contractor shall provide the Project Representative with written approvals of landowners from whom materials are to be obtained, prior to approval.

The Contractor may use materials from any source, providing the materials have been tested through representative samples and will meet the Specifications.

Water for compaction efforts shall be supplied by the Contractor.

15. MATERIALS SALVAGE AND DISPOSAL

Notify the Owner for any material salvaged from the project site not identified in the Contract Documents. The Owner reserves the right to maintain salvaged material at the project site, compensate the Contractor for relocation of salvaged material, or agreed compensation to Owner for material salvaged by the Contractor.

Haul and waste all waste material to a legal site and obey all state, county, and local disposal restrictions and regulations.

16. STORED MATERIALS

Contractor shall use an approved storage area for materials. Materials and/or equipment purchased by the Contractor may be compensated on a monthly basis. For compensation, provide the Project Representative invoices for said materials, shop drawings and/or submittals for approval, and applicable insurance coverage, see General Conditions, Article 9.

17. STAGING AND STOCKPILING AREA

Contractor shall use staging and stockpiling sites for to facilitate the project as approved by the Owner. Contract Documents may show approved staging and stockpiling locations. Notify Owner within 24 hours for approval of staging and stockpiling sites not shown on the Contract Drawings.

18. SECURITY

The Contractor shall provide all security measures necessary to assure the protection of equipment, materials in storage, completed work, and the project in general.

19. CLEANUP

Cleanup for each item of work shall be <u>fully</u> completed and accepted before the item is

Special Provisions Page 11 considered final. If the Contractor fails to perform cleanup within a timely manner the Owner reserves the right to withhold final payment.

Review these Contract Documents for additional Final Cleanup specifications for specific measures, associated with Contractor responsibilities and final payment.

20. ACCESS DURING CONSTRUCTION

Provide access to all public and private roadways and approaches within the project throughout the construction period.

Provide emergency access at all times within the project throughout the construction period.

21. CONSTRUCTION TRAFFIC CONTROL

The Contractor is responsible for providing safe construction and work zones within the project limits by implementing the rules, regulations, and practices of the <u>Manual on Uniform Traffic Control Devices</u>, current edition.

22. SANITARY FACILITIES

Provide on-site toilet facilities for employees of Contractor and Sub-Contractors and maintain in a sanitary condition.

23. CONTRACT CLOSEOUT

The Contractor's Superintendent shall maintain at the project site, a "Record Set of Drawings" showing field changes, as-built elevations, unusual conditions encountered during construction, and such other data as required to provide the Owner with an accurate "as constructed" set of record drawings. The Contractor shall furnish the "Record Set" to the Project Representative following the Final Inspection of the Project.

The Contractor's final payment will not be processed until the "Record Set" of drawings are received and approved by the Project Representative.

24. MEASUREMENT AND PAYMENT

Review these Contract Documents for additional Measurement and Payment specifications for definitions. Quantities are listed on the Bid Proposal for Payment Items. Additional material quantities, volumes, and measurements may be shown on the Contract Document drawings and/or specifications.

Unit Price quantities and measurements shown on the Bid Proposal are for bidding and contract purpose only. Quantities and measurements supplied, completed for the project, and verified by the Project Representative shall determine payment. Each unit

price will be deemed to include an amount considered by the Contractor to be adequate to cover Contractor's overhead and profit for each bid item.

The Owner or Contractor may make a Claim for an adjustment in Contract Unit Price if the quantity of any item of Unit Price Work performed by the Contractor <u>differs</u> <u>materially and/or significantly (increase or decrease by 50%)</u> from the estimated quantity indicated on the Bid Proposal.

Lump sum bid item quantities will not be measured. Payment for these lump sum bid proposal items will be paid in full amount listed on the Bid Proposal when accepted by the Project Representative, unless specified otherwise.

1. <u>Mobilization/Demobilization:</u>

* <u>Description</u>: This bid item includes all equipment, labor and associated work necessary for the transporting of equipment to and from the work site to construct the project to the lines and grades as noted in the specifications and drawings. This bid item shall not be measured and will be paid as lump sum.

2. Clearing and Grubbing:

* <u>Description</u>: This bid item includes all equipment, labor and associated work necessary for the stripping and removal of ground cover, trees, sod and other deleterious material from within the construction limits as noted in the specifications and drawings. This bid item shall not be measured and will be paid as lump sum.

3. Excavation and Embankment:

* <u>Description</u>: This bid item includes all equipment, labor and associated work for the excavation and the embankment needed to bring the area to grade. This bid item shall not be measured and will be paid as lump sum.

Estimated Quantity: Cut - Approximately 96 cy Fill - Approximately 115 cy

4. Asphalt Roadway (PGAB - PG 64-22):

Description: This bid item includes all equipment, labor and associated work for placement of the specified type and thickness of hot plant mix asphalt concrete pavement, complete in place, for producing, furnishing, transporting, placing, shaping, compacting and finishing of the paving mix, for improving unsatisfactory areas, furnishing samples, and for all materials, manipulation, tools, labor, equipment and incidentals necessary to complete this item. Final pay quantity will be the final square yardage of asphalt placed, not exceeding bid amount unless modified by Change Order. Measurement shall be to the neat line, accepted, in place area as determined by the Engineer.

Estimated Quantity: 140 square yards

5. Entrance Station:

* <u>Description</u>: This bid item includes all equipment, labor and associated work necessary for the construction of the entrance station building as detailed on the plans and specifications. Including, but not limited to; asphalt removal, excavation, concrete foundation, framing, finishing, doors and windows, electrical wiring, and roofing. This bid item shall not be measured and will be paid as lump sum.

6. Concrete Bollards:

* <u>Description</u>: This bid item includes all equipment, labor and associated work necessary for the installation of four (4) concrete-filled, six-inch steel pipe bollards as detailed on the plans and specifications. This bid item shall be paid per each.

7. Electrical Service:

* <u>Description</u>: This bid item includes all equipment, labor and associated work necessary for the extension of electrical service from the park information kiosk to the entrance station. This bid item shall be paid per linear foot (to the nearest one foot) of electrical service line installed. Contractor shall coordinate with local provider as necessary for electrical service line extension.

Estimated Quantity: 150 linear feet

8. Telephone Service:

<u>Description</u>: This bid item includes all equipment, labor and associated work necessary for the extension of telephone service from the park host site to the entrance station. This bid item shall be paid per linear foot (to the nearest one foot) of telephone service line installed.

Estimated Quantity: 500 linear feet

SPECIFICATIONS FOR WORK

TECHNICAL PROVISIONS

Incorporation of Montana Public Works Technical Specifications.

The Technical Specifications as found in Montana Public Works Standard Specifications (MPWSS), Sixth Edition, April 2010; are hereby incorporated by reference and made a part of this Contract:

Incorporation of Montana Fish, Wildlife & Parks Technical Specifications and Modifications to MPW Technical Specifications.

In addition to the MPWSS Technical Specifications are the following Montana Fish, Wildlife & Parks Technical Specifications (modifications to MPWSS Technical Specifications).

SECTION 01050 - Field Engineering
SECTION 01450 - Mobilization/Demobilization
SECTION 01610 - General Equipment Stipulations
SECTION 01750 - Final Cleanup
SECTION 01800 - Erosion and Sediment Control

SECTION 02236 - Gravel Leveling Course SECTION 02510- Asphalt Concrete Pavement

SECTION 03100 - Concrete Formwork SECTION 03210 - Concrete Reinforcement SECTION 03310 - Structural Concrete

SECTION 06100 - Carpentry SECTION 16000 - Electrical



FIELD ENGINEERING

All applicable portions of this specification section in the MPWSS shall apply with the following additions, deletions and/or modifications.

PART 3 EXECUTION

1.1 CONSTRUCTION SURVEY

A. Perform all survey, staking, recording of data, and calculations as necessary to construct the project from the initial layout to final completion. Reset stakes as many times as necessary to construct the work.

PART 4 MEASUREMENT AND PAYMENT

Add the following:

A. Construction Surveying will not be measured or paid for and is considered incidental to other work items.

MOBILIZATION/DEMOBILIZATION

Added Section.

PART 1 GENERAL

1.1 DESCRIPTION

- A. This item shall consist of the prepatory work and operations necessary performed by the Contractor for the movement of personnel, equipment, supplies, and incidentals to and from the work site. The work includes those actions necessary for obtaining necessary permits required for mobilization; for the establishment of all offices and facilities necessary to work on the project; for premiums on contract bonds; for insurance for the contract; and for other work on the various items on the project site. Mobilization costs for subcontracted work shall be considered to be included.
- B. Contractor's cost for administration, bonding, insurance, and site documents shall be included in mobilization and shall not be paid as a separate item.
- C. All equipment moved to the project sites shall be in good mechanical condition and free of fuel, oil, lubrication, or other fuel leaks. The Contractor shall immediately remove any equipment potentially or actually discharging environmentally damaging fluids.
- D. All equipment moved to the project sites shall be thoroughly cleaned before it is brought to the sites to prevent the introduction of weed seeds. Equipment removed fro the sites may not be returned to the sites again until it is thoroughly cleaned again.

PART 2 PRODUCTS – NOT USED

PART 3 EXECUTION – NOT USED

PART 4 MEASUREMENT AND PAYMENT

4.1 MEASUREMENT

A. There will be no direct measurement of this item.

4.2 PAYMENT

B. Partial payments for mobilization/demobilization will be made based on the lump sum bid price as follows:

- ➤ 25% of the amount bid for mobilization/demobilization when the Contractor has moved on-site and begun construction activities.
- > 50% of the amount bid for mobilization/demobilization when 25% of the contract amount (exclusive mobilization/demobilization) has been completed.
- > 75% of the amount bid for mobilization/demobilization when 50% of the contract amount (exclusive mobilization/demobilization) has been completed.
- ➤ 100% of the amount bid for mobilization/demobilization when 75% of the contract amount (exclusive mobilization/demobilization) has been completed.

GENERAL EQUIPMENT STIPULATIONS

SECTION 01610

1. SECTION INCLUDES

A. All equipment furnished and installed under this Contract shall conform to the general stipulations set forth in this section except as otherwise specified in other sections.

2. GENERAL

- A. Manufacturer's Experience: Unless specifically named in the Specifications, a manufacturer shall have furnished equipment of the type, size, and service specified which has been in successful operation at two facilities for not less than the past five years.
- B. Manufacture shall provide references from their installation including a contact name and phone number upon request.
- C. Workmanship and Materials:
 - 1. **Supplier** shall guarantee all equipment against faulty or inadequate design, improper assembly or erection, defective workmanship or materials, and leakage, breakage, or other failure. Materials shall be suitable for service conditions.
 - 2. All equipment shall be designed, fabricated, and assembled in accordance with recognized and acceptable engineering and shop practice. Individual parts shall be manufactured to standard sizes and gauges so that repair parts, furnished at any time, can be installed in the field. Like parts of duplicate units shall be interchangeable. Equipment shall not have been in service at any time prior to delivery, except as required by tests.
 - 3. Except where otherwise specified, structural and miscellaneous fabricated steel used in equipment shall conform to AISC standards. All structural members shall be designed for shock or vibratory loads. Unless otherwise specified, all steel which will be submerged, all or in part, during normal operation of the equipment shall be at least 1/4-inch thick.
- D. Elevation: The elevation of the site is approximately 3000 feet above mean sea level. All equipment furnished shall be designed to meet stipulated conditions and to operate satisfactorily at this elevation.
- E. Single Source: Like items of equipment shall be the end product of one manufacturer in order to achieve standardization.
- F. Manufacturer's Representative:
 - 1. Manufacturer shall provide a Manufacturer's Representative where specified to assist in the installation, adjustment, startup, certification and operating training.

- 2. Manufacturer's Representative shall be an employee of manufacturer who is factory trained and knowledgeable in the technical aspects of the products and systems including both operation and maintenance.
- 3. When the services of the representative are specifically required for a listed time period, the days shall represent 8 hours straight time exclusive of Saturdays, Sundays and holidays. Travel time is considered incidental to the work and will not apply to the required listed time.
- 4. If listed time is not required or is modified, an appropriate adjustment in payment shall be made. If the provided Manufacturer's Representative is found deficient in training or experience by the Owner or Engineer, the manufacturer shall furnish another acceptable representative.
- 5. Any training shall be at the job site at times scheduled by the engineer. And will be considered concluded only when the engineer is satisfied in regard to complete and thorough coverage.

3. ACCESSORIES

- A. General: All equipment shall be provided with the following accessories as applicable.
- B. Special Tools: Equipment requiring periodic repair and adjustment shall be furnished complete with all special tools, instruments, and accessories required for proper maintenance. Equipment requiring special devices for lifting or handling shall be furnished complete with those devices.

C. Spare Parts:

- 1. Furnish all spare parts specified or purchased prior to requesting the issuance of a Certificate of Completion and/or operation of the equipment by the Owner.
- 2. Spare parts and special tools shall be properly packaged to avoid damage, in their original cartons insofar as possible, and shall be stored in a location as determined by the Engineer. Any spare parts found to be damaged or otherwise inoperable at the time of delivery shall be replaced or, if approved by the Engineer, satisfactorily repaired.
- 3. Spare parts and special tools shall be labeled with a minimum 3-inch by 6-inch manila spare parts tag with such information as the part description, the manufacturer's part number, the applicable equipment description and manufacturer, the quantity of parts delivered in each package, the applicable specification section, and the **CONTRACTOR'S** and Project's name. This tag shall be firmly affixed to, and prominently displayed on the outside of each package.

4. OPERATION AND MAINTENANCE (O&M) MANUALS

- A. In addition to any requirement of other specifications, the manufacturer shall furnish four (4) copies of a complete instruction manual for installation, operation, maintenance, and lubrication requirements for each component of mechanical and electrical equipment or system. Each instruction manual furnished shall be clearly labeled to designate the system or equipment for which it is intended with reference to the building and equipment number. and the specification section where the item is specified.
- B. The manuals shall be furnished prior to the 75 percent completion point of the work. Submission of the manuals shall precede payment for all work completed in excess of the 75 percent completion level on the particular equipment and systems for which the manuals are due. Any deficiencies found by the Engineer to exist in the manuals submitted shall be corrected within 30 calendar days following notification of the deficiencies.
- C. Each instruction manual shall include, but not be limited to the following:
 - 1. Diagrams and illustrations.
 - 2. Detailed description of the function of each principal component of the system.
 - 3. Performance and nameplate data.
 - 4. Installation instructions.
 - 5. Procedure for starting.
 - 6. Proper adjustment.
 - 7. Test procedures.
 - 8. Procedure for operating.
 - 9. Shutdown instructions.
 - 10. Emergency operating instruction and troubleshooting guide.
 - 11. Safety precautions.
 - 12. Maintenance and overhaul instruction which shall include detailed assembly drawings with part numbers, parts list, instructions for ordering spare parts, and complete preventive maintenance instructions required to ensure satisfactory performance and longevity of the equipment.
 - 13. Lubrication instructions, which shall list points to be greased or oiled, shall recommend type, grade, and temperature range of lubricants, and shall recommend frequency of lubrication.
 - 14. List of electrical relay settings and control and alarm contact settings.

- 15. Electrical interconnection wiring diagram for equipment, including all control and lighting systems.
- D. Manuals shall be complete in all respects for all equipment, controls, accessories, and associated appurtenances.
- E. Manuals shall be assembled in one or more binders, each with title page, typed table of contents, and heavy section dividers with numbered plastic index tabs. Each manual shall be divided into sections paralleling the Equipment Specifications. Binders shall be three-ring, hard-back type. All data shall be punched for binding and composition and printing shall be arranged so that punching does not obliterate any data. The project title, division designation, and manual title printed thereon shall be as furnished by the Engineer.
- F. When more than one binder is required, they shall be labeled "Vol. I." "Vol. 2," and so on. The table of contents for the entire set, identified by volume number, shall appear in each binder. Submit manual organization and format to the Engineer for approval prior to manual preparation.
- G. Each O&M Manual shall be transmitted to the Engineer prior to installation of the equipment and all equipment shall be serviced in accordance with the manufacturer's recommendations prior to operation. A service record shall be maintained on each item of equipment and shall be delivered to the Engineer prior to final acceptance of the project.

5. WARRANTY

A. A manufacturer's warranty is required for each piece of equipment as defined in the Contract General Conditions or technical specifications. The One-Year Correction Period shall begin at Substantial Completion of the entire project.

6. TESTS

- A. Pre-test mechanical and electrical equipment and systems and make corrections required for proper operation of such systems before requesting final tests. Final tests will not be conducted unless pre-tested.
- B. Conduct final tests required in various sections of specifications in presence of authorized representative of the Contracting Officer. **CONTRACTOR** shall furnish all labor, materials, equipment, instruments, and forms, to conduct and record such tests.

FINAL CLEANUP

Added Section.

PART 1 GENERAL

1.1 DESCRIPTION

A. This work consists of final cleanup of the project site prior to final acceptance.

PART 2 PRODUCTS – NOT USED

PART 3 EXECUTION

3.1 CONTRACTOR RESPONSIBILITES

The contractor shall be responsible for final clean up at the end of the project to a level satisfactory to the owner. All construction debris, no mater how small, shall be collected and removed from the site. All wheel ruts shall be filled in and be leveled to match the adjacent grade and material. Re-seeding or re-sodding, or other re-surfacing may be necessary to repair any construction related impacts or damage.

All survey markings, stakes, temporary paint marks, flagging and other devices shall be removed regardless of who installed them. All excess pavement, concrete, gravel, soil, or other construction materials not intended for permanent use shall be removed.

All final slopes shall be dressed manually to remove woody debris, accumulated trash and oversized material. Any new slope or topsoil surfaces shall be hand raked to provide a uniform appearance. The contractor shall dress all gravel, pavement and concrete edges to eliminate abrupt edges and provide a smooth transition. All construction related temporary sediment control devices shall be removed as soon as practical.

PART 4 MEASUREMENT AND PAYMENT

4.1 PAYMENT

Unless specifically noted otherwise, all final cleanup work shall be incidental to other work items in the contract and no separate payment shall be made.

EROSION AND SEDIMENT CONTROL

Added Section.

PART 1 GENERAL

1.1 DESCRIPTION

A. This work consists of furnishing, constructing, and maintaining permanent and temporary erosion control and sediment control measures.

PART 2 PRODUCTS

2.1 GENERAL

A. Temporary and erosion control products utilized include but are not limited to backfill material; berms; brush barriers; erosion control bales, wattles, logs, rolls; erosion control culvert pipe; detention basins; fertilizer; geotextile; mulch; plastic lining; riprap; sandbags; seed; silt fence; and water.

2.2 SEDIMENT RETENTION

A. Provide a sediment retention product made from straw and coconut fiber reinforced with a 100% bio-degradable netting. Use wood stakes to secure sediment retention product in place, spacing per the manufacturer's recommendations. An acceptable product is *Sediment Stop*®, manufactured by *North American Green*, or approved equal.

PART 3 EXECUTION

3.1 INSTALLATION

- A. Provide permanent and temporary erosion control measures to minimize erosion and sedimentation during and after construction as necessary according to applicable environmental permits, and as directed by the Project Representative. These erosion control measures shall be designed, implemented, and maintained by the Contractor in accordance with Best Management Practices (BMPs) to control erosion and sediment release from the work site.
- B. When erosion control measures are not functioning as intended, immediately take corrective action.

PART 4 MEASUREMENT AND PAYMENT

4.1 PAYMENT

A. All items in this section are incidental to the work and no separate payment is made for these items.

GRAVEL LEVELING COURSE

Added Subsection.

PART 1 GENERAL

1.1 DESCRIPTION

B. This work also consists of placing clean, screened gap-graded gravel leveling course beneath cast-in-place concrete.

PART 2 PRODUCTS

2.1 GRAVEL LEVELING COURSE GRADATION

A. Furnish gravel leveling course that is crushed aggregate as shown in Table 1. The gravel leveling course must not contain other deleterious material, such as shale, alkali, mica, or soft flaky particles.

Table 1. Gravel Leveling Course Gradation

Sieve Size	Percent Passing
1"	100
3/4"	90-100
3/8"	20-55
No. 4	0-10
No. 8	0-5

PART 3 EXECUTION

3.1 PLACEMENT AND SPREADING

- A. Place material to specified depth as indicated on the project drawings. Deposit and spread the material in a uniform layer and screed to make a uniform surface at the specified grade as indicated on the project drawings.
- B. Perform compaction efforts by mechanical tamping as approved by the Project Representative.

PART 4 MEASUREMENT AND PAYMENT

4.1 GRAVEL LEVELING COURSE

A. Gravel Leveling Course will not be measured for payment and is considered incidental to other work items in this Contract.

ASPHALT CONCRETE PAVEMENT

All applicable portions of this specification section in the MPWSS shall apply with the following additions, deletions and/or modifications.

PART 2 PRODUCTS

2.3 ASPHALT BIDER MATERIAL

Delete the entire section and replace with the following:

Use (PGAB) PG 64-22.

- 2.5 COMPOSITION OF MIXES
 - C. ASPHALT CONCRETE SURFACE COURSE

Delete the entire section and replace with the following:

3. The average density shall be equal to or greater than 95 percent of the maximum dry density as determined by ASTM D2041 and no individual sample shall be less than 92 percent of maximum density.

PART 3 EXECUTION

3.28 DENSITY AND SURFACE REQUIREMENTS:

Delete the entire section and replace with the following:

A. The average mat density shall be equal to or greater than 95 percent of the maximum dry density as determined by ASTM D2041 and no individual sample shall be less than 92 percent of maximum (Rice's) density, prepared as specified in Part 2-Products in this section and made from plant mix meeting the job-mix formula. Verification of maximum density as determined by ASTM D2041 from plant produced material during production is recommended.

CONCRETE FORMWORK

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Form work for cast-in place concrete, with shoring, bracing and anchorage.
- B. Form accessories.
- C. Form stripping.

1.2 PRODUCTS INSTALLED BUT NOT FURNISHED UNDER THIS SECTION

A. Section 03300 - Cast-In-Place Concrete: Supply of concrete accessories for placement by this section.

1.3 RELATED SECTIONS

- A. Section 03200 Concrete Reinforcement.
- B. Section 03300 Cast-in-Place Concrete.

1.4 REFERENCES

- A. ACI 301 Structural Concrete for Buildings.
- B. ACI 318 Building Code Requirements for Reinforced Concrete.
- C. ACI 347 Recommended Practice For Concrete Form work.
- D. PS 1 Construction and Industrial Plywood.

1.5 DESIGN REQUIREMENTS

A. Construct form work, shoring and bracing to conform to design and code requirements; resultant concrete to conform to required shape, line and dimension.

1.6 REGULATORY REQUIREMENTS

A. Conform to applicable code for fabrication, erection and removal of formwork.

1.7 COORDINATION

- A. Coordinate this Section with other Sections of work which require attachment of components to form work.
- B. If formwork is placed after reinforcement resulting in insufficient concrete cover over reinforcement before proceeding, request instructions from Project Manager.

PART 2 PRODUCTS

2.1 FORM MATERIALS

A. Form Materials: At the discretion of the Contractor.

2.2 FORMWORK ACCESSORIES

- A. Form Release Agent: Colorless vegetable oil, approved for use in fresh water which will not stain concrete, or absorb moisture.
- B. Nails, Spikes, Lag Bolts, Through Bolts, Anchors: Sized as required, of sufficient strength and character to maintain form work in place while placing concrete.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify lines, levels and centers before proceeding with formwork. Ensure that dimensions agree with drawings.

3.2 EARTH FORMS

A. Earth forms are not permitted.

3.3 ERECTION - FORMWORK

- A. Erect form work, shoring and bracing to achieve design requirements, in accordance with requirements of ACI 301.
- B. Provide bracing to ensure stability of formwork. Shore or strengthen formwork subject to over stressing by construction loads.
- C. Arrange and assemble formwork to permit dismantling and stripping. Do not damage

 """"SECTION 03100 Page 2 of 3

concrete during stripping. Permit removal of remaining principal shores.

D. Align joints and make watertight. Keep form joints to a minimum.

3.4 APPLICATION - FORM RELEASE AGENT

- A. Apply form release agent on formwork in accordance with manufacturer's recommendations.
- B. Apply prior to placement of reinforcing steel, anchoring devices, and embedded items.
- C. Soak inside surfaces of untreated forms with clean water. Keep surfaces coated with form release agent prior to placement of concrete.

3.5 FORMWORK TOLERANCES

A. Construct formwork to maintain tolerances required by Section 03300 - Cast-in-Place Concrete.

3.6 FIELD QUALITY CONTROL

A. Inspect erected form work, shoring, and bracing to ensure that work is in accordance with design, and that supports, fastenings, wedges, ties, and items are secure.

3.7 FORM REMOVAL

- A. Do not remove forms or bracing until concrete has gained sufficient strength to carry its own weight and imposed loads.
- B. Loosen forms carefully. Do not wedge pry bars, hammers, or tools against finish concrete surfaces scheduled for exposure to view.

PART 4 METHODS OF MEASUREMENT

4.1 This work is part of the item for the poured concrete and shall not be measured.

PART 5 BASIS OF PAYMENT

5.1 This work is part of the item for the poured concrete and shall not be paid separately.

END OF SECTION

CONCRETE REINFORCEMENT

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Reinforcing steel, fibermesh and accessories for cast-in-place concrete.

1.2 RELATED SECTIONS

- A. Section 03100 Concrete Formwork.
- B. Section 03310 Structural Concrete.

1.3 REFERENCES

- A. CRSI Concrete Reinforcing Steel Institute Manual of Practice.
- B. CRSI 63 Recommended Practice For Placing Reinforcing Bars.
- C. CRSI 65 Recommended Practice For Placing Bar Supports, Specifications and Nomenclature.

1.4 QUALITY ASSURANCE

A. Perform Work in accordance with CRSI 63, 65 and Manual of Practice.

PART 2 PRODUCTS

2.1 REINFORCEMENT

- A. Fibermesh reinforcement: Fibrillate polypropylene olefin fibermesh or approved equal.
- B. Reinforcement bars shall conform to ASTM Specification A-615-68, "Deformed Billet Steel Bars for Concrete Reinforcement." The size shall be shown on the Plans.

3.1 STEEL REINFORCEMENT

A. Steel reinforcement shall be carefully cut to proper length and accurately bent before placement. Cold bends shall be made around a pin having a minimum diameter eight times the diameter of the bar being bent.

- B. Placing Reinforcement Steel. Reinforcing steel delivered or stored at the site of the work shall be neatly piled on blocks or timbers in such a way as to keep it off the ground, and shall be covered to prevent intrusion of moisture.
- C. Before being placed, all steel shall be thoroughly cleaned of mill scale, rust, grease, or other coatings that will destroy the bond.
- D. Reinforcement shall be carefully placed as indicated on the Plans. Bars shall not be bent or straightened in a manner that will injure the material.
- E. Bars shall be accurately and rigidly secured in position by use of such approved metal clips, spacers, bar supports, or hychairs as may be necessary.
- F. Splices in reinforcing bars shall be lapped at least 12 inches.
- G. Reinforcement shall be secured in position, inspected, and approved before concrete is placed. In no case shall reinforcement be allowed to be in contact with the ground or touch from work once installed.
- H. All main reinforcement shall have the following cover unless otherwise shown on the Plans. The reinforcement of footings and other principal structural members in which the concrete is deposited against the ground contact surface shall be placed three inches from the contact surface. If contact surfaces after removal of the forms are to be exposed to the weather or are to be in contact with the ground, the reinforcement shall be protected with not less than 1 1/2 inches for #5 bars or smaller.

PART 3 EXECUTION

3.1 FIELD QUALITY CONTROL

A. Field inspection of the reinforcement shall be performed by the Project Manager.

PART 4 MEASUREMENT AND PAYMENT

4.1 METHODS OF MEASUREMENT

A. This work is part of the item for the poured concrete and shall not be measured.

4.2 BASIS OF PAYMENT

A. This work is part of the item for the poured concrete and shall not be paid separately.

STRUCTURAL CONCRETE

All applicable portions of this specification section in the MPWSS shall apply with the following additions, deletions and/or modifications.

PART 1 GENERAL

PART 2 PRODUCT

2.1 CLASSIFICATION

Add the following to Subsection A.1:

1. Use M-4000 concrete for cast-in-place concrete.

PART 3 EXECUTION

Add the following:

B. Provide written and/or verbal communication notice to the Project Manager three (3) working days, excluding Saturday and Sunday, prior to any project concrete pour, regardless of pour quantity. For clarification, all written communication notices have to received in the FWP Design and Construction Office per this requirement. Failure to provide notification will result in a deduct of pour quantity from the associated bid item. Lump sum bid items will be deducted based on the concrete placed percentage.

PART 4 MEASUREMENT AND PAYMENT

4.1 GENERAL

Delete this section and add the following:

A. Cast-in-Place Concrete will not be measured and will be paid by the lump sum (LPSM) including all labor, equipment, materials, and incidentals required for the completion of the work.

CARPENTRY

PART 1 GENERAL

1.1 DESCRIPTION

A. This work consists of framing, roofing, siding, finishing and trimming a "stick-framed" eight (8) foot by twelve (12) foot entrance station. Also includes installation of windows, doors, soffit, facia, and other appurtenances to construct a complete and useable structure.

PART 2 PRODUCTS

2.1 LUMBER

- A. All framing lumber shall be kiln dried douglas fir No. 2 grade or better
- B. All construction panels (OSB sheathing and flooring) shall be APA verified and shall conform to US Voluntary Product Standard PS2. Sizes as indicated on plans.

2.2 SIDING & EXTERIOR TRIM

- A. Siding shall be 8 ¼" cement board lap siding.
 - 1. Cedarmill texture (or approved equal)
 - 2. Color as directed by owner
- B. Exterior trim shall be 1" x 4" (nominal size) cement trim board.
 - 1. Cedarmill texture (or approved equal)
 - 2. Color as directed by owner

2.3 ROOFING AND TRIM

- A. Roofing shall be ribbed metal roofing with 30# felt paper underlayment.
 - 1. Roofing shall be 29 gauge
 - 2. Color as directed by owner
- B. Drip edge, soffit, and facia shall be aluminum
 - 1. Color to match roofing

2.4 WINDOWS AND DOORS

A. WINDOWS

1. Windows shall be vinyl clad sliding windows.

B. DOOR

- 1. Doors shall be flush panel type, 1-3/4 inches thick and a minimum of 18 gauge prime coated steel panels and a minimum of 16 gauge internal bracing channels with a fiberglass insulation core. Door shall come with a 2' by 3' window with embedded wire mesh. See Drawings
- 2. Door frames shall be knockdown or welded type, single rabbet, minimum 16 gauge prime coated steel width to be compatible with wall thickness.

 Adequate rubber door silencers shall be provided on latch side of frame.
- 3. Door shall be equipped with an industrial strength lockset.

2.5 MISCELLANEOUS MATERIALS

A. METAL HANGARS

- 1. Joist Hangars shall be Simpson U26 or approved equal.
- 2. Truss clips shall USP Rafter Clip (1-9/16" x 2-5/8" x 5-1/4") or approved equal
- 3. All clips and hangers shall be hot dip zinc coated

B. AIR CONDITIONING UNIT

1. Air conditioning unit shall be a 115 volt 5000 BTU "window" mounted air conditioner.

PART 3 EXECUTION

3.1 CONTRACTOR RESPONSIBILITES

- A. All work shall conform to all applicable industry standards and codes.
- B. Contractor shall obtain required electrical permit from the State of Montana.

PART 4 MEASUREMENT AND PAYMENT

4.1 PAYMENT

A. Entrance station onstruction will be paid by the lump sum (LPSM) including all labor, equipment, materials, and incidentals required for the completion of the work.

ELECTRICAL

PART 1 GENERAL

1.1 DESCRIPTION

A. This work consists of wiring and installing light fixtures, interior and exterior outlets, and a telephone line in a new park entrance station building. Also included is coordination with electrical service provider to extend the services to the structure.

PART 2 PRODUCTS

2.1 WIRING

- A. All components to be UL listed
- B. All wire will be copper

2.2 LIGHT FIXTURES

A. GENERAL

1. Lighting on the exterior of building will be photocell activated; interior and chase room lighting will be switch activated.

B. EXTERIOR

1. 35-watt High Pressure Sodium lights, photocell vandal resistant.

C. INTERIOR

1. Vandal resistant 2 bulb T8 4 foot wrap around lens fixtures with low temperature ballast, emergency battery pack and fluorescent night light.

2.3 ELECTRICAL OUTLETS

A. EXTERIOR

1. GFCI protected electrical outlets with lockable metal cover.

B. INTERIOR

1. Standard electrical outlet.

PART 3 EXECUTION

3.1 CONTRACTOR RESPONSIBILITES

- A. All work shall conform to all applicable industry standards and codes.
- B. Contractor shall obtain required electrical permit from the State of Montana.

PART 4 MEASUREMENT AND PAYMENT

4.1 PAYMENT

A. Electrical will not be measured and will be paid by the lump sum (LPSM) including all labor, equipment, materials, and incidentals required for the completion of the work.