# **SPECIFICATIONS**

# Montana Fish, Wildlife & Parks

# SPECIFICATIONS FOR WORK SPECIAL PROVISIONS

#### **Contents:**

- 1. Project Description
- 2. Project Related Contracts
- 3. Site Inspection
- 4. Soils Information
- 5. Project Representative, Inspections, and Testing
- 6. Engineering Interpretations
- 7. Rejected Work
- 8. Utilities
- 9. Construction Safety
- 10. Construction Limits and Areas of Disturbance
- 11. Decontaminate Construction Equipment
- 12. Tree Protection and Preservation
- 13. Construction Surveys
- 14. Material Sources and Construction Water
- 15. Materials Salvage and Disposal
- 16. Stored Materials
- 17. Staging and Stockpiling Areas
- 18. Security
- 19. Cleanup
- 20. Access During Construction
- 21. Construction Traffic Control
- 22. Sanitary Facilities
- 23. Contract Closeout
- 24. Measurement and Payment

#### 1. PROJECT DESCRIPTION

The Project involves construction work associated with:

Boulder Forks Fishing Access Site (FAS) Site Development Fish, Wildlife & Parks (FWP) project # 7153722 Located in Sweet Grass County, MT

The project generally includes new parking area and access road construction involving clearing and grubbing, excavation/embankment construction, gravel base course and surfacing, conserved topsoil placement, boat ramp development, and incidentals. Designated gravel base course supplied offsite by Montana Fish, Wildlife and Parks shall be loaded, hauled and placed onsite as part of this project.

#### 2. PROJECT RELATED CONTACTS

Project contacts are designated as follows:

Owner: Montana FWP

1420 E. Sixth Ave. PO Box 200701

Helena, MT 59620-0701

FWP Project Representative: Thomas M. Mannatt

**FWP Project Manager** 

1522 9<sup>th</sup> Avenue Helena, MT 59620 406-841-4006 (wk) 406-431-4031 (cell) 406-841-4004 (fax)

# 3. SITE INSPECTION

All Bidders should satisfy themselves as to the construction conditions by personal examination of the site described in this document. Bidders are encouraged to make any investigations necessary to assess the nature of the construction and the difficulties to be encountered, see General Conditions, Article 3.

#### 4. SOILS INFORMATION

Geotechnical investigation work has not been done for this Project. It is the responsibility of the Bidders to conduct all investigations and determine the soil type and digging conditions that may be encountered with this Project prior to bid preparation, see General Conditions, Article 3.

# 5. PROJECT REPRESENTATIVE, INSPECTIONS, AND TESTING

The Contractor's work will be periodically tested and observed to insure compliance with the Contract Documents. Complete payment will not be made until the Contractor has demonstrated that the work is complete and has been performed as required. If the Project Representative detects a discrepancy between the work and the requirements of the Contract Documents at any time, up to and including final inspection, such work will not be completely paid for until the Contractor has corrected the deficiency, see General Conditions, Article 9.

The Project Representative will periodically monitor the construction of work to determine if the work is being performed in accordance with the contract requirements. The Project Representative does not have the authority or means to control the Contractor's methods of construction. It is, therefore, the Contractor's responsibility to utilize all methods, equipment, personnel, and other means necessary to assure that the work is installed in compliance with the Drawings and Specifications, and laws and regulations applicable to the work. Any discrepancies noted shall be brought to the Contractor's attention, who shall immediately correct the discrepancy. Failure of the Project Representative to detect a discrepancy will not relieve the Contractor of his ultimate responsibility to perform the work as required, see General Conditions, Article 3.

The Contractor shall inspect the work as it is being performed. Any deviation from the Contract requirements shall be immediately corrected. Prior to any scheduled observation by the Project Representative, the Contractor shall again inspect the work and certify to the Project Representative that he has inspected the work and it meets the requirements of the Contract Documents. The Project Representative may require uncovering of work to verify the work was installed according to the contract documents, see General Conditions, Article 12.

The work will be subject to review by the Project Representative. The results of all such observations, and all contract administration, shall be directed to the Contractor only through the Project Representative.

- 5.1 <u>Services Required by the Contractor</u>. The Contractor shall provide the following services:
  - a. Any field surveys to establish locations, elevations, and alignments as stipulated on the Contract Documents. FWP reserves the right to set preliminary construction staking for the project. The Contractor is responsible to notify FWP for any construction staking discrepancies.
  - b. Preparation and certification of all required shop drawings and submittals as described in the General Conditions, Article 3.
  - c. All testing requiring the services of a laboratory to determine compliance with the Contract Documents shall be performed by an independent commercial testing laboratory acceptable to the Project Representative. The laboratory shall be staffed with experienced technicians properly equipped, and fully qualified to perform the tests in accordance with the specified standards.

- d. Preparation and submittal of a construction schedule, including submittals, see General Conditions, Article 3. The schedule shall be updated as required, as defined in the Contract Documents.
- e. All Quality Control testing as required by the Contractor's internal policies.
- f. All Quality Assurance testing and/or re-testing as stated in the Contract Documents, see General Conditions. Article 13.
- 5.2 <u>Services Provided by the Owner</u>. The Owner shall provide the following services at no cost to the Contractor except as required for retests as defined in the Contract Documents.
  - a. The Project Representative may check compaction of backfill and surfacing courses using laboratory testing submittal information supplied by the Contractor. These tests are to determine if compaction requirements are being fulfilled in accordance with the Contract Documents. It is ultimately the responsibility of the Contractor to insure that this level of compaction is constant and met in all locations.
  - b. Any additional Quality Assurance testing deemed appropriate by the Owner, at the Owner's expense.

#### 6. ENGINEERING INTERPRETATIONS

Timely Engineering decisions on construction activities or results have an important bearing on the Contractor's schedule. When engineering interpretation affects a plan design or specifications change, it should be realized that more than 24 hours may be required to gain the necessary Owner participation in the decision process including time for formal work directive, or change order preparation as required.

#### 7. REJECTED WORK

Any defective work or nonconforming materials or equipment that may be discovered at any time prior to the expiration of the warranty period, shall be removed and replaced with work or materials conforming to the provisions of the Contract Documents, see General Conditions, Article 12. Failure on the part of the Project Representative to condemn or reject bad or inferior work, or to note nonconforming materials or equipment on the Contractors submittals, shall not be construed to imply acceptance of such work. The Owner shall reserve and retain all its rights and remedies at law against the Contractor and its Surety for correction of any and all latent defects discovered after the guarantee period (MCA 27-2-208).

Only the Project Representative will have the authority to reject work which does not conform to the Contract Documents.

#### 8. UTILITIES

The exact locations of existing utilities that may conflict with the work are not precisely known. It shall be the Contractor's responsibility to contact the owners of the respective utilities and arrange for field location services. **One Call Locators, 1-800-424-5555** 

The Contract Documents may show utility locations based on limited field observation and information provided to the Project Representative by others. **The Project Representative cannot guarantee their accuracy.** The Contractor shall immediately notify the Project Representative of any discrepancies with utility locations as shown on the Contract Drawings and/or their bury depths that may in any way affect the intent of construction as scoped in these specifications.

There will be no separate payment for exploratory excavation required to locate underground utilities.

- 8.1 <u>Notification</u>. The Contractor shall contact, in writing, all public and private utility companies that may have utilities encountered during excavation. The notification includes the following information:
  - a. The nature of the work that the Contractor will be performing.
  - b. The time, date and location that the Contractor will be performing work that may conflict with the utility.
  - c. The nature of work that the utility will be required to perform such as moving a power pole, supporting a pole or underground cable, etc.
  - d. Requests for field location and identification of utilities.

A copy of the letter of notification shall be provided to the Project Representative. During the course of construction, the Contractor shall keep the utility companies notified of any change in schedule, or nature of work that differs from the original notification.

8.2 <u>Identification</u>. All utilities that may conflict with the work shall be the Contractor's responsibility to locate before any excavation is performed. Field markings provided by the utility companies shall be preserved by the Contractor until actual excavation commences. All utility locations on the Drawings should be considered approximate and should be verified in the field by the Contractor. The Contractor shall also be responsible for locating all utilities that are not located on the Drawings.

Utilities are depicted on the Contract Documents in accordance with their achieved "Quality Levels," as defined in the American Society of Civil Engineer's Document, ASCE 38, "Standard Guideline for the Collection and Depiction of Existing Subsurface Utility Data." Reliance upon these data for risk management purposes during bidding does not relieve the Contractor, or Utility Owner from following all applicable utility damage prevention statutes,

policies, and/or procedures during construction. It is important that the Contractor investigates and understands the scope of work between the project Owner and Engineer regarding scope of limits of the utility investigations leading to these utility depictions. Definitions of Quality Levels are described as follows:

- a. "QUALITY LEVEL A" (QLA): LOCATING THROUGH EXCAVATION. QLA data are highly accurate and are obtained by surveying an exposed utility. As such, both horizontal and vertical data are recorded. Survey accuracies are typically set at 15mm (1/2-inch) vertically, and to project survey standards horizontally (typically the same as for topography features), although these survey accuracies and precisions are generally left to the owner to specify in a scope of work. In addition to the applicable standard of care and any other additional standards imposed by commercial indemnity clauses, the accuracy of these location data is also typically guaranteed. Other data typically characterized include material type, surface elevation, utility size/capacity, outside dimensions, and configurations, soil type, and utility condition.
- b. "QUALITY LEVEL B" (QLB): DESIGNATING. QLB information is obtained through the application of appropriate surface geophysical methods to identify the existence and approximate horizontal location of utilities (a utility's "designation") within the project limits, followed by survey, mapping, and professional review of that designation. Underground utilities are identified by interpretation of received signals generated either actively or passively, and through correlating these received signals with visible objects (QLC) and record data (QLD) to determine function. Designated utilities that can't be identified are labeled as "unknowns." Although approximate has no accuracy associated with it, generally the locations are within inches rather than feet. The more utility congested the area or the deeper the utilities, the less likely it is that the designations will achieve that accuracy. These designations are then surveyed to project accuracies and precisions, typically third-order accuracy similar to other topography features. Note that surveying existing one-call marks does not lead to QLB data, since the genesis of the marks was not under the direct responsible charge of the professional certifying the QLB depictions, and one-call generally does not address unknown utilities, privately owned utilities, utilities without records, abandoned utilities, and so on. Nor does the professional have knowledge of the field technician's qualifications, training, and level of effort.
- c. "QUALITY LEVEL C" (QLC): SURFACE VISIBLE FEATURE SURVEY. QLC builds upon the QLD information by adding an independent detailed topography site survey for surface-visible appurtenances of subsurface utilities including but not limited to fire

hydrants, valves, risers, and manholes. Professional judgment is used to correlate the QLD data to the surveyed features, thus increasing the reliability of both utility location and existence. It is a function of the professional to determine when records and features do not agree and resolve discrepancies. This may be accomplished by depiction of a utility line at quality level D, effectively bypassing or disregarding (but still depicting) a surveyed structure of unknown origin. Additional resolution may result from consultation with utility owners.

- d. "QUALITY LEVEL D" (QLD): EXISTING RECORDS RESEARCH. QLD is the most basic level of information. Information is obtained from the review and documentation of existing utility records, verbal accounts, and/or one-call markings (to determine the existence of major active utilities and their approximate locations).
- 8.3 Removal or Relocation of Utilities. All electric power, street lighting, gas, telephone, and television utilities that require relocation will be the responsibility of the utility owner. A request for extending the specified contract time will be considered if utility owners cause delays.
- 8.4 <u>Public Utilities</u>. Water, sewer, storm drainage, and other utilities owned and operated by the public entities shall, unless otherwise specifically requested by the utility owner, be removed, relocated, supported or adjusted as required by the Contractor at the Contractor's expense. All such work shall be in accordance with these Contract Documents, or the Owner's Standard Specifications or written instructions when the work involved is not covered by these Specifications.
- 8.5 Other Utilities. Utilities owned and operated by private individuals, railroads, school districts, associations, or other entities not covered in these Special Provisions shall, unless otherwise specifically requested by the utility owner, be removed, relocated, supported or adjusted as required by the Contractor at the Contractor's expense. All work shall be in accordance with the utility owner's directions, or by methods recognized as being the standard of the industry when directions are not given by the owner of the utility.
- 8.6 <u>Damage to Utilities and Private Property</u>. The Contractor shall protect all utilities and private property and shall be solely responsible for any damage resulting from his construction activities. The Contractor shall hold the Owner and Project Representative harmless from all actions resulting from his failure to properly protect utilities and private property. All damage to utilities shall be repaired at the Contractor's expense to the full satisfaction of the owner of the damaged utility or property. The Contractor shall provide the Owner with a letter from the owner of the damaged utility or property stating that it has been repaired to the utility owner's full satisfaction.

- 8.7 <u>Structures</u>. The Contractor shall exercise every precaution to prevent damage to existing buildings or structures in the vicinity of his work. In the event of such damages, he shall repair them to the satisfaction of the owner of the damaged structure at no cost to the Owner.
- 8.8 Overhead Utilities. The Contractor shall use extreme caution to avoid a conflict, contact, or damage to overhead utilities, such as power lines, streetlights, telephone lines, television lines, poles, or other appurtenances during the course of construction of this project.
- 8.9 <u>Buried Gas Lines</u>. The Contractor shall provide some means of overhead support for buried gas lines exposed during trenching to prevent rupture in case of trench caving.
- 8.10 Pavement Removal. Where trench excavation or structure excavation requires the removal of curb and gutter, concrete sidewalks, or asphalt or concrete pavement, the pavement or concrete shall be cut in a straight line parallel to the edge of the excavation by use of a spade-bitted air hammer, concrete saw, colter wheel, or similar approved equipment to obtain a straight, square clean break. Pavement cuts shall be 2 feet wider than the actual trench opening.
- 8.11 Survey Markers and Monuments. The Contractor shall use every care and precaution to protect and not disturb any survey marker or monuments, such as those that might be located at lot or block corners, property pins, intersection of street monuments or addition line demarcation. Such protection includes markings with flagged high lath and close supervision. No monuments shall be disturbed without prior approval of the Project Representative. Any survey marker or monument disturbed by the Contractor during the construction of the project shall be replaced at no cost to the Owner by a licensed land surveyor.
- 8.12 <u>Temporary Utilities</u>. The Contractor shall provide all temporary electrical, lighting, telephone, heating, cooling, ventilating, water, sanitary, fire protection, and other utilities and services necessary for the performance of the work. All fees, charges, and other costs associated therewith shall be paid for by the Contractor.

# 9. CONSTRUCTION SAFETY

The Contractor shall be solely and completely responsible for conditions of the jobsite, including safety of all persons (including employees and subcontractors) and property during performance of the work. This requirement shall apply continuously and not be

Special Provisions Page 8 limited to normal working hours. Safety provisions shall conform to U.S. Department of Labor (OSHA), and all other applicable federal, state, county, and local laws, ordinances, codes, and regulations. Where any of these are in conflict, the more stringent requirement shall be followed. The Contractor's failure to thoroughly familiarize himself with the aforementioned safety provisions shall not relieve them from compliance with the obligations and penalties set forth therein, see General Conditions, Article 10.

# 10. CONSTRUCTION LIMITS AND AREAS OF DISTURBANCE

- 10.1 Construction Limits. Where construction easements or property lines, are not specifically called out on the Contract Documents, limit the construction disturbance to ten (10) feet, when measured from the edge of the slope stake grading, or to the adjacent property line, whichever is less. Disturbance and equipment access beyond this limit is not allowed without the written approval of <a href="bottom:bottom-beyond-construction-limits-shall-meet-all-requirements-imposed-by-the-landowner;">bottom-beyond-construction-limits-shall-meet-all-requirements-imposed-by-the-landowner;</a> this includes existing roads used and/or improved as well as the construction of new access roads. Special construction, reclamation, or post-construction reclamation or other closure provisions required by the landowner on access roads beyond the construction limits shall be performed by the Contractor at no additional cost to the Owner.
- 10.2 Areas of Disturbances. Approved areas of disturbance are those areas disturbed by construction activities within the construction limits and along designated or approved access routes. Such areas may require reclamation and revegetation operations, including grading to the original contours, top soiling with salvaged or imported topsoil, seeding, fertilizing, and mulching as specified herein. Other areas that are disturbed by the Contractor's activities outside of the limits noted above will be considered as site damage or unapproved areas of disturbance, see General Conditions, Articles 3 and 10. This includes areas selected by the Contractor outside the defined construction limits for mobilization, offices, equipment, or material storage.

#### 11. DECONTAMINATE CONSTRUCTION EQUIPMENT

Power wash all construction equipment entering the project site to prevent the spread of noxious weeds and aquatic invasive species. This applies to all FWP projects, whether or not individual construction permits specifically address cleaning of equipment.

#### 12. TREE PROTECTION AND PRESERVATION

The Contractor and the Owner shall individually inspect all trees within the project construction limits prior to construction. The Owner shall determine which trees are to be removed and which trees are to be preserved. Construction of the grading, utilities and various roadway facilities must not significantly damage the trees root system or hinder it's chances for survival. Reasonable variations from the Contract Documents,

as directed by the Project Representative, may be employed to ensure the survival of trees.

#### 13. CONSTRUCTION SURVEYS

The Contractor will be responsible for all layout and construction staking utilizing the Project Representative's existing control and coordinate data for the project. Dimensions and elevations indicated in layout of work shall be verified by the Contractor. Discrepancies between Drawings, Specifications, and existing conditions shall be referred to the Project Representative for adjustment before work is performed. The Project Representative may set location and grade stakes prior to construction; however, it is ultimately the responsibility of the Contractor to check and verify all construction staking for the project.

Existing survey control (horizontal and vertical) has been set for use in the design and ultimately the construction of these improvements. A listing of the coordinates and vertical elevation for each of these control points may be included in the project drawings.

The Contractor will be responsible for preserving and protecting the survey control until proper referencing by the Contractor has been completed. Any survey control obliterated, removed, or otherwise lost during construction will be replaced at the Contractor's expense.

Contractor shall be aware of property pins and survey monuments. Damage to these pins will require replacement of such by a registered land surveyor at no cost to the owner.

The Contractor shall provide construction staking from the Contractor's layouts and the control points. Contractor's construction staking includes at a minimum:

- 1. Slope stakes located at critical points as determined by the Project Representative.
- 2. Blue tops every longitudinally and transversely for subgrade and crushed base to verify finish grading of course.
- 3. Location and grade stakes for drainage features and retaining walls.
- 4. Location stakes for roadside safety items, permanent and temporary traffic control, and misc. items as determined by the Project Representative.

Original field notes, computations and other records take by the Contractor for the purpose of quantity and progress surveys shall be furnished promptly to the Project Representative and shall be used to the extent necessary in determining the proper amount of payment due to the Contractor.

# 14. MATERIAL SOURCES AND CONSTRUCTION WATER

The Contractor shall be responsible for locating all necessary material sources, including aggregates, earthen borrow and water necessary to complete the work. The Contractor shall be responsible for meeting all transportation and environmental regulations as well as paying any royalties. The Contractor shall provide the Project Representative with written approvals of landowners from whom materials are to be obtained, prior to approval.

The Contractor may use materials from any source, providing the materials have been tested through representative samples and will meet the Specifications.

Water for compaction efforts shall be supplied by the Contractor.

# 15. MATERIALS SALVAGE AND DISPOSAL

Notify the Owner for any material salvaged from the project site not identified in the Contract Documents. The Owner reserves the right to maintain salvaged material at the project site, compensate the Contractor for relocation of salvaged material, or agreed compensation to Owner for material salvaged by the Contractor.

Haul and waste all waste material to a legal site and obey all state, county, and local disposal restrictions and regulations.

#### 16. STORED MATERIALS

Contractor shall use an approved storage area for materials. Materials and/or equipment purchased by the Contractor may be compensated on a monthly basis. For compensation, provide the Project Representative invoices for said materials, shop drawings and/or submittals for approval, and applicable insurance coverage, see General Conditions, Article 9.

#### 17. STAGING AND STOCKPILING AREA

Contractor shall use staging and stockpiling sites for to facilitate the project as approved by the Owner. Contract Documents may show approved staging and stockpiling locations. Notify Owner within 24 hours for approval of staging and stockpiling sites not shown on the Contract Drawings.

#### 18. SECURITY

The Contractor shall provide all security measures necessary to assure the protection of equipment, materials in storage, completed work, and the project in general.

#### 19. CLEANUP

Cleanup for each item of work shall be <u>fully</u> completed and accepted before the item is

Special Provisions Page 11 considered final. If the Contractor fails to perform cleanup within a timely manner the Owner reserves the right to withhold final payment.

Review these Contract Documents for additional Final Cleanup specifications for specific measures, associated with Contractor responsibilities and final payment.

#### 20. ACCESS DURING CONSTRUCTION

Provide access to all public and private roadways and approaches within the project throughout the construction period.

#### 21. CONSTRUCTION TRAFFIC CONTROL

The Contractor is responsible for providing safe construction and work zones within the project limits by implementing the rules, regulations, and practices of the <u>Manual on Uniform Traffic Control Devices</u>, current edition.

#### 22. SANITARY FACILITIES

Provide on-site toilet facilities for employees of Contractor and Sub-Contractors and maintain in a sanitary condition.

#### 23. CONTRACT CLOSEOUT

The Contractor's Superintendent shall maintain at the project site, a "Record Set of Drawings" showing field changes, as-built elevations, unusual conditions encountered during construction, and such other data as required to provide the Owner with an accurate "as constructed" set of record drawings. The Contractor shall furnish the "Record Set" to the Project Representative following the Final Inspection of the Project.

The Contractor's final payment will not be processed until the "Record Set" of drawings are received and approved by the Project Representative.

#### 24. MEASUREMENT AND PAYMENT

Review these Contract Documents for additional Measurement and Payment specifications for definitions. Quantities are listed on the Bid Proposal for Payment Items. Additional material quantities, volumes, and measurements may be shown on the Contract Document drawings and/or specifications.

Unit Price quantities and measurements shown on the Bid Proposal are for bidding and contract purpose only. Quantities and measurements supplied, completed for the project, and verified by the Project Representative shall determine payment. Each unit price will be deemed to include an amount considered by the Contractor to be adequate to cover Contractor's overhead and profit for each bid item.

The Owner or Contractor may make a Claim for an adjustment in Contract Unit Price if

the quantity of any item of Unit Price Work performed by the Contractor <u>differs</u> <u>materially and/or significantly (increase or decrease by 50%)</u> from the estimated quantity indicated on the Bid Proposal.

Lump sum bid item quantities will not be measured. Payment for these lump sum bid proposal items will be paid in full amount listed on the Bid Proposal when accepted by the Project Representative, unless specified otherwise.

# Montana Fish, Wildlife & Parks

# SPECIFICATIONS FOR WORK TECHNICAL PROVISIONS

# **Incorporation of Montana Public Works Technical Specifications.**

The Technical Specifications as found in Montana Public Works Standard Specifications (MPWSS), Sixth Edition, April 2010 and/or current Addendums or Revisions; are hereby incorporated by reference and made a part of this Contract:

# Incorporation of Montana Fish, Wildlife & Parks Technical Specifications and Modifications to MPWSS Technical Specifications.

In addition to the MPWSS Technical Specifications are the following Montana Fish, Wildlife & Parks Technical Specifications (modifications to MPWSS Technical Specifications).

SECTION 01050 -Field Engineering Mobilization/Demobilization SECTION 01450 -Final Cleanup SECTION 01750 -SECTION 01800 -**Erosion and Sediment Control** SECTION 01802-Silt Fence Street Excavation, Backfill, and Compaction SECTION 02230 -**SECTION 02235 -**Crushed Base Course **SECTION 02238-**Drain Rock **Barrier Rocks** SECTION 02241-SECTION 02910-Revegetation SECTION 02930-Signing Concrete Post & Cable Barrier SECTION 03001-

Wheel Stops

SECTION 03321-

#### FIELD ENGINEERING

All applicable portions of this specification section in the MPWSS shall apply with the following additions, deletions and/or modifications.

#### PART 3 EXECUTION

#### 1.1 CONSTRUCTION SURVEY

- A. Engineer will provide survey control (northing/easting), benchmarks(vertical datum), and grade stakes for all designed alignments and profiles, as shown on the project Plans. Engineer will provide one set of stakes prior to the construction of the various project elements. The contractor shall notify the Engineer 72 hours in advance that the site has been prepared and staking is needed to start construction.
- B. Contractor shall perform all additional surveying, staking, recording of data, and calculations as necessary to construct the project from the initial layout to final completion. Reset stakes as many times as necessary to construct the work.
- C. The Engineer will set center alignment stakes and key geometric points and described above in item A. The contractor set reference stakes, based the Engineer's stakes, at 50' intervals on tangent sections and at 25' on horizontal curves or as necessary to construct the work. Additionally, the Contractor shall set reference/slope stakes at PC and PT locations as well as the begin and end of project stationing. Limit grade stake tolerances to +/-0.1'.

# PART 4 MEASUREMENT AND PAYMENT

# Add the following:

A. Construction Surveying is incidental to the work and no separate payment is made for this item.

#### MOBILIZATION/DEMOBILIZATION

#### Added Section.

#### PART 1 GENERAL

#### 1.1 DESCRIPTION

- A. This item shall consist of the prepatory work and operations necessary performed by the Contractor for the movement of personnel, equipment, supplies, and incidentals to and from the work site. The work includes those actions necessary for obtaining necessary permits required for mobilization; for the establishment of all offices and facilities necessary to work on the project; for premiums on contract bonds; for insurance for the contract; and for other work on the various items on the project site. Mobilization costs for subcontracted work shall be considered to be included.
- B. Contractor's cost for administration, bonding, insurance, and site documents shall be included in mobilization and shall not be paid as a separate item.
- C. All equipment moved to the project sites shall be in good mechanical condition and free of fuel, oil, lubrication, or other fuel leaks. The Contractor shall immediately remove any equipment potentially or actually discharging environmentally damaging fluids.
- D. All equipment moved to the project sites shall be thoroughly cleaned before it is brought to the sites to prevent the introduction of weed seeds. Equipment removed from the sites may not be returned to the sites again until it is thoroughly cleaned again.

PART 2 PRODUCTS – NOT USED

PART 3 EXECUTION – NOT USED

PART 4 MEASUREMENT AND PAYMENT

#### 4.1 MEASUREMENT

A. There will be no direct measurement of this item.

#### 4.2 PAYMENT

B. Partial payments for mobilization/demobilization will be made based on the lump sum bid price as follows:

- ➤ 25% of the amount bid for mobilization/demobilization when the Contractor has moved on-site and begun construction activities.
- > 50% of the amount bid for mobilization/demobilization when 25% of the contract amount (exclusive mobilization/demobilization) has been completed.
- > 75% of the amount bid for mobilization/demobilization when 50% of the contract amount (exclusive mobilization/demobilization) has been completed.
- ➤ 100% of the amount bid for mobilization/demobilization when 75% of the contract amount (exclusive mobilization/demobilization) has been completed.

#### FINAL CLEANUP

#### Added Section.

#### PART 1 GENERAL

#### 1.1 DESCRIPTION

A. This work consists of final cleanup of the project site prior to final acceptance.

# PART 2 PRODUCTS – NOT USED

#### PART 3 EXECUTION

#### 3.1 CONTRACTOR RESPONSIBILITES

The contractor shall be responsible for final clean up at the end of the project to a level satisfactory to the owner. All construction debris, no mater how small, shall be collected and removed from the site. All wheel ruts shall be filled in and be leveled to match the adjacent grade and material. Re-seeding or re-sodding, or other re-surfacing may be necessary to repair any construction related impacts or damage.

All survey markings set as control points and boundary corners shall not be disturbed. If the contractor encounters a control point or boundary corner and it is in the way of construction it shall be brought to the attention of the FWP project representative so that it can be avoided or properly preserved. The Project surveyor shall identify control points, whenever possible, with a marking/point to be saved.

All final slopes shall be dressed manually to remove woody debris, accumulated trash and oversized material. Any new slope or topsoil surfaces shall be hand raked to provide a uniform appearance. The contractor shall dress all gravel, pavement and concrete edges to eliminate abrupt edges and provide a smooth transition. All construction related temporary sediment control devices shall be removed as soon as practical.

# PART 4 MEASUREMENT AND PAYMENT

#### 4.1 PAYMENT

Unless specifically noted otherwise, all final cleanup work shall be incidental to other work items in the contract and no separate payment shall be made.

#### EROSION AND SEDIMENT CONTROL

# Added Section.

#### PART 1 GENERAL

#### 1.1 DESCRIPTION

A. This work consists of furnishing, constructing, and maintaining permanent and temporary erosion control and sediment control measures as shown on the project drawings and/or project related construction permits.

#### PART 2 PRODUCTS

#### 2.1 GENERAL

A. Temporary and erosion control products utilized include but are not limited to backfill material; berms; brush barriers; erosion control blankets, bales, wattles, logs, rolls; erosion control culvert pipe; detention basins; fertilizer; geotextile; mulch; plastic lining; riprap; sandbags; seed; silt fence; and water.

#### 2.2 EROSION CONTROL WATTLES

A. Where designated, provide a sediment retention product made from straw and coconut fiber reinforced with a 100% bio-degradable netting. Use wood stakes to secure sediment retention product in place, spacing per the manufacturer's recommendations. An acceptable product is *Sediment Stop*, manufactured by *North American Green*, or approved equal.

#### 2.2 EROSION CONTROL BLANKETS

A. Where designated, provide a sediment retention product made from straw and coconut fiber reinforced with a 100% bio-degradable netting. Use wood stakes to secure sediment retention product in place, spacing per the manufacturer's recommendations. An acceptable product is *BioNet® S150BN<sup>TM</sup>*, manufactured by *North American Green*, or approved equal.

# 2.3 SILT FENCE

A. Where designated, provide silt fencing in accordance with Section 01802 Silt Fence of these specifications.

#### PART 3 EXECUTION

#### 3.1 INSTALLATION

- A. Provide permanent and temporary erosion control measures to minimize erosion and sedimentation during and after construction according to the contract erosion control plan, environmental permits, and as directed by the Project Representative. These erosion control measures shall be designed, implemented, and maintained by the Contractor in accordance with Best Management Practices (BMPs) to control erosion and sediment release from the work site.
- B. Install permanent and temporary erosion control measures according to the Storm Water Pollution Prevention Plan (SWPPP), if applicable, approved construction permits, and erosion control drawings.
- C. When erosion control measures are not functioning as intended, immediately take corrective action.

# PART 4 MEASUREMENT AND PAYMENT

#### 4.1 MEASUREMENT AND PAYMENT

A. All items in this section are incidental to the work and no separate payment is made for these items.

#### **SILT FENCE**

# Added Section.

#### PART 1 GENERAL

#### 1.1 DESCRIPTION

A. Silt fences allow sediment to settle from runoff before water leaves the construction site. This work consists of furnishing and installing a temporary silt fence to control sedimentation and suspended solids during construction at appropriate locations and as shown on the Plans. Fence shall be maintained throughout the construction period and removed in conjunction with the final grading and site stabilization.

# PART 2 PRODUCTS

#### 2.1 GENERAL

- A. Provide a filter fabric geotextile material that meets the requirements of MPWS specification 02110 Geotextiles and as described herein.
- B. Provide support posts spaced not greater than 10 feet center to center. Post shall be either wood posts with a cross sectional area of 1.5"x1.5" or a standard metal tee post.
- C. Fasteners that attach the fabric to the posts shall be No. 10 gauge wire, 50 pound plastic zip ties or approved equal.
- D. Material used to entrench the fabric into native soil shall be compacted aggregated base.

# 2.2 MATERIALS

Table 1. Materials and properties for silt fence construction

Woven Geotextile Fabric Width(in)	Min. Post Length (in)*	Min. Grab Tensile(lbs) (ASTM D 4632)	Min. Trapezoidal Tear Strength ((lbs) (ASTM D 4533)	Min. Permittivity (sec <sup>-1</sup> )(ASTM D4491)	Max. Apparent Open Size (mm)(ASTM D4751)
24	48	100	45	0.1	0.6
36	60	100	45	0.1	0.6

<sup>\*</sup>Posts shall be metal tee post or hardwood posts with a minimum 1-1/2"x1-1/2" thickness

See Section 02110 GEOTEXTILES of MONTANA PUBLIC WORKS STANDARD SPECIFICATIONS for additional information on ASTM Standards references listed in Table 1.

#### PART 3 EXECUTION

#### 3.1 INSTALLATION

- A. Install silt fence parallel to the shoreline around the construction area of disturbance. Silt fence installation is required prior to any and all work below the ordinary high water mark.
- B. Silt fencing shall be placed below the toe of exposed and erodible slopes, down-slope of exposed soil areas, around temporary stockpiles, along streams and channels, and as shown on the Plans.
- C. Fabric shall be attached to the post at the top of the fabric and at least three other points spaced evenly downward.
- D. Post shall have a minimum embedment depth of 18" or to a depth that provides a stable silt fence.
- E. Fabric shall be entrenched into the ground as shown on the on the Plans and to a minimum depth of 6 inches.
- F. Fabric splices where required shall be constructed as shown on the Plans.
- G. Inspect the silt fence daily to ensure sedimentation is controlled and proper function of the erosion control BMP. Immediately correct silt fence deficiencies before continuing with work. If silt fence deficiencies are not corrected, the Contractor may be in violation with approved construction permits and may be issued a stop work order by the Project Represent
- H. Maintain silt fence throughout all work activities until removal approval by the Project Representative. Allow sediment to settle or disperse for 12 hours after construction disturbance prior to removal. Sediment shall be removed when sediment accumulation reaches 1/4 of the barrier height.

#### PART 4 MEASUREMENT AND PAYMENT

#### 4.1 GENERAL

A. Silt Fence will be measured and paid for on a per lineal foot basis.

# STREET EXCAVATION, BACKFILL AND COMPACTION

All applicable portions of this specification section in the MPWSS shall apply with the following additions, deletions and/or modifications.

#### PART 1 GENERAL

#### 1.3 DENSITY CONTROL TESTING

#### A. FIELD DENSITY TESTING

# Delete this section and add the following:

In-place field density tests for quality assurance are at Contractors expense meeting AASHTO T238 (ASTM D2922) and AASHTO T239 (ASTM D3017), Nuclear Densometer Methods. Quality assurance field density testing frequency is once per compacted lift, or as directed by Engineer.

Retesting of failing areas is at the expense of the Contractor.

#### B. LABORATORY MAXIMUM DENSITY and OPTIMUM MOISTURE

# Delete this section and add the following:

Quality assurance tests will be made by the Contractors independent testing laboratory for each on-site natural soil or each source of off-site material, including borrow material, to determine the laboratory maximum density values and optimum compaction moisture content under AASHTO T99 or ASTM D698.

# PART 3 EXECUTION

#### 3.1 CLEARING AND GRUBBING

#### Add the following:

Obtain necessary burning permits if cleared and grubbed material is burned on site. All stumps within construction limits shall be grubbed under this contract.

During the clearing and grubbing portion of the work the contractor shall stock pile sufficient desirable topsoil material for constructing the proposed landscape mounds as shown on the Plans.

#### 3.4 EXCAVATION

# Add the following:

Sheeting, Shoring, and Bracing: Except where trench banks are cut back on a stable slope, provide and maintain all sheeting, shoring, and bracing necessary to protect workers, and to protect adjoining grades and structures from caving, sliding, erosion or other damage in accordance with Occupational Safety and Health Standards (29 CFR Part 1926 – Construction Standards for Excavations), the Site Specific Health and Safety Plan, and other applicable codes and governing authorities.

# PART 4 MEASUREMENT AND PAYMENT

#### 4.1 METHOD OF MEASUREMENT AND PAYMENT

Delete this section and add the following:

#### A. CLEARING AND GRUBBING

1. Clearing and grubbing will not be measured for payment and is considered incidental to other work items in this Contract.

#### B. EXCAVATION AND EMBANKMENT

1. Excavation and embankment will be measured and paid by the lump sum (LPSM).

#### **CRUSHED BASE COURSE**

All applicable portions of this specification section in the MPWSS shall apply with the following additions, deletions and/or modifications.

#### PART 2 PRODUCTS

#### 2.3 GRADATION

Replace Section 2.3 with the following:

A. The Contractor shall use the material from the stockpile shown on Sheet 2 of the Plans to be used as "Crushed Base Course." No further testing of this material is necessary to show that this material meets this specification.

#### PART 3 EXECUTION

# 3.3 FIELD DENSITY REQUIREMENTS

# Add the following:

- D. The Contractor is responsible for providing all compaction testing by an independent testing agency.
- E. Compaction testing locations and frequency will be performed as follows:

<b>Compaction Testing</b>	Location*	Frequency
Subgrade and Subbase	None**	None**
Crushed Base Course	Access Parking	2
	Ramp & Truck/Trailer Parking	2
	Access Road	4

<sup>\*</sup> Station/Offset determined by Engineer

# PART 4 MEASUREMENT AND PAYMENT

# 4.1 METHOD OF MEASUREMENT AND PAYMENT

Crushed base course will be measured and paid for on a per cubic yard basis.

<sup>\*\*</sup>Proof roll subgrade only for observation by Engineer prior to base course placement.

#### **DRAIN ROCK**

# Added Section.

#### PART 1 GENERAL

#### 1.1 DESCRIPTION

A. This work consists of furnishing, placing, and finishing drain rock placement at designated areas on the project drawings or as directed by the Project Representative.

#### PART 2 PRODUCTS

#### 2.1 DRAIN ROCK GRADATION

- A. Furnish drain rock that is rounded to sub-rounded aggregate as shown in Table 1:
- B. The drain rock material must be non-plastic. A minim of 70 percent by weight of the drain rock must have at least one fractured face.

**Table 1. Drain Rock Gradation** 

Sieve Size	Percent Passing
4 inch	100
<sup>3</sup> / <sub>4</sub> inch	0-10
No. 4	0-5

# PART 3 EXECUTION

# 3.1 GENERAL

A. Install drain rock according to the project drawings or as directed by the Project Representative.

#### PART 4 MEASUREMENT AND PAYMENT

#### 4.1 GENERAL

A. Drain rock placement will be measured and paid for a per lineal foot basis.

#### BARRIER ROCKS

# Added Section.

#### PART 1 GENERAL

#### 1.1 DESCRIPTION

A. This work consists of furnishing and/or excavating onsite rocks within the excavated area and placing the same as barrier rocks at designated areas on the project drawings or as directed by the Engineer.

# PART 2 PRODUCTS – NOT USED

# PART 3 EXECUTION

#### 3.1 GENERAL

- A. Furnish hard, durable, angular barrier rock that is resistant to weathering and water action and free of organic or other unsuitable material. During the excavation process, stockpile barrier rock that that meets this specification and use if desired. Do not use shale, rock with shale seams, or other fissured rock that may break into smaller pieces in the process of handling and placing.
- B. Rocks that measure approximately 8 cubic feet (2.5 3.5 feet in nominal diameter as measured on the long axis) shall be classified as Barrier Rock. Embed barrier rocks 1/3 of the diameter below finished or existing grade. Backfill around embedded barrier rocks by tamping with hand tools and/or mechanical equipment. Space barrier rocks at 5 feet clearance as measured from edge to edge.
- C. Install barrier rocks according to the project drawings or as directed by the Engineer.

# PART 4 MEASUREMENT AND PAYMENT

# 4.1 PAYMENT

A. Barrier rock placement will be measured and paid for by the each (EACH).

#### REVEGETATION

All applicable portions of this specification section in the MPWSS shall apply with the following additions, deletions and/or modifications.

#### PART 1 GENERAL

#### 1.1 DESCRIPTION

# Add following:

This work also includes conserving, placing, and finishing topsoil placement at designated areas on the project drawings or as directed by the Engineer.

# PART 2 PRODUCTS

#### 2.1 SEED

# Add the following:

Utilize the following seed mix for all areas to be seeded.

Seed Name	% Pure Live Seed	Lbs. Per Acre
Western Wheatgrass	30	*
Bluebunch Wheatgrass	20	*
Hard Fescue	20	*
Slender Wheatgrass	15	*
Green Needlegrass	15	*

<sup>\*</sup> Drilled Rate = 25 lbs/acre, Broadcast and Hydroseed Rate = 50 lbs/acre

# 2.2 TOPSOIL

# Add the following:

Utilize all salvaged topsoil conserved from clearing and grubbing operations to cover excavation and embankment slopes prior to fertilizing, seeding, or mulching.

#### 2.4 FERTILIZER

Delete this Section.

# PART 4 MEASUREMENT AND PAYMENT

# 4.1 GENERAL

# Delete this section and add the following:

- A. Revegetation will be measured and paid by the lump sum (LPSM) including all labor, equipment, materials and incidentals required for the completion of the work.
- B. Placing conserved topsoil will not be measured for payment and is considered incidental to other work items in this Contract.

#### **SIGNING**

# Added Section.

#### PART 1 GENERAL

#### 1.1 DESCRIPTION

A. This work consists of furnishing and placement and/or removal and reset of signs and sign posts at designated areas on the project drawings or as directed by the Engineer. This work also consists of the mounting and complete installation of FWP supplied signing at designated areas on the project drawings or as directed by the Engineer.

#### PART 2 PRODUCTS

# 2.1 WOOD POSTS

A. Furnish posts from dry no. 1 grade Douglas fir, southern or Ponderosa pine, hemlock, spruce, or western larch conforming to AASHTO M 168. Treat the posts with water-borne preservative ACA, ACZA, or CCA according to AWPA Standard C14 except the minimum preservative retention is 0.40 pounds per cubic foot.

# 2.2 HARDWARE

A. Furnish galvanized steel or aluminum alloy material for lag screws, washers, clip angles, wood screws, shear plates, U-bolts, clamps, bolts, nuts, and other fasteners.

# PART 3 EXECUTION

#### 3.1 GENERAL

A. Sign locations may be changed to fit field conditions as approved by the Engineer. Determine sign support lengths measured from the top of the sign to bottom of the footing. Backfill signs supports and post by tamping with hand tools and/or mechanical equipment. Install sign supports according to the project drawings or as directed by the Engineer.

#### PART 4 MEASUREMENT AND PAYMENT

#### 4.1 PAYMENT

A. Sign post and panel installation (FWP supplied sign panels) will be measured and paid for by the each (EACH).

#### CONCRETE POST AND STEEL CABLE BARRIERS

#### Added Section.

# PART 1 GENERAL

#### 1.1 DESCRIPTION

A. This work consists of transporting and installing repurposed concrete guardrail posts (provided by owner) and steel barrier cable and incidentals to the lines and grades as designated in the project drawings and specifications or as directed by the Project Representative.

#### PART 2 PRODUCTS

# 2.1 REPURPOSED CONCRETE POSTS

- A. Repurposed concrete barrier posts to be furnished by owner, Montana Fish, Wildlife and Parks (FWP), stockpiled onsite and made available to the contractor for the construction of this project.
- B. Posts which exhibit excessive deterioration or cracking shall be brought to the attention of the Project Representative and shall not be installed.

#### 2.2 CABLE

A. Furnish 5/16" galvanized aircraft cable.

# 2.2 HARDWARE

A. Furnish (2) galvanized cable clamps at each end of cable.

#### PART 3 EXECUTION

#### 3.1 INSTALLATION

- **A.** Embed all concrete posts at a spacing of 10' O.C. and at a minimum depth of 2 feet. Assure posts are plumb and are of equal height (approximately 3'). Assure pre-drilled holes are aligned properly for continuous cable installation.
- **B.** Secure galvanized aircraft cable to wood posts through pre-drilled holes. Ensure cable is tight and with minimum deflection but not so tight as to pull posts from plumb orientation. Secure each end with loop around last post and (2) minimum galvanized cable clamps.

C. Provide administrative access openings, where indicated on drawings or as directed by the Project Representative, by providing a closed loop with (2) minimum galvanized cable clamps at each loop.

# PART 4 MEASUREMENT AND PAYMENT

#### 4.1 MEASUREMENT AND PAYMENT

A. Concrete posts w/galvanized aircraft cable will be measured and paid by the number of posts placed (EACH) including all labor, equipment, materials and incidentals required for the completion of the work.

#### WHEEL STOPS

# Added Section.

#### PART 1 GENERAL

#### 1.1 DESCRIPTION

A. This work consists of furnishing and placement of wheel stops at designated areas on the project drawings or as directed by the Project Representative. This work also includes removing and resetting existing wheel stops as directed by the Project Representative.

# PART 2 PRODUCTS

#### 1.1 WHEEL STOPS

A. Furnish pre-fabricated concrete wheel stops 96" in length as designated on the project drawings or as directed by the Project Representative.

#### PART 3 EXECUTION

# 3.1 GENERAL

**A.** Install curb stops at locations as designated on the project drawings or as directed by the Project Representative. Furnish and place No. 5 rebar measuring 3 feet in length to hold curb stops in place. Drive rebar flush with the top of each curb stop.

# PART 4 MEASUREMENT AND PAYMENT

#### 4.1 PAYMENT

A. Wheel stops will be measured and paid for by the each (EACH).