

ADDENDUM #1

Salmon Lake and Placid Lake State Parks Recreational Bicycle Camping Project FWP #7166601.B

Near Seeley Lake, Montana

April 5, 2016

Bidders for the above listed project are hereby notified that the following changes have been made to the bid documents:

1. ***Replace Section 2.2.E of TECHNICAL SPECIFICATION 11/150 CAMPSITE EQUIPMENT as follows:***
 - E. Bicycle Racks shall be as manufactured by Pilot Rock, model SRE/5 or approved equal.

2. ***Replace Section 2.9.B of TECHNICAL SPECIFICATION 11/170 PREMANUFACTURED PICNIC SHELTER as follows:***
 - B. Finish system shall be tested to meet the following criteria:
 1. Humidity resistance per ASTM D2247-02 to 1,000 hours with no loss of adhesion or blistering.

3. ***Replace a portion of SPECIAL PROVISION #5, the section under the heading Grade and Alignment as follows:***

Grade and Alignment – Construction staking will be provided by the Owner.
Staking provided will be as follows:

 - Tent Pads – 2 corners along an edge
 - Trash Receptacles – 2 corners of slab along an edge
 - Food Storage lockers – 2 corners of slab along an edge
 - Picnic Shelter – 2 corners of slab along an edge
 - Fire Ring - 1 point, center of ring
 - Bicycle Racks – 2 points, one at each end
 - Trails – 1 point every 30 feet, center of trail

Stakes will be set in actual locations with reference stakes set at 5 to 10-feet offsets.

Survey will be provided at the Preconstruction Conference. The Contractor is responsible for protection of stakes. Any restaking is the responsibility of the Contractor.

4. *Add SPECIAL PROVISION #16 as follows:*

16. CONSTRUCTION WORK HOURS

Construction work hours are restricted to between 8:00 am and 6:00 pm.

5. *Add SPECIAL PROVISION #17 as follows:*

17. MEMORIAL DAY WEEKEND WORK STOPPAGE

No work is allowed during Memorial Day Weekend, May 28th through May 30th, 2016. These days will not be included in the contract time for this project.

6. *Add SPECIAL PROVISION #18 as follows:*

18. ACCESS TO THE PARK

The water line crossing of the main entrance to the park will be completed in a manner to maintain vehicular access to the entire park at all times.

7. *Add SPECIAL PROVISION #19 as follows:*

19. MATERIALS TESTING

Materials Testing will be provided as specified in the Montana Public Works Specification. The following is a schedule of testing required for this project.

Concrete: 1 set of tests and cylinders per each site

Subgrade Compaction Testing:

Tent Pads – 1 each

Food storage locker slab – 1 each

Trash receptacle slab – 1 each

Picnic shelter slab - 2 each

Crushed Base Course Compaction Testing:

Food storage locker slab – 1 each

Trash receptacle slab – 1 each

Picnic shelter slab - 2 each

It is the Contractor's responsibility to obtain a proctor for each site.

8. *Modify Detail F, Sheet C4 of the DRAWINGS as follows:*

Replace callouts for 4x4 redwood with 4x4 pressure treated.

Add the following note:

Note:

Splicing of 4x4 pressure treated edging is not allowed.

9. *Add a note to Sheet C1 of the DRAWINGS as follows:*

Note:

Remove trees as necessary to facilitate construction along waterline alignment. Tree removal is expected to be required for several trees.

10. *Modify Detail H, Sheet C6 of the DRAWINGS as follows:*

Bury depth shall be modified to be 89-3/8", not 8'-10 3/4".

The reference to "self closing" shall be removed from the yard hydrant call out in the plan view.


Jeffrey L. Larson, P.E.

PLEASE ACKNOWLEDGE RECEIPT OF THIS ADDENDUM ON THE DESIGNATED PLACE IN THE BID FORM **AND ON THE FACE OF THE ENVELOPE.**