

## ADDENDUM NO. 2

---

TO: ALL BIDDERS OF RECORD

PROJECT: Jocko River Trout Hatchery Raceway Replacement

FWP PROJECT #: 7153101  
DATE: June 1, 2016

FROM: Craig Jenneskens P.E., Robert Peccia and Associates  
Troy Monroe P.E. , Montana FWP Project Manager

**Acknowledge receipt of this addendum by inserting its number and date in the Proposal Form and on the Bid Envelope. Failure to do so may subject bidder to disqualification.**

This Addendum forms a part of the Contract Documents. Clarification and/or modifications area as follows:

1. Raceway Inlet Valves (Sheet C106)  
Detail 3 on Sheet C106 incorrectly states to re-use the existing 2-inch raceway inlet valves. The valves shall be replaced with new, per the call-out note on Section A on Sheet C106. Any of the existing inlet piping other than the valves, that is salvageable, shall be re-used, per the call-out note on Section A.
2. Colored Concrete for Show Pond  
The show pond concrete shall also be colored, per the construction note on Sheet S101.
3. Treated Utility Poles (Sheet E101)  
The wood utility poles shall be butt-treated. They are not required to be full-length treated.
4. Electrical Improvements to Feed Shed (Sheet E101)  
In addition to the new lights, outlets and switches for the existing Feed Shed building, electrical improvements shall include a new 8-slot load center or panel board, located inside the Feed Shed. A general duty disconnect shall also be added, and installed on the exterior wall of the building, near the entry door.
5. Feed Shed - Interior Light Fixture (Sheet E101)  
The interior light fixture at the Feed Shed shall be a medium-base porcelain lamp holder, with a heavy duty wire lamp guard (McGill 1433 or equal).
6. Native American Hiring Preference  
CSKT Tribal Ordinance No. 101A is not required for this project due to no Federal funding. However, State Statue (MCA 2-18-111 ) as outlined in 3.4.4.3 of the General Conditions still apply.

(CONT.)

7. Prevailing Wages

*Montana Prevailing Wage Rates for Heavy Construction Services 2016* are required for this project. FWP does not require certification but records need to be kept per Dept. of Labor requirements.

8. American Made

All products must meet the standards listed in the specifications and that are common to the industry. No requirements on the origin of material. Submittals for products are required.

9. On Site Power

A limited number of outside outlets are available for contractor use. Contractor will coordinate with Hatchery personnel prior to use. Contractor will be responsible for keeping roadways and access routes safe and useable.

10. Work Hours

Contractor may contact Hatchery personnel with proposed work hours outside of those listed in the General Conditions. Permission granted from Hatchery personnel will be on a case-by-case basis and not guaranteed.

(END)