

Montana Fish, Wildlife & Parks

SPECIFICATIONS FOR WORK SPECIAL PROVISIONS

Contents:

1. Project Description
2. Project Related Contracts
3. Site Inspection
4. Soils Information
5. Project Representative, Inspections, and Testing
6. Engineering Interpretations
7. Rejected Work
8. Utilities
9. Construction Safety
10. Construction Limits and Areas of Disturbance
11. Decontaminate Construction Equipment
12. Tree Protection and Preservation
13. Construction Surveys
14. Material Sources and Construction Water
15. Materials Salvage and Disposal
16. Stored Materials
17. Staging and Stockpiling Areas
18. Security
19. Cleanup
20. Access During Construction
21. Construction Traffic Control
22. Sanitary Facilities
23. Contract Closeout
24. Measurement and Payment

1. PROJECT DESCRIPTION

The Project involves construction work associated with:

**Rosebud West Fishing Access Site (FAS) 2016 Boat Ramp Replacement & Bank Stabilization Project, Fish, Wildlife & Parks (FWP) Project # 7153401
Located in Forsyth, Rosebud County, MT**

The project generally includes demolition of an existing boat ramp, installing a new boat ramp and placing stabilizing Rip-Rap along the riverbank involving clearing and grubbing, demolition, excavation/embankment construction, grading, gravel base leveling, boat ramp development, and incidentals.

2. PROJECT RELATED CONTACTS

Project contacts are designated as follows:

Owner:

Montana FWP
1420 E. Sixth Ave.
PO Box 200701
Helena, MT 59620-0701

FWP Project Representative:

Thomas M. Mannatt
FWP Project Manager
1522 9th Avenue
Helena, MT 59620
406-841-4006 (wk)
406-431-4031 (cell)
406-841-4004 (fax)

3. SITE INSPECTION

All Bidders should satisfy themselves as to the construction conditions by personal examination of the site described in this document. Bidders are encouraged to make any - investigations necessary to assess the nature of the construction and the difficulties to be encountered, see General Conditions, Article 3.

4. SOILS INFORMATION

Geotechnical investigation work has not been done for this Project. It is the responsibility of the Bidders to conduct all investigations and determine the soil type and digging conditions that may be encountered with this Project prior to bid preparation, see General Conditions, Article 3.

5. PROJECT REPRESENTATIVE, INSPECTIONS, AND TESTING

The Contractor's work will be periodically tested and observed to insure compliance with

the Contract Documents. Complete payment will not be made until the Contractor has demonstrated that the work is complete and has been performed as required. If the Project Representative detects a discrepancy between the work and the requirements of the Contract Documents at any time, up to and including final inspection, such work will not be completely paid for until the Contractor has corrected the deficiency, see General Conditions, Article 9.

The Project Representative will periodically monitor the construction of work to determine if the work is being performed in accordance with the contract requirements. The Project Representative does not have the authority or means to control the Contractor's methods of construction. It is, therefore, the Contractor's responsibility to utilize all methods, equipment, personnel, and other means necessary to assure that the work is installed in compliance with the Drawings and Specifications, and laws and regulations applicable to the work. Any discrepancies noted shall be brought to the Contractor's attention, who shall immediately correct the discrepancy. Failure of the Project Representative to detect a discrepancy will not relieve the Contractor of his ultimate responsibility to perform the work as required, see General Conditions, Article 3.

The Contractor shall inspect the work as it is being performed. Any deviation from the Contract requirements shall be immediately corrected. Prior to any scheduled observation by the Project Representative, the Contractor shall again inspect the work and certify to the Project Representative that he has inspected the work and it meets the requirements of the Contract Documents. The Project Representative may require uncovering of work to verify the work was installed according to the contract documents, see General Conditions, Article 12.

The work will be subject to review by the Project Representative. The results of all such observations, and all contract administration, shall be directed to the Contractor only through the Project Representative.

5.1 Services Required by the Contractor. The Contractor shall provide the following services:

- a. Any field surveys to establish locations, elevations, and alignments as stipulated on the Contract Documents. FWP reserves the right to set preliminary construction staking for the project. The Contractor is responsible to notify FWP for any construction staking discrepancies.
- b. Preparation and certification of all required shop drawings and submittals as described in the General Conditions, Article 3.
- c. All testing requiring the services of a laboratory to determine compliance with the Contract Documents shall be performed by an independent commercial testing laboratory acceptable to the Project Representative. The laboratory shall be staffed with experienced technicians properly equipped, and fully qualified to perform the tests in accordance with the specified standards.

- d. Preparation and submittal of a construction schedule, including submittals, see General Conditions, Article 3. The schedule shall be updated as required, as defined in the Contract Documents.
- e. All Quality Control testing as required by the Contractor's internal policies.
- f. All Quality Assurance testing and/or re-testing as stated in the Contract Documents, see General Conditions, Article 13.

5.2 Services Provided by the Owner. The Owner shall provide the following services at no cost to the Contractor except as required for retests as defined in the Contract Documents.

- a. The Project Representative may check compaction of backfill and surfacing courses using laboratory testing submittal information supplied by the Contractor. These tests are to determine if compaction requirements are being fulfilled in accordance with the Contract Documents. It is ultimately the responsibility of the Contractor to insure that this level of compaction is constant and met in all locations.
- b. Any additional Quality Assurance testing deemed appropriate by the Owner, at the Owner's expense.

6. ENGINEERING INTERPRETATIONS

Timely Engineering decisions on construction activities or results have an important bearing on the Contractor's schedule. When engineering interpretation affects a plan design or specifications change, it should be realized that more than 24 hours may be required to gain the necessary Owner participation in the decision process including time for formal work directive, or change order preparation as required.

7. REJECTED WORK

Any defective work or nonconforming materials or equipment that may be discovered at any time prior to the expiration of the warranty period, shall be removed and replaced with work or materials conforming to the provisions of the Contract Documents, see General Conditions, Article 12. Failure on the part of the Project Representative to condemn or reject bad or inferior work, or to note nonconforming materials or equipment on the Contractor's submittals, shall not be construed to imply acceptance of such work. The Owner shall reserve and retain all its rights and remedies at law against the Contractor and its Surety for correction of any and all latent defects discovered after the guarantee period (MCA 27-2-208).

Only the Project Representative will have the authority to reject work which does not conform to the Contract Documents.

8. UTILITIES

The exact locations of existing utilities that may conflict with the work are not precisely known. It shall be the Contractor's responsibility to contact the owners of the respective utilities and arrange for field location services. **One Call Locators, 1-800-424-5555**

The Contract Documents may show utility locations based on limited field observation and information provided to the Project Representative by others. **The Project Representative cannot guarantee their accuracy.** The Contractor shall immediately notify the Project Representative of any discrepancies with utility locations as shown on the Contract Drawings and/or their bury depths that may in any way affect the intent of construction as scoped in these specifications.

There will be no separate payment for exploratory excavation required to locate underground utilities.

8.1 Notification. The Contractor shall contact, in writing, all public and private utility companies that may have utilities encountered during excavation. The notification includes the following information:

- a. The nature of the work that the Contractor will be performing.
- b. The time, date and location that the Contractor will be performing work that may conflict with the utility.
- c. The nature of work that the utility will be required to perform such as moving a power pole, supporting a pole or underground cable, etc.
- d. Requests for field location and identification of utilities.

A copy of the letter of notification shall be provided to the Project Representative. During the course of construction, the Contractor shall keep the utility companies notified of any change in schedule, or nature of work that differs from the original notification.

8.2 Identification. All utilities that may conflict with the work shall be the Contractor's responsibility to locate before any excavation is performed. Field markings provided by the utility companies shall be preserved by the Contractor until actual excavation commences. All utility locations on the Drawings should be considered approximate and should be verified in the field by the Contractor. The Contractor shall also be responsible for locating all utilities that are not located on the Drawings.

Utilities are depicted on the Contract Documents in accordance with their achieved "Quality Levels," as defined in the American Society of Civil Engineer's Document, ASCE 38, "Standard Guideline for the Collection and Depiction of Existing Subsurface Utility Data." Reliance upon these data for risk management purposes during bidding does not relieve the Contractor, or Utility Owner from following all applicable utility damage prevention statutes, policies, and/or procedures during construction. It is important that the

Contractor investigates and understands the scope of work between the project Owner and Engineer regarding scope of limits of the utility investigations leading to these utility depictions. Definitions of Quality Levels are described as follows:

- a. "QUALITY LEVEL A" – (QLA): LOCATING THROUGH EXCAVATION. QLA data are highly accurate and are obtained by surveying an exposed utility. As such, both horizontal and vertical data are recorded. Survey accuracies are typically set at 15mm (1/2-inch) vertically, and to project survey standards horizontally (typically the same as for topography features), although these survey accuracies and precisions are generally left to the owner to specify in a scope of work. In addition to the applicable standard of care and any other additional standards imposed by commercial indemnity clauses, the accuracy of these location data is also typically guaranteed. Other data typically characterized include material type, surface elevation, utility size/capacity, outside dimensions, and configurations, soil type, and utility condition.
- b. "QUALITY LEVEL B" – (QLB): DESIGNATING. QLB information is obtained through the application of appropriate surface geophysical methods to identify the existence and approximate horizontal location of utilities (a utility's "designation") within the project limits, followed by survey, mapping, and professional review of that designation. Underground utilities are identified by interpretation of received signals generated either actively or passively, and through correlating these received signals with visible objects (QLC) and record data (QLD) to determine function. Designated utilities that can't be identified are labeled as "unknowns." Although approximate has no accuracy associated with it, generally the locations are within inches rather than feet. The more utility congested the area or the deeper the utilities, the less likely it is that the designations will achieve that accuracy. These designations are then surveyed to project accuracies and precisions, typically third-order accuracy similar to other topography features. Note that surveying existing one-call marks does not lead to QLB data, since the genesis of the marks was not under the direct responsible charge of the professional certifying the QLB depictions, and one-call generally does not address unknown utilities, privately owned utilities, utilities without records, abandoned utilities, and so on. Nor does the professional have knowledge of the field technician's qualifications, training, and level of effort.
- c. "QUALITY LEVEL C" – (QLC): SURFACE VISIBLE FEATURE SURVEY. QLC builds upon the QLD information by adding an independent detailed topography site survey for surface-visible appurtenances of subsurface utilities including but not limited to fire hydrants, valves, risers, and manholes. Professional judgment is

used to correlate the QLD data to the surveyed features, thus increasing the reliability of both utility location and existence. It is a function of the professional to determine when records and features do not agree and resolve discrepancies. This may be accomplished by depiction of a utility line at quality level D, effectively bypassing or disregarding (but still depicting) a surveyed structure of unknown origin. Additional resolution may result from consultation with utility owners.

- d. "QUALITY LEVEL D" – (QLD): EXISTING RECORDS RESEARCH. QLD is the most basic level of information. Information is obtained from the review and documentation of existing utility records, verbal accounts, and/or one-call markings (to determine the existence of major active utilities and their approximate locations).

- 8.3 Removal or Relocation of Utilities. All electric power, street lighting, gas, telephone, and television utilities that require relocation will be the responsibility of the utility owner. A request for extending the specified contract time will be considered if utility owners cause delays.
- 8.4 Public Utilities. Water, sewer, storm drainage, and other utilities owned and operated by the public entities shall, unless otherwise specifically requested by the utility owner, be removed, relocated, supported or adjusted as required by the Contractor at the Contractor's expense. All such work shall be in accordance with these Contract Documents, or the Owner's Standard Specifications or written instructions when the work involved is not covered by these Specifications.
- 8.5 Other Utilities. Utilities owned and operated by private individuals, railroads, school districts, associations, or other entities not covered in these Special Provisions shall, unless otherwise specifically requested by the utility owner, be removed, relocated, supported or adjusted as required by the Contractor at the Contractor's expense. All work shall be in accordance with the utility owner's directions, or by methods recognized as being the standard of the industry when directions are not given by the owner of the utility.
- 8.6 Damage to Utilities and Private Property. The Contractor shall protect all utilities and private property and shall be solely responsible for any damage resulting from his construction activities. The Contractor shall hold the Owner and Project Representative harmless from all actions resulting from his failure to properly protect utilities and private property. All damage to utilities shall be repaired at the Contractor's expense to the full satisfaction of the owner of the damaged utility or property. The Contractor shall provide the Owner with a letter from the owner of the damaged utility or property stating that it has been repaired to the utility owner's full satisfaction.

- 8.7 Structures. The Contractor shall exercise every precaution to prevent damage to existing buildings or structures in the vicinity of his work. In the event of such damages, he shall repair them to the satisfaction of the owner of the damaged structure at no cost to the Owner.
- 8.8 Overhead Utilities. The Contractor shall use extreme caution to avoid a conflict, contact, or damage to overhead utilities, such as power lines, streetlights, telephone lines, television lines, poles, or other appurtenances during the course of construction of this project.
- 8.9 Buried Gas Lines. The Contractor shall provide some means of overhead support for buried gas lines exposed during trenching to prevent rupture in case of trench caving.
- 8.10 Pavement Removal. Where trench excavation or structure excavation requires the removal of curb and gutter, concrete sidewalks, or asphalt or concrete pavement, the pavement or concrete shall be cut in a straight line parallel to the edge of the excavation by use of a spade-bitted air hammer, concrete saw, colter wheel, or similar approved equipment to obtain a straight, square clean break. Pavement cuts shall be 2 feet wider than the actual trench opening.
- 8.11 Survey Markers and Monuments. The Contractor shall use every care and precaution to protect and not disturb any survey marker or monuments, such as those that might be located at lot or block corners, property pins, intersection of street monuments or addition line demarcation. Such protection includes markings with flagged high lath and close supervision. No monuments shall be disturbed without prior approval of the Project Representative. Any survey marker or monument disturbed by the Contractor during the construction of the project shall be replaced at no cost to the Owner by a licensed land surveyor.
- 8.12 Temporary Utilities. The Contractor shall provide all temporary electrical, lighting, telephone, heating, cooling, ventilating, water, sanitary, fire protection, and other utilities and services necessary for the performance of the work. All fees, charges, and other costs associated therewith shall be paid for by the Contractor.

9. CONSTRUCTION SAFETY

The Contractor shall be solely and completely responsible for conditions of the jobsite, including safety of all persons (including employees and subcontractors) and property during performance of the work. This requirement shall apply continuously and not be limited to normal working hours. Safety provisions shall conform to U.S. Department of

Labor (OSHA), and all other applicable federal, state, county, and local laws, ordinances, codes, and regulations. Where any of these are in conflict, the more stringent requirement shall be followed. The Contractor's failure to thoroughly familiarize himself with the aforementioned safety provisions shall not relieve them from compliance with the obligations and penalties set forth therein, see General Conditions, Article 10.

10. CONSTRUCTION LIMITS AND AREAS OF DISTURBANCE

- 10.1 Construction Limits. Where construction easements or property lines, are not specifically called out on the Contract Documents, limit the construction disturbance to ten (10) feet, when measured from the edge of the slope stake grading, or to the adjacent property line, whichever is less. Disturbance and equipment access beyond this limit is not allowed without the written approval of both the Project Representative and the Owner of the affected property. If so approved, disturbance beyond construction limits shall meet all requirements imposed by the landowner; this includes existing roads used and/or improved as well as the construction of new access roads. Special construction, reclamation, or post-construction reclamation or other closure provisions required by the landowner on access roads beyond the construction limits shall be performed by the Contractor at no additional cost to the Owner.
- 10.2 Areas of Disturbances. Approved areas of disturbance are those areas disturbed by construction activities within the construction limits and along designated or approved access routes. Such areas may require reclamation and revegetation operations, including grading to the original contours, top soiling with salvaged or imported topsoil, seeding, fertilizing, and mulching as specified herein. Other areas that are disturbed by the Contractor's activities outside of the limits noted above will be considered as site damage or unapproved areas of disturbance, see General Conditions, Articles 3 and 10. This includes areas selected by the Contractor outside the defined construction limits for mobilization, offices, equipment, or material storage.

11. DECONTAMINATE CONSTRUCTION EQUIPMENT

Power wash all construction equipment entering the project site to prevent the spread of noxious weeds and aquatic invasive species. This applies to all FWP projects, whether or not individual construction permits specifically address cleaning of equipment.

12. TREE PROTECTION AND PRESERVATION

The Contractor and the Owner shall individually inspect all trees within the project construction limits prior to construction. The Owner shall determine which trees are to be removed and which trees are to be preserved. Construction of the grading, utilities and various roadway facilities must not significantly damage the trees root system or hinder it's chances for survival. Reasonable variations from the Contract Documents, as directed by the Project Representative, may be employed to ensure the survival of

trees.

13. CONSTRUCTION SURVEYS

The Contractor will be responsible for all layout and construction staking utilizing the Project Representative's existing control and coordinate data for the project. Dimensions and elevations indicated in layout of work shall be verified by the Contractor. Discrepancies between Drawings, Specifications, and existing conditions shall be referred to the Project Representative for adjustment before work is performed.

The Project Representative may set location and grade stakes prior to construction; however, it is ultimately the responsibility of the Contractor to check and verify all construction staking for the project.

Existing survey control (horizontal and vertical) has been set for use in the design and ultimately the construction of these improvements. A listing of the coordinates and vertical elevation for each of these control points may be included in the project drawings.

The Contractor will be responsible for preserving and protecting the survey control until proper referencing by the Contractor has been completed. Any survey control obliterated, removed, or otherwise lost during construction will be replaced at the Contractor's expense.

Contractor shall be aware of property pins and survey monuments. Damage to these pins will require replacement of such by a registered land surveyor at no cost to the owner.

The Contractor shall provide construction staking from the Contractor's layouts and the control points. Contractor's construction staking includes at a minimum:

1. Slope stakes located at critical points as determined by the Project Representative.
2. Blue tops every longitudinally and transversely for subgrade and crushed base to verify finish grading of course.
3. Location and grade stakes for drainage features and retaining walls.
4. Location stakes for roadside safety items, permanent and temporary traffic control, and misc. items as determined by the Project Representative.

Original field notes, computations and other records take by the Contractor for the purpose of quantity and progress surveys shall be furnished promptly to the Project Representative and shall be used to the extent necessary in determining the proper amount of payment due to the Contractor.

14. MATERIAL SOURCES AND CONSTRUCTION WATER

The Contractor shall be responsible for locating all necessary material sources, including

aggregates, earthen borrow and water necessary to complete the work. The Contractor shall be responsible for meeting all transportation and environmental regulations as well as paying any royalties. The Contractor shall provide the Project Representative with written approvals of landowners from whom materials are to be obtained, prior to approval.

The Contractor may use materials from any source, providing the materials have been tested through representative samples and will meet the Specifications.

Water for compaction efforts shall be supplied by the Contractor.

15. MATERIALS SALVAGE AND DISPOSAL

Notify the Owner for any material salvaged from the project site not identified in the Contract Documents. The Owner reserves the right to maintain salvaged material at the project site, compensate the Contractor for relocation of salvaged material, or agreed compensation to Owner for material salvaged by the Contractor.

Haul and waste all waste material to a legal site and obey all state, county, and local disposal restrictions and regulations.

16. STORED MATERIALS

Contractor shall use an approved storage area for materials. Materials and/or equipment purchased by the Contractor may be compensated on a monthly basis. For compensation, provide the Project Representative invoices for said materials, shop drawings and/or submittals for approval, and applicable insurance coverage, see General Conditions, Article 9.

17. STAGING AND STOCKPILING AREA

Contractor shall use staging and stockpiling sites for to facilitate the project as approved by the Owner. Contract Documents may show approved staging and stockpiling locations. Notify Owner within 24 hours for approval of staging and stockpiling sites not shown on the Contract Drawings.

18. SECURITY

The Contractor shall provide all security measures necessary to assure the protection of equipment, materials in storage, completed work, and the project in general.

19. CLEANUP

Cleanup for each item of work shall be fully completed and accepted before the item is considered final. If the Contractor fails to perform cleanup within a timely manner the

Owner reserves the right to withhold final payment.

Review these Contract Documents for additional Final Cleanup specifications for specific measures, associated with Contractor responsibilities and final payment.

20. ACCESS DURING CONSTRUCTION

Provide access to all public and private roadways and approaches within the project throughout the construction period.

21. CONSTRUCTION TRAFFIC CONTROL

The Contractor is responsible for providing safe construction and work zones within the project limits by implementing the rules, regulations, and practices of the Manual on Uniform Traffic Control Devices, current edition.

22. SANITARY FACILITIES

Provide on-site toilet facilities for employees of Contractor and Sub-Contractors and maintain in a sanitary condition.

23. CONTRACT CLOSEOUT

The Contractor's Superintendent shall maintain at the project site, a "Record Set of Drawings" showing field changes, as-built elevations, unusual conditions encountered during construction, and such other data as required to provide the Owner with an accurate "as constructed" set of record drawings. The Contractor shall furnish the "Record Set" to the Project Representative following the Final Inspection of the Project.

The Contractor's final payment will not be processed until the "Record Set" of drawings are received and approved by the Project Representative.

24. MEASUREMENT AND PAYMENT

Review these Contract Documents for additional Measurement and Payment specifications for definitions. Quantities are listed on the Bid Proposal for Payment Items. Additional material quantities, volumes, and measurements may be shown on the Contract Document drawings and/or specifications.

Unit Price quantities and measurements shown on the Bid Proposal are for bidding and contract purpose only. Quantities and measurements supplied, completed for the project, and verified by the Project Representative shall determine payment. Each unit price will be deemed to include an amount considered by the Contractor to be adequate to cover Contractor's overhead and profit for each bid item.

The Owner or Contractor may make a Claim for an adjustment in Contract Unit Price if the quantity of any item of Unit Price Work performed by the Contractor differs

materially and/or significantly (increase or decrease by 50%) from the estimated quantity indicated on the Bid Proposal.

Lump sum bid item quantities will not be measured. Payment for these lump sum bid proposal items will be paid in full amount listed on the Bid Proposal when accepted by the Project Representative, unless specified otherwise.

Montana Fish, Wildlife & Parks

SPECIFICATIONS FOR WORK TECHNICAL PROVISIONS

Incorporation of Montana Public Works Technical Specifications.

The Technical Specifications as found in Montana Public Works Standard Specifications (MPWSS), Sixth Edition, April 2010 and/or current Addendums or Revisions; are hereby incorporated by reference and made a part of this Contract:

Incorporation of Montana Fish, Wildlife & Parks Technical Specifications and Modifications to MPWSS Technical Specifications.

In addition to the MPWSS Technical Specifications are the following Montana Fish, Wildlife & Parks Technical Specifications (modifications to MPWSS Technical Specifications).

SECTION 01050 -	Field Engineering
SECTION 01450 -	Mobilization/Demobilization
SECTION 01750 -	Final Cleanup
SECTION 01800 -	Erosion and Sediment Control
SECTION 01801-	Turbidity Curtain
SECTION 02230 -	Street Excavation, Backfill, and Compaction
SECTION 02236-	Gravel Leveling Course
SECTION 02238-	Drain Rock
SECTION 02240-	Rip-Rap
SECTION 02910-	Revegetation
SECTION 03310-	Structural Concrete
SECTION 03311-	Push-In-Slab Concrete Boat Ramp

SECTION 01050

FIELD ENGINEERING

All applicable portions of this specification section in the MPWSS shall apply with the following additions, deletions and/or modifications.

PART 3 EXECUTION

1.1 CONSTRUCTION SURVEY

- A. Engineer will provide survey control (northing/easting), benchmarks(vertical datum), and grade stakes for all designed alignments and profiles, as shown on the project Plans. Engineer will provide one set of stakes prior to the construction of the various project elements. The contractor shall notify the Engineer 72 hours in advance that the site has been prepared and staking is needed to start construction.
- B. Contractor shall perform all additional surveying, staking, recording of data, and calculations as necessary to construct the project from the initial layout to final completion. Reset stakes as many times as necessary to construct the work.
- C. The Engineer will set center alignment stakes and key geometric points and described above in item A. The contractor set reference stakes, based the Engineer's stakes, at 50' intervals on tangent sections and at 25' on horizontal curves or as necessary to construct the work. Additionally, the Contractor shall set reference/slope stakes at PC and PT locations as well as the begin and end of project stationing. Limit grade stake tolerances to +/-0.1'.

PART 4 MEASUREMENT AND PAYMENT

Add the following:

- A. Construction Surveying is incidental to the work and no separate payment is made for this item.

END OF SECTION 01050

SECTION 01450

MOBILIZATION/DEMOBILIZATION

Added Section.

PART 1 GENERAL

1.1 DESCRIPTION

- A. This item shall consist of the preparatory work and operations necessary performed by the Contractor for the movement of personnel, equipment, supplies, and incidentals to and from the work site. The work includes those actions necessary for obtaining necessary permits required for mobilization; for the establishment of all offices and facilities necessary to work on the project; for premiums on contract bonds; for insurance for the contract; and for other work on the various items on the project site. Mobilization costs for subcontracted work shall be considered to be included.
- B. Contractor's cost for administration, bonding, insurance, and site documents shall be included in mobilization and shall not be paid as a separate item.
- C. All equipment moved to the project sites shall be in good mechanical condition and free of fuel, oil, lubrication, or other fuel leaks. The Contractor shall immediately remove any equipment potentially or actually discharging environmentally damaging fluids.
- D. All equipment moved to the project sites shall be thoroughly cleaned before it is brought to the sites to prevent the introduction of weed seeds. Equipment removed from the sites may not be returned to the sites again until it is thoroughly cleaned again.

PART 2 PRODUCTS – NOT USED

PART 3 EXECUTION – NOT USED

PART 4 MEASUREMENT AND PAYMENT

4.1 MEASUREMENT

- A. There will be no direct measurement of this item.

4.2 PAYMENT

- B. Partial payments for mobilization/demobilization will be made based on the lump sum bid price as follows:

- 25% of the amount bid for mobilization/demobilization when the Contractor has moved on-site and begun construction activities.
- 50% of the amount bid for mobilization/demobilization when 25% of the contract amount (exclusive mobilization/demobilization) has been completed.
- 75% of the amount bid for mobilization/demobilization when 50% of the contract amount (exclusive mobilization/demobilization) has been completed.
- 100% of the amount bid for mobilization/demobilization when 75% of the contract amount (exclusive mobilization/demobilization) has been completed.

END OF SECTION 01450

SECTION 01750

FINAL CLEANUP

Added Section.

PART 1 GENERAL

1.1 DESCRIPTION

- A. This work consists of final cleanup of the project site prior to final acceptance.

PART 2 PRODUCTS – NOT USED

PART 3 EXECUTION

3.1 CONTRACTOR RESPONSIBILITIES

The contractor shall be responsible for final clean up at the end of the project to a level satisfactory to the owner. All construction debris, no matter how small, shall be collected and removed from the site. All wheel ruts shall be filled in and be leveled to match the adjacent grade and material. Re-seeding or re-sodding, or other re-surfacing may be necessary to repair any construction related impacts or damage.

All survey markings set as control points and boundary corners shall not be disturbed. If the contractor encounters a control point or boundary corner and it is in the way of construction it shall be brought to the attention of the FWP project representative so that it can be avoided or properly preserved. The Project surveyor shall identify control points, whenever possible, with a marking/point to be saved.

All final slopes shall be dressed manually to remove woody debris, accumulated trash and oversized material. Any new slope or topsoil surfaces shall be hand raked to provide a uniform appearance. The contractor shall dress all gravel, pavement and concrete edges to eliminate abrupt edges and provide a smooth transition. All construction related temporary sediment control devices shall be removed as soon as practical.

PART 4 MEASUREMENT AND PAYMENT

4.1 PAYMENT

Unless specifically noted otherwise, all final cleanup work shall be incidental to other work items in the contract and no separate payment shall be made.

END OF SECTION 01750

SECTION 01800

EROSION AND SEDIMENT CONTROL

Added Section.

PART 1 GENERAL

1.1 DESCRIPTION

- A. This work consists of furnishing, constructing, and maintaining permanent and temporary erosion control and sediment control measures as shown on the project drawings and/or project related construction permits.

PART 2 PRODUCTS

2.1 GENERAL

- A. Temporary and erosion control products utilized include but are not limited to backfill material; berms; brush barriers; erosion control blankets, bales, wattles, logs, rolls; erosion control culvert pipe; detention basins; fertilizer; geotextile; mulch; plastic lining; riprap; sandbags; seed; silt fence; and water.

2.2 EROSION CONTROL WATTLES

- A. Where designated, provide a sediment retention product made from straw and coconut fiber reinforced with a 100% bio-degradable netting. Use wood stakes to secure sediment retention product in place, spacing per the manufacturer's recommendations. An acceptable product is *Sediment Stop*, manufactured by *North American Green*, or approved equal.

2.2 EROSION CONTROL BLANKETS

- A. Where designated, provide a sediment retention product made from straw and coconut fiber reinforced with a 100% bio-degradable netting. Use wood stakes to secure sediment retention product in place, spacing per the manufacturer's recommendations. An acceptable product is *BioNet® S150BNTM*, manufactured by *North American Green*, or approved equal.

2.3 SILT FENCE

- A. Where designated, provide silt fencing in accordance with Section 01802 Silt Fence of these specifications.

PART 3 EXECUTION

3.1 INSTALLATION

- A. Provide permanent and temporary erosion control measures to minimize erosion and sedimentation during and after construction according to the contract erosion control plan, environmental permits, and as directed by the Project Representative. These erosion control measures shall be designed, implemented, and maintained by the Contractor in accordance with Best Management Practices (BMPs) to control erosion and sediment release from the work site.
- B. Install permanent and temporary erosion control measures according to the Storm Water Pollution Prevention Plan (SWPPP), if applicable, approved construction permits, and erosion control drawings.
- C. When erosion control measures are not functioning as intended, immediately take corrective action.

PART 4 MEASUREMENT AND PAYMENT

4.1 MEASUREMENT AND PAYMENT

- A. All items in this section are incidental to the work and no separate payment is made for these items.

END OF SECTION 01800

SECTION 01801

FLOATING TURBIDITY CURTAIN

Added Section.

PART 1 GENERAL

1.1 DESCRIPTION

- A. This work consists of furnishing and installing a floating turbidity curtain to control sedimentation and suspended solids during underwater construction methods.

PART 2 PRODUCTS

2.1 GENERAL

- A. Provide a turbidity curtain with a geotextile material curtain, floatation boom, and anchorage system.
- B. Provide a woven geotextile material as approved for turbidity containment by manufacture's recommendations.
- C. An acceptable floating turbidity curtain product is *Layfield Turbidity Curtains*, or approved equal. www.layfield.com, (800) 796-6868

PART 3 EXECUTION

3.1 INSTALLATION

- A. Install turbidity curtain parallel to the shoreline around the construction area of disturbance. Turbidity curtain installation is required prior to any and all work below the ordinary high water mark.
- B. Extend the turbidity curtain to the lake bottom at all installation locations.
- C. Provide flexible flotation buoys for the top of the turbidity curtain.
- D. Provide an anchorage system consisting of load lines attached to the bottom of the turbidity curtain. Place anchors every 50' connected to the top of the floatation buoy.
- E. Inspect the turbidity curtain daily to ensure sedimentation is controlled and proper function of the erosion control BMP. Immediately correct turbidity curtain deficiencies before continuing with work. If turbidity curtain deficiencies are not

corrected, the Contractor may be in violation with approved construction permits and may be issued a stop work order by the Project Represent

- F. Maintain turbidity curtain throughout all work activities until removal approval by the Project Representative. Allow sediment to settle or disperse for 12 hours after construction disturbance prior to removal.

PART 4 MEASUREMENT AND PAYMENT

4.1 GENERAL

- A. Turbidity curtain will be measured and paid by the lump sum (LPSM) including all labor, equipment, materials, and incidentals required for the completion of the work.

END OF SECTION 01801

SECTION 02230

STREET EXCAVATION, BACKFILL AND COMPACTION

All applicable portions of this specification section in the MPWSS shall apply with the following additions, deletions and/or modifications.

PART 1 GENERAL

1.3 DENSITY CONTROL TESTING

A. FIELD DENSITY TESTING

Delete this section and add the following:

In-place field density tests for quality assurance are at Contractors expense meeting AASHTO T238 (ASTM D2922) and AASHTO T239 (ASTM D3017), Nuclear Densometer Methods. Quality assurance field density testing frequency is once per compacted lift, or as directed by Engineer.

Retesting of failing areas is at the expense of the Contractor.

B. LABORATORY MAXIMUM DENSITY and OPTIMUM MOISTURE

Delete this section and add the following:

Quality assurance tests will be made by the Contractors independent testing laboratory for each on-site natural soil or each source of off-site material, including borrow material, to determine the laboratory maximum density values and optimum compaction moisture content under AASHTO T99 or ASTM D698.

PART 3 EXECUTION

3.1 CLEARING AND GRUBBING

Add the following:

Obtain necessary burning permits if cleared and grubbed material is burned on site. All stumps within construction limits shall be grubbed under this contract.

During the clearing and grubbing portion of the work the contractor shall stock pile sufficient desirable topsoil material for constructing the proposed landscape mounds as shown on the Plans.

3.4 EXCAVATION

Add the following:

Sheeting, Shoring, and Bracing: Except where trench banks are cut back on a stable slope, provide and maintain all sheeting, shoring, and bracing necessary to protect workers, and to protect adjoining grades and structures from caving, sliding, erosion or other damage in accordance with Occupational Safety and Health Standards (29 CFR Part 1926 – Construction Standards for Excavations), the Site Specific Health and Safety Plan, and other applicable codes and governing authorities.

PART 4 MEASUREMENT AND PAYMENT

4.1 METHOD OF MEASUREMENT AND PAYMENT

Delete this section and add the following:

A. CLEARING AND GRUBBING

1. Clearing and grubbing will not be measured for payment and is considered incidental to other work items in this Contract.

B. EXCAVATION AND EMBANKMENT

1. Excavation and embankment will be measured and paid by the lump sum (LPSM).

END OF SECTION 02230

SECTION 02236

GRAVEL LEVELING COURSE

Added Subsection.

PART 1 GENERAL

1.1 DESCRIPTION

- B. This work also consists of placing clean, screened gap-graded gravel leveling course beneath push-in concrete boat ramp slab.

PART 2 PRODUCTS

2.1 GRAVEL LEVELING COURSE GRADATION

- A. Furnish gravel leveling course that is crushed aggregate as shown in Table 1. The gravel leveling course must not contain other deleterious material, such as shale, alkali, mica, or soft flaky particles.

Table 1. Gravel Leveling Course Gradation

Sieve Size	Percent Passing
1"	100
3/4"	90-100
3/8"	20-55
No. 4	0-10
No. 8	0-5

PART 3 EXECUTION

3.1 PLACEMENT AND SPREADING

- A. Place material to specified depth as indicated on the project drawings. Deposit and spread the material in a uniform layer and screed to make a uniform surface at the specified boat ramp grade as indicated on the project drawings.
- B. Perform compaction efforts by mechanical tamping as approved by the Project Representative.

PART 4 MEASUREMENT AND PAYMENT

4.1 GRAVEL LEVELING COURSE

- A. Gravel Leveling Course will not be measured for payment and is considered incidental to other work items in this Contract.

END OF SECTION 02236

SECTION 02238

DRAIN ROCK

Added Section.

PART 1 GENERAL

1.1 DESCRIPTION

- A. This work consists of furnishing, placing, and finishing drain rock placement at designated areas on the project drawings or as directed by the Project Representative.

PART 2 PRODUCTS

2.1 DRAIN ROCK GRADATION

- A. Furnish drain rock that is rounded to sub-rounded aggregate as shown in Table 1:
- B. The drain rock material must be non-plastic. A minimum of 70 percent by weight of the drain rock must have at least one fractured face.

Table 1. Drain Rock Gradation

Sieve Size	Percent Passing
4 inch	100
¾ inch	0-10
No. 4	0-5

PART 3 EXECUTION

3.1 GENERAL

- A. Install drain rock according to the project drawings or as directed by the Project Representative.

PART 4 MEASUREMENT AND PAYMENT

4.1 GENERAL

- A. Drain rock placement will be measured and paid for a per lineal foot basis.

END OF SECTION 02238

SECTION 02242

RIP-RAP

Added Section.

PART 1 GENERAL

1.1 DESCRIPTION

- A. This work shall consist of the construction of loose rock rip-rap revetments and blankets, including filter layers or bedding where specified.

PART 2 PRODUCTS

2.1 ROCK

A. General

Rock for rock rip-rap shall be obtained from designated sources or, shall conform to the following specifications:

Individual rock fragments shall be dense, sound and free from cracks, seams and other defects conducive to accelerated weathering. The rock fragments shall be angular to sub-rounded in shape. The least dimension of an individual rock fragment shall be not less than one-third the greatest dimension of the fragment.

Unless otherwise specified and except as provided below, the rock shall have the following properties:

- a. Bulk specific gravity (saturated surface-dry basis) not less than 2.5.
- b. Absorption not more than 2 percent.
- c. Soundness: Weight loss in 5 cycles not more than 10 percent when sodium sulfate and 15 percent when magnesium sulfate is used.

The bulk specific gravity and absorption shall be determined by ASTM Method C 127. The soundness shall be performed by ASTM Method C 88 for coarse aggregate modified as follows:

The test sample shall not be separated into fractions. It shall consist of 5000 + 300 grams of rock fragments, reasonably uniform in size and shape and weighing approximately 100 grams each, obtained by breaking the rock and selecting fragments of the required size.

After the sample has been dried, following completion of the final test cycle and washing to remove the sodium sulfate or magnesium sulfate, the loss of weight shall be determined by subtracting from the original weight of the sample the final weight of all fragments which have not been broken into three or more pieces.

The report shall show the percentage loss of weight and the results of the qualitative examination.

Rock that fails to meet the requirements stated in a, b, and c above, may be accepted only if similar rock from the same source has been demonstrated to be sound after five years of service under conditions of weather, wetting and drying, icing, and erosive forces similar to those anticipated for the rock to be installed under this specification.

B. Grading

The rock shall conform to the specified grading limits after it has been placed in the riprap.

The rock shall be free from dirt, clay, sand rock fines and other materials not meeting the required gradation limits.

At least 30 days prior to the delivery of rock from other than designated sources, the Contractor shall designate in writing the source from which they intend to obtain the rock. The Contractor will also provide satisfactory documentation to the technician that the material meets the requirements of the specification. The Contractor shall provide the technician free access to the source for obtaining samples for testing. The size and grading of the rock shall be as specified in the special provisions.

Rock from the designated sources shall be excavated, selected and processed as necessary to meet the quality and grading requirements in the special provisions. The rock shall conform to the specified grading when installed as Class I or Class III riprap.

Class I Rip-Rap Gradation

Size	% Passing
12 inch	100
9 inch	60-100
6 inch	30-50
3 inch	10-35
1.5 inch	0-25

Class III Random Rip-Rap Gradation

Weight of Stone	Equivalent Sphere Diameter ¹	% of Total WT That Must Be Smaller Than Given Size
2000 pounds	2.90 feet	100
1400 pounds	2.61 feet	70-90
700 pounds	2.06 feet	40-60
40 pounds	0.79 feet	0-10

Notes:

1. Based on unit weight of 156 pounds per cubic foot

2.2 FILTER AND BEDDING MATERIALS

When required, granular filter and bedding materials shall, unless otherwise specified, conform to Montana Construction Specification MT-117, Drainfill and Filters.

PART 3 EXECUTION

3.1 GENERAL

- A. Furnish hard, durable, and angular in shape rock that is resistant to weathering and water action and free from overburden, spoil, and organic or other unsuitable material. During the excavation process, Do not use rounded stone or boulders from a streambed source as riprap. Angular faces of stone shall inter-lock to provide a stable surface.

3.2 SUBSURFACE PREPARATION

The subgrade surfaces on which the riprap or bedding course is to be placed shall be cut or filled and graded to the lines and grades shown on the drawings. When fill to subgrade lines is required, it shall consist of approved materials and shall conform to the requirements of the specified class of fill.

Riprap shall not be placed until the foundation preparation is completed and the subgrade surfaces have been inspected and approved by the Technician.

3.3 EQUIPMENT – PLACED ROCK RIPRAP

The rock shall be placed by equipment on the surfaces and to the depths specified. The riprap shall be constructed to the full course thickness in one operation and in such a manner as to avoid serious displacement of the underlying materials. The rock shall be delivered and placed in a manner that will insure that the riprap in place shall be reasonably homogeneous with the larger rocks uniformly distributed and firmly in contact one to another with the smaller rocks and spalls filling the voids between the larger rocks.

Riprap shall be placed in a manner to prevent damage to structures. Hand placing will be required to the extent necessary to prevent damage to the permanent works.

3.4 HAND – PLACED RIPRAP

The rock shall be placed by hand on the surfaces and to the depths specified. It shall be securely bedded with the larger rocks firmly in contact one to another. Spaces between the larger rocks shall be filled with smaller rocks and spalls. Smaller rocks shall not be grouped as a substitute for larger rock. Flat slab rock shall be laid on edge.

3.4 FILTER LAYERS OR BEDDING

When filter layers or bedding beneath riprap is specified, the filter or bedding material shall be spread uniformly on the prepared subgrade surfaces to the depth specified. Compaction of filter layers or bedding will not be required, but the surface of such layers shall be finished reasonably free of mounds, dips or windrows.

When a geotextile filter is specified, the material used shall be non-woven and meet the requirements as outlined in Table 1. Geotextile shall be joined by over-lapping a minimum distance of 18 inches. Anchoring of the fabric is not required but care shall be taken to minimize displacement.

Rock riprap shall not be dropped from a height greater than three feet on geotextile. Sufficient hand work shall be done to produce a dense section with a neat and uniform surface.

TABLE 1. REQUIREMENTS FOR NONWOVEN GEOTEXTILES

PROPERTY	TEST METHOD	Class I	Class II
Weight - Typical	ASTM D-5261	8.0 oz/sy	10 oz/sy
Tensile Strength	ASTM D-4632	205 lbs	230 lbs
Elongation @ Break	ASTM D-4632	50%	50%
Mullen Burst*	ASTM D-3786*	350 psi	500 psi
Puncture Strength*	ASTM D-4833*	110 lbs	120 lbs
CBR Puncture	ASTM D-6241	500 lbs	700 lbs
Trapezoidal Tear	ASTM D-4533	80 lbs	95 lbs
Apparent Opening Size	ASTM D-4751	80 US Sieve	100 US Sieve
Permittivity	ASTM D-4491	1.35 Sec-1	1.2 Sec-1
Water Flow Rate	ASTM D-4491	90 g/min/sf	80 g/min/sf
UV Resistance @ 500 Hours	ASTM D-4355	70%	70%

*Historical averages (current values not available): Mullen Burst Strength ASTM D-3786 is no longer recognized by ASTM D-35 on Geo-synthetics as an acceptable test method. Puncture Strength ASTM D-4833 is not recognized by AASHTO M288 and has been replaced with CBR Puncture ASTM D-6241.

Use Class I for $d_{50} \leq 15''$

Use Class II for $d_{50} \geq 16''$

PART 4 MEASUREMENT AND PAYMENT

4.1 PAYMENT

Measurement and payment will be made to the nearest cubic yard and will be based on the neat Lines shown on the drawings.

Such payment will constitute full compensation for all materials, labor, equipment, tools, and all other items necessary and incidental to the completion of the work.

Compensation for geotextile or any other item of work shown on the drawings or described in the special provisions but not listed on the bid schedule will be considered incidental to and included in the pay items listed on the bid schedule.

PART 5 SUBMITTALS REQUIRED

- Geotextiles
- The Contractor shall designate in writing the source from which they intend to obtain the rock.
- When other than pre-approved rock sources are selected for use, site specific test results shall be submitted demonstrating compliance with Section 2 of this specification.

Submittals are to be received by the Contracting Officer a minimum of 15 days prior to the start of placing rock material.

END OF SECTION 02241

SECTION 02910

REVEGETATION

All applicable portions of this specification section in the MPWSS shall apply with the following additions, deletions and/or modifications.

PART 1 GENERAL

1.1 DESCRIPTION

Add following:

Areas that have been disturbed during construction shall be revegetated to prevent erosion in conformance with the specification contained within this Section. This work also includes conserving, placing, and finishing topsoil placement at designated areas on the project drawings or as directed by the Engineer.

PART 2 PRODUCTS

2.1 SEED

Add the following:

Utilize the following seed mix for all areas to be seeded.

Seed Name	% Pure Live Seed	Lbs. Per Acre
Western Wheatgrass	30	*
Bluebunch Wheatgrass	20	*
Hard Fescue	20	*
Slender Wheatgrass	15	*
Green Needlegrass	15	*

* Drilled Rate = 25 lbs/acre, Broadcast and Hydroseed Rate = 50 lbs/acre

2.2 TOPSOIL

Add the following:

Utilize all salvaged topsoil conserved from clearing and grubbing operations to cover excavation and embankment slopes prior to fertilizing, seeding, or mulching.

2.4 FERTILIZER

Delete this Section.

PART 4 MEASUREMENT AND PAYMENT

4.1 GENERAL

Delete this section and add the following:

- A. Revegetation will not be measured and considered incidental to other work items in this Contract.
- B. Placing conserved topsoil will not be measured for payment and is considered incidental to other work items in this Contract.

END OF SECTION 02910

SECTION 03310
STRUCTURAL CONCRETE

All applicable portions of this specification section in the MPWSS shall apply with the following additions, deletions and/or modifications.

PART 1 GENERAL

1.1 DESCRIPTION

Add the following:

- B. FWP will provide a grooving tool(s) for producing a grooved finish on the concrete surface. The tool(s) provided by FWP shall be returned cleaned. The finishing tool surfaces shall be free of hardened concrete and in good condition. A cleaning cost of \$250.00 will be retained if the tool(s) are returned not cleaned or poorly cleaned. Additional costs for repair or replacement of damaged tools may also be retained.

PART 2 PRODUCT

2.1 CLASSIFICATION

Add the following to Subsection A.1:

- 1. Use M-4000 concrete for all concrete.

PART 3 EXECUTION

3.4 PLACING CONCRETE

- A. Delete the last sentence.

Add the following:

- B. Provide written and/or verbal communication notice to the Project Manager three (3) working days, excluding Saturday and Sunday, prior to any project concrete pour, regardless of pour quantity. For clarification, all written communication notices have to be received in the FWP Design and Construction Office per this requirement. Failure to provide notification will result in a deduct of pour quantity from the associated bid item. Lump sum bid items will be deducted based on the concrete placed percentage.

3.4A CONCRETE V-GROOVE FINISHING

A. Required Accuracy

1. The Contractor shall construct all specified work as shown on the project drawings within the specified tolerances, shown in Table 1. The following are reasonable tolerances that allow for a maximum specified deviation which may occur in the field during construction. Deviations beyond any values listed below may result in reduction in payment, or rejection, in part due to poor aesthetics, loss of functionality, or does not meet desired design criteria.
2. If the Contractor fails to meet specified tolerances, that portion of the work area, as specified below, may be reduced in payment or rejected, removed and replaced in accordance with General Conditions, ARTICLE 12 – UNCOVERING AND CORRECTION OF WORK.

Table 1. V-Groove Finish Tolerances

Criteria	Tolerance
V-Groove Angle Orientation	30 degrees
V-Groove Depth	0.25"
V-Groove Connections (End to End Alignment)	0.5"

B. Concrete V-Groove Finish

1. Provide a v-groove finish on all ramp surfaces as shown in the project drawings or directed by the Project Representative. Provide adequate laborers to begin concrete v-groove finish during concrete placement. Timing of v-grooving finish is critical.
2. Factors that may influence the v-groove finish and concrete performance include air content, water content, add-mixtures and strength. Some Contractors delay starting the finish, or may have a tendency to add water to the concrete surface, in order to achieve a "perfect" ramp finish. This must be avoided, as significant amounts of water in the surface layer will result in weak strength of the v-grooves, which at best contain less quantity of large aggregate due to the nature of the finish process. Refer to the Technical Specifications for other influential factors including, but not limited to: mix design, mixing and placement time, weather, correct placement of rebar, and correct thickness of ramp.

C. V-Groove Rating Score

1. The following rating score shall be used to determine allowable tolerances for all v-groove concrete finishes. The Project Representative shall make the final determination on any deficient or unacceptable area, determine the rating score, and conduct measurements as deemed necessary for evaluation. Three

(3) v-grooving evaluation criteria will be considered in determining the rating score including: appearance; angle orientation; and depth. A criteria rating score will be assigned for each based on the V-Groove Rating System, shown in Table 2. An overall, or final, rating score is made by averaging the three criteria rating scores. Final rating scores will be rounded to the nearest whole number.

Rating Score

- 1 Unacceptable, Contractor shall replace that portion of the ramp.
- 2 Poor, Reduction of 50% in payment for that portion of the ramp, or Contractor shall replace that portion of the ramp.
- 3 Fair, Minimum acceptance range.
- 4 Good.
- 5 Excellent, Letter of commendation to Contractor.

Table 2. V-Groove Evaluation Rating System

Evaluation Criteria	Criteria	Area	Score
V-Groove Appearance (top or bottom of groove)	Shallow, Uneven, Rough, Torn	40+ sf	-5
	Rounded, Flat, Semi-Rough	80+ sf	0
	Sharp, Crisp, Clean, Smooth		5
V-Groove Angle Orientation	0-5 or >56 degrees	40+ sf	1
	6-10 or 51-55 degrees	40+ sf	2
	11-15 or 46-50 degrees	80+ sf	3
	16-24 or 41-34 degrees	80+ sf	4
	25-35 degrees		5
V-Groove Depth	0.00" to 0.20"	40+ sf	1
	0.21" to 0.40"	40+ sf	2
	0.41" to 0.50"	80+ sf	3
	0.51" to 0.60"	80+ sf	4
	0.61" to 0.75"		5

3.4 TESTING

A. 3. Compression Tests

Add the following to subsection a.:

Mold a minimum of three (3) field cure cylinders (6-inch diameter), for each day of concrete placement. Follow requirements for field curing and strength testing found in this section.

PART 4 MEASUREMENT AND PAYMENT

4.1 GENERAL

Delete this section and add the following:

- A. Cast-in-Place Concrete Boat Ramp will be measured and paid for by the square foot (SF) in place including all labor, equipment, materials, and incidentals required for the completion of the work.

END OF SECTION 03310

SECTION 03311

PUSH-IN-SLAB CONCRETE BOAT RAMP

Added Section.

PART 1 GENERAL

1.1 DESCRIPTION

- A. This work consists of furnishing and installing a submerged concrete push-in-slab boat ramp surface.

PART 2 PRODUCTS

2.1 GENERAL

- A. Refer to Section 03310 for structural concrete materials and ramp surface finish.
- B. Refer to Section 03210 for reinforcing steel materials.
- C. Rail System
 - 1. Furnish new material consisting of W6x20 steel beams or approved equal to support push-in slab during installation.

PART 3 EXECUTION

3.1 INSTALLATION

- A. Casting
 - 1. Push-in-slab shall be placed on approximately a matching grade to that of the final grade of the ramp. Imported embankment material may be necessary to construct the push-in slab at the matching ramp grade, as well as provide a cushion for mechanical pushing equipment.
 - 2. Push-in-slabs shall be placed on a layer of compacted aggregate (6 inch minimum thickness) and shall be allowed to cure for a minimum of 14 days prior to movement. Provide a smooth surface to reduce friction forces during push-in slab movement (i.e. plastic sheeting).
 - 3. Push-in-slabs shall be built to a size that can be handled by the Contractor's equipment, preferably one slab per site. Each slab shall be constructed to a length that can be controlled and placed in the desired position.

4. Remove all imported embankment from the ramp surface after the push-in slab is in place. Cleanliness of the ramp surface must be approved by the Project Representative, prior to final acceptance.

B. Rail System

1. Rails shall be placed at the grade specified in the plans. Space steel beams longitudinally as shown on the project drawings. Beams shall have adequate cross braces to insure beams remain parallel as slab is pushed over beams.
2. Six inches (6") of clean, screened crushed $\frac{3}{4}$ " gravel leveling course shall be placed around the railing system and screeded to top of rail system prior to push-in slab installation. See Section 02235.

PART 4 MEASUREMENT AND PAYMENT

4.1 GENERAL

- A. Push-In-Slab Concrete Boat Ramp including excavation, preparation, rail system installation will be measured and paid for by the square foot (SF) in place including all labor, equipment, materials, and incidental required for the completion of the work.

END OF SECTION 03311