

ADDENDUM NO. 1

TO: ALL BIDDERS OF RECORD

PROJECT: Yellow Bay State Park Water System Upgrades

FWP PROJECT #: 7136321

DATE: 02/09/17

FROM: Jason Senn , Montana FWP Project Manager

Acknowledge receipt of this addendum by inserting its number and date in the Proposal Form and on the Bid Envelope. Failure to do so may subject bidder to disqualification.

This Addendum forms a part of the Contract Documents. Clarification and/or modifications area as follows:

1) Modification - **Revised Bid Opening Date:**

Due to poor weather, the Bid Opening date has been extended 7 days. Sealed Bids will be received up to and including **3:00 PM** on **February 23, 2017**, and will be publicly opened and read aloud in the offices of the Design and Construction, 1522 9th Avenue, P.O. Box 200701, Helena, MT 59620-0701. If you were unable to attend the pre-bid, please contact Amy Grout at 837-3041 x3 to schedule a tour of the project site.

2) Modification - **Fencing Specification**

Under section 1.1 A, replace "This work consists of Owner furnished and/or furnishing, erection, and placement of new fencing per the drawings and specifications" with "This work consists of **Contractor** furnished and/or furnishing, erection, and placement of new fencing per the drawings and specifications."

The fence shall be smooth wire.

3) Clarification - **Bentonite Barrier Quantity**

The bentonite impervious layer to be placed over the existing spring shall be 10' wide by 20' long and 4" thick.

4) Clarification - **PVC Removal Quantity**

The piping to be removed in the pump house is approximately 15 lf of 1" PVC.

5) Clarification – **Secondary Containment**

The proposed secondary containment called out on plan sheet 3 of 5 can be any containment structure, such as a barrel, that has the capacity to contain 25 gallons and can fit the existing hypochlorite storage tank it in.