

SPECIFICATIONS FOR WORK

TECHNICAL SPECIFICATIONS

Incorporation of Montana Public Works Technical Specifications.

The Technical Specifications as found in Montana Public Works Standard Specifications (MPWSS), Sixth Edition, April 2010; are hereby incorporated by reference and made a part of this Contract:

Incorporation of Montana Fish, Wildlife & Parks Technical Specifications and Modifications to MPW Technical Specifications.

In addition to the MPWSS Technical Specifications are the following Montana Fish, Wildlife & Parks Technical Specifications (modifications to MPWSS Technical Specifications).

SECTION 02112 - Removal of Existing Pavement, Concrete Curb, Sidewalk, Driveway
 and/or Structures

SECTION 02112

REMOVAL OF EXISTING PAVEMENT, CONCRETE CURB, SIDEWALK, DRIVEWAY AND/OR STRUCTURES

All applicable portions of this specification section in the MPWSS shall apply with the following additions, deletions and/or modifications.

PART 1 GENERAL

1.1 DESCRIPTION

A. Delete this section and add the following:

This work consists of the demolition, removal, burning and burying of structures, dwellings, utility poles, fences, and tree vegetation. In addition, the work includes conserved topsoil placement over reclaimed structure and dwelling areas.

This project consists of the demolition and removal of a 678 SF A-frame cabin, 24'x 98' Calving barn, 12'x18' shed, corrals and wire fencing. Buildings are to be demolished, debris removed from site and the area leveled and reclaimed.

The buildings can be burned on site. All metal debris will need to be removed from the site; foundation and other concrete debris can be buried on site and covered with top soil.

PART 3 EXECUTION

Delete this section and add the following:

3.1 DEMOLITION/SALVAGING

Prior to demolition of dwellings and structures, meet with on-site FWP project representative (Mark Schlepp, 406-467-3234) to review demolition plan. One structure, located on the Beckman WMA complex, shall not be disturbed and left in its existing condition:

- 8' x 12' Metal pump shed

Retain and protect the above-mentioned structures from damage of nearby demolition activities. Restore any damage inflicted to the above-mentioned structures at no cost to the Owner. The Owner reserves the right to reject damage work if not repaired to a satisfactory condition.

The Contractor can salvage any dwelling, structure (not listed above), or material found within and around these facilities with the following stipulations:

- All salvaged items must be removed by the Contractor from the Beckman Wildlife Management Area (FWP property).

3.2 REMOVAL

Remove all scrap metal including fencing materials (wire), dwelling (household) appliances, and misc. metal from the Wildlife Management Area (FWP property).

Haul all removed material to a legal site and obey all state, county, and local disposal restrictions and regulations.

3.3 BURNING

Lumber or wood and misc. debris can be burned on site.

Burning will only be allowed from December 1, 2017 through January 31, 2018.

Obtain all necessary burning permits from Fergus County (406) 535-9046

3.4 BURYING

Salvage topsoil from excavated areas where materials are to be buried.

Bury all concrete foundations, concrete slabs, non-burnable debris, and all other material not salvaged or removed from the Beckman WMA.

3.5 RECLAMATION

Reclaim site by re-grading demolition areas to its original condition. Re-grading of area includes flattening all buried and burned piles below original ground contours.

Place conserved or salvaged topsoil over reclaimed areas to a depth of two feet if adequate material is available. Re-grade conserved topsoil to remove all lumps, piles, and windrows to provide a smooth uniform surface. Re-grade area as approved by the FWP project representative. The disturbed areas will need to be seeded with the following seed mix.

<u>Grass Species</u>	<u>% PLS Count</u>	<u>lbs./acre</u>
● Streambank Wheatgrass	40%	Broadcast Rate (24 lbs./acre)
● Western Wheatgrass	20%	
● Sheep Fescue	15%	
● Blue Grama	15%	
● Green Needlegrass	10%	

PART 4 MEASUREMENT AND PAYMENT

Delete this section and add the following:

Beckman WMA Barber Addition Building Removal will be measured and paid by the lump sum (LS). Payment indicated to include compensation for all labor, equipment, materials and incidentals required for the completion of the work.

END OF SECTION 02112