

## ADDENDUM NO. 1

---

TO: ALL BIDDERS OF RECORD

PROJECT: ***JOCKO RIVER TROUT HATCHERY RACEWAY REPLACEMENT***

FWP PROJECT #: 7153101

ADDENDUM DATE: June 15, 2017  
BID OPENING DATE: June 22, 2017, 3 PM

FROM: Craig Jenneskens., RPA  
Troy Monroe P.E., Montana FWP

**Acknowledge receipt of this addendum by inserting its number and date in the Proposal Form and on the Bid Envelope. Failure to do so may subject bidder to disqualification.**

This Addendum forms a part of the Contract Documents. Clarification and/or modifications area as follows:

1. Electrical Conduit at Spawn House and Feed Shed  
EMT conduit is acceptable for all exposed conduit installation at the Spawn House and Feed Shed, in lieu of the specified rigid conduit.
2. Electrical Conduit for new Light Poles  
SCH 40 PVC conduit is acceptable for all buried conduit to the new power poles. Exposed (above-ground) conduit on the power poles shall be SCH 80 PVC. All elbows shall be rigid.
3. Show Pond Supply Piping (Sheet C201) – Additive Alternate #1  
Replace the 18"x8" MJ tee and 8" MJ valve on the show pond supply piping with an 18"x8" tapping saddle and 8" FLxMJ valve. Tapping sleeve body can be of stainless steel, ductile iron or fusion bonded epoxy coated steel.