

PLANS FOR CONSTRUCTION OF:

# FREEZEOUT LAKE WMA COLD STORAGE BUILDING

NEAR FAIRFIELD, MONTANA  
FWP PROJECT #7179102

SHEET INDEX

TITLE SHEET	T1
SITE PLAN	C1
NOTES AND DETAILS	C2
BUILDING FOUNDATION PLAN	C3
BUILDING ELEVATIONS	C4
BUILDING SECTION	C5
ELECTRICAL PLAN	E1
ELECTRICAL PLAN	E2

CIVIL SITE DESIGN BY:


LARSON CIVIL ENGINEERING, LLC

ELECTRICAL DESIGN BY:


AMES ENGINEERING

ARCHITECTURAL REVIEW BY:

SLATE ARCHITECTURE



VICINITY MAP



CODE ANALYSIS	
<b>CODES:</b> BUILDING: 2012 INTERNATIONAL BUILDING CODE (IBC) MECHANICAL: 2012 INTERNATIONAL MECHANICAL CODE (IMC) PLUMBING: 2012 UNIFORM PLUMBING CODE (UPC) ELECTRICAL: 2014 NATIONAL ELECTRICAL CODE (NEC) FIRE: 2012 INTERNATIONAL FIRE CODE ENERGY: 2012 INTERNATIONAL ENERGY CONSERVATION CODE (IECC) ACCESSIBILITY: ANSI 117.1	<b>EXTERIOR WALL PROTECTION:</b> IBC TABLE 602 NONE REQUIRED
<b>BUILDING AREA:</b> TOTAL BUILDING AREA: 2,400 S.F.	<b>FLAME SPREAD:</b> IBC TABLE 803.9 EXIT ENCLOSURE & PASSAGEWAYS: B CORRIDORS: B ROOMS AND ENCLOSED SPACES: C
<b>OCCUPANCY:</b> IBC SECT. 311 75-11 OCCUPANCY	<b>AUTOMATIC SPRINKLER SYSTEM:</b> IBC SECTION 903 NONE
<b>CONSTRUCTION TYPE:</b> IBC TABLE 601 TYPE V-B PERMITTED: 9,000 SF/FLR (TABLE 503) ACTUAL AREA: 2,400 SF	<b>EXITS:</b> IBC TABLE 1004.1.1 OCCUPANT LOAD: WAREHOUSES: 500 S.F. PER OCCUPANT OCCUPANT LOAD (NEW): 4
<b>OCCUPANCY SEPARATION:</b> IBC TABLE 508.4 NA	<b>EXIT CALCULATION:</b> IBC CH. 10 - TABLE 1015.1 2 EXITS PROVIDED
<b>LOCATION ON PROPERTY:</b> 430' OPEN SPACE	<b>DISTANCE TO EXITS:</b> IBC SECTION 1016 200 FT. MAX.; LESS THAN 200 FT. PROVIDED
<b>FIRE RESISTANCE:</b> IBC TABLE 601 STRUCTURAL FRAME: PERMITTED EXTERIOR BEARING WALLS: NONE REQUIRED INTERIOR BEARING WALLS: NONE REQUIRED EXTERIOR NONBEARING WALLS: NONE REQUIRED INTERIOR NONBEARING WALLS: NONE REQUIRED FLOOR CONSTRUCTION: NONE REQUIRED ROOF CONSTRUCTION: NONE REQUIRED	<b>ROOF CONSTRUCTION:</b> IBC TABLE 1505.1 CLASS C - MINIMUM CLASSIFICATION

J. LARSON  
DRAWN BY: DATE: MARCH 2, 2018  
J. LARSON  
CHECKED BY: DATE: MARCH 2, 2018

REVISED BY: DATE:  
J. LARSON MARCH 2, 2018  
APPROVED BY: DATE:

APPROVED BY: DATE:  
APPROVED BY: DATE:




Montana Fish  
Wildlife & Parks

TITLE SHEET  
FREEZEOUT LAKE WMA COLD STORAGE BUILDING  
FWP #7179102



28 ANTLER AVENUE  
CLANCY, MT 59634  
406-443-6111  
jeff@larsonce.com


SHEET: T1





CP2 ON NORTH SIDE  
OF ENTRANCE ROAD


LEGEND


EXISTING FEATURES


 BUILDING

 SIDEWALK


 UNDERGROUND ELECTRICAL POWER


 IRRIGATION PIPING


 BOLLARD


 LIGHT POLE

PROPOSED FEATURES

 BUILDING



 GRAVEL SUIRFACING

 SIDEWALK

 SPOT ELEVATION

CONTROL POINT TABLE				
POINT	NORTHING	EASTING	ELEVATION	DESCRIPTION
CP1	5,000.00	5,000.00	1,000.00	IRON PIN
CP2	4,859.44	4,905.73	1,001.01	IRON PIN
CP3	4,947.37	4,875.45	998.88	IRON PIN

ASSUMED DATUM



J. LARSON	MARCH 2, 2018
DRAWN BY:	DATE:
J. LARSON	MARCH 2, 2018
CHECKED BY:	DATE:

REVISED BY:	DATE:
J. LARSON	MARCH 2, 2018
APPROVED BY:	DATE:

APPROVED BY:	DATE:
APPROVED BY:	DATE:



Montana Fish,  
Wildlife & Parks

156

SITE PLAN  
FREEZEOUT LAKE WMA COLD STORAGE BUILDING  
FWP #7179102



28 ANTLER AVENUE  
CLANCY, MT 59634  
406-443-6111  
jeff@larsonce.com

SHEET: C1




CONSTRUCTION NOTES:

1. ALL WORK SHALL BE CONSTRUCTED IN ACCORDANCE WITH "MONTANA PUBLIC WORKS STANDARD SPECIFICATIONS", SIXTH EDITION (MPW).
2. BEFORE DIGGING, CALL 811 FOR LOCATION OF EXISTING UTILITIES.
3. CRUSHED BASE COURSE SHALL BE 1" MINUS PER MPW SPECIFICATIONS.
4. CONCRETE SLABS AND SIDEWALK SHALL BE REINFORCED WITH FIBER MESH.
5. CRUSHED TOP SURFACING FOR GRAVEL SURFACING SHALL MEET THE FOLLOWING SPECIFICATIONS INCLUDING BINDER OR BLENDING MATERIAL:


SIEVE SIZE	% PASSING
3/4" SIEVE	100%
No. 4 SIEVE	40-80%
No. 10 SIEVE	25-60%
No. 200 SIEVE	8-20%

- IN ADDITION, THE PORTION PASSING THE NO. 200 SIEVE CANNOT EXCEED 2/3 OF THE PORTION PASSING THE #40 SIEVE; THE MAXIMUM LIQUID LIMIT FOR THE MATERIAL PASSING THE NO. 40 SIEVE SHALL NOT EXCEED 35, WHILE THE PLASTICITY INDEX CAN VARY BETWEEN 3 AND 10; THE WEAR FACTOR SHALL NOT EXCEED 50% AT 500 REVOLUTIONS; AND AT LEAST 20% OF THE AGGREGATE RETAINED ON NO. 4 SIEVE SHALL HAVE A FRACTURED FACE.
6. CRUSHED TOP SURFACE SHALL BE PLACED AND COMPACTED AS IDENTIFIED IN MPW SPECIFICATION 02/235 CRUSHED BASE COURSE.
  7. ALL EXCAVATION AND EMBANKMENT ON THIS PROJECT, SHALL MEET THE REQUIREMENTS OF MPW SPECIFICATION 02/230 STREET EXCAVATION, BACKFILL AND COMPACTION.
  8. CONCRETE SHALL BE M-4000 PER MPW SPECIFICATIONS. ALL REBAR #4 AND LARGER SHALL BE ASTM GRADE 60, #3 REBAR SHALL BE ASTM GRADE 40.
  9. ALL HOLES DRILLED IN CONCRETE FOR BOLT EMBEDS SHALL BE THOROUGHLY CLEANED OF DUST BY BLOWING OUT THE HOLE WITH AN AIR COMPRESSOR.
  10. COMPACTION AND CONCRETE TESTING SHALL BE PERFORMED IN ACCORDANCE WITH THE MPW SPECIFICATIONS BY AN INDEPENDENT LABORATORY HIRED BY THE CONTRACTOR. SUBMIT RESULT TO BOTH OWNER AND ENGINEER. PROVIDE TESTING AS INDICATED IN THE FOLLOWING SCHEDULE:
    - ONE TEST EACH FOR SUBGRADE AND GRAVEL AT EACH FOOTING, OR EVERY 50' FOR LINEAR FOOTINGS.
    - SUBGRADE FOR PARKING, SIDEWALK, BUILDING SLAB AND BUILDING GRAVEL ONE TEST PER 400 SF.
    - GRAVEL FOR PARKING, BUILDING GRAVEL, SIDEWALK AND BASE UNDER SLAB ONE TEST PER 400 SF.
  11. THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING DETAILED DRAWINGS AND STRUCTURAL CALCULATIONS FOR THE BUILDING AND FOUNDATION. DRAWNGS AND CALCULATIONS SHALL BE STAMPED BY A PROFESSIONAL ENGINEER LICENSED IN MONTANA.
  12. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING A BUILDING PERMIT FROM THE STATE OF MONTANA. THE COST OF THE PERMIT SHALL BE PAID BY THE CONTRACTOR AND SHALL BE INCLUDED IN THE CONTRACTORS BID.
  13. PROVIDE ONE FIRE EXTINGUISHER AND CABINET AS SPECIFIED. LOCATION TO BE DETERMINED BY OWNER.
  14. IMPORT BACKFILL MATERIAL CAN BE OBTAINED FROM A STATE OWNED PIT IN NE 1/4 OF SECTION 3, TOWNSHIP 22 NORTH, RANGE 3 WEST. THE MATERIAL IS SIMILAR TO 3" MINUS PIT RUN. ANY EXCESS SPOIL MATERIAL CAN BE DISPOSED OF AT THE PIT.
  15. SOIL SEPARATION FABRIC SHALL BE NON-WOVEN POLYPROPYLENE GEOTEXTILE THAT IS INERT TO BIOLOGICAL DEGRADATION AND RESISTANT TO NATURALLY OCCURRING CHEMICALS, ALKALIS AND ACIDS. SOIL SEPARATION FABRIC SHALL HAVE AN TENSILE STRENGTH (GRAB) OF 160 LBS AND SHALL BE GEOTEX 601 OR APPROVED EQUAL.

CONCRETE APRON AND SIDEWALK



GRAVEL SURFACING SECTION



SURFACING SECTIONS

NO SCALE



J. LARSON MARCH 2, 2018  
DRAWN BY: DATE:  
J. LARSON MARCH 2, 2018  
CHECKED BY: DATE:

REVISED BY: DATE:  
J. LARSON MARCH 2, 2018  
APPROVED BY: DATE:

APPROVED BY: DATE:  
APPROVED BY: DATE:



Montana Fish  
Wildlife & Parks

157


NOTES AND DETAILS  
FREEZEOUT LAKE WMA COLD STORAGE BUILDING  
FWP #7179102



28 ANTLER AVENUE  
CLANCY, MT 59634  
406-443-6111  
jeff@larsonce.com

SHEET:


C2



KEY:  
—— CJ —— CONSTRUCTION JOINTS SAW CUT TO 1-1/2" DEPTH IN SLAB

FOOTING AND FOUNDATION NOTES:


1. THE STRUCTURAL DESIGN OF FOUNDATIONS AND FOOTINGS IS THE RESPONSIBILITY OF THE CONTRACTOR. DETAILS AND CALCULATIONS STAMPED BY A PROFESSIONAL ENGINEER SHALL BE SUBMITTED FOR REVIEW PRIOR TO ORDERING THE BUILDING PACKAGE.
2. FOOTINGS AND FOUNDATION ARE TO BE CONCRETE CONSTRUCTION. COLUMNS SHALL NOT EXTEND BELOW FLOOR ELEVATION.
3. FOOTINGS SHALL BE DESIGNED TO BE INDEPENDENT OF THE FLOOR SLAB.
4. SOIL BEARING CAPACITY FOR FOOTING DESIGN IS 2,000 PSF.
5. A MODULUS OF SUBGRADE REACTION, k, OF 150 PSI MAY BE USED FOR THE SLAB DESIGN.



NOTES:

1. THIS DETAIL IS TYPICAL ALONG ALL EDGES OF THE BUILDING SLAB
2. THIS DETAIL IS THE MINIMUM SECTION ALLOWED. IF THE STRUCTURAL DESIGN REQUIRES A LARGER DIMENSIONS, THE STRUCTURAL DESIGN SHALL SUPERCEDE THIS DETAIL.
3. FOOTING ELEVATION MAY BE STEPPED TO MATCH FINISH GROUND ELEVATION AROUND THE BUILDING. MAINTAIN 42" OF COVER IN ALL LOCATIONS.


SECTION  
SCALE 1" = 1'-0"



NOTES:

1. THIS DETAIL IS TYPICAL ALONG ALL EDGES OF THE BUILDING SLAB
2. THIS DETAIL IS THE MINIMUM SECTION ALLOWED. IF THE STRUCTURAL DESIGN REQUIRES A LARGER DIMENSIONS, THE STRUCTURAL DESIGN SHALL SUPERCEDE THIS DETAIL.
3. FOOTING ELEVATION MAY BE STEPPED TO MATCH FINISH GROUND ELEVATION AROUND THE BUILDING. MAINTAIN 42" OF COVER IN ALL LOCATIONS.

SECTION (ADDITIVE ALTERNATE #2)  
SCALE 1" = 1'-0"



FOUNDATION PLAN  
SCALE 1/8" = 1'-0"

J. LARSON MARCH 2, 2018  
DRAWN BY: DATE:  
J. LARSON MARCH 2, 2018  
CHECKED BY: DATE:

REVISED BY: DATE:  
J. LARSON MARCH 2, 2018  
APPROVED BY: DATE:

APPROVED BY: DATE:  
APPROVED BY: DATE:








Montana Fish  
Wildlife & Parks  
158

BUILDING FOUNDATION PLAN  
FREEZEOUT LAKE WMA COLD STORAGE BUILDING  
FWP #7179102



28 ANTLER AVENUE  
CLANCY, MT 59634  
406-443-6111  
jeff@larsonce.com

SHEET: C3



NOTE: COLORS OF ROOFING, SIDING AND TRIM ARE OWNER SELECT.

# BUILDING ELEVATIONS

SCALE 1"= 10'-0"

J. LARSON  
DRAWN BY: MARCH 2, 2018  
J. LARSON  
CHECKED BY: MARCH 2, 2018

REVISED BY: DATE:  
J. LARSON MARCH 2, 2018  
APPROVED BY: DATE:

APPROVED BY: DATE:  
APPROVED BY: DATE:





BUILDING ELEVATIONS  
FREEZEOUT LAKE WMA COLD STORAGE BUILDING  
FWP #7179102

LARSON CIVIL  
ENGINEERING, LLC  
28 ANTLER AVENUE  
CLANCY, MT 59634  
406-443-6111  
jeff@larsonce.com

SHEET: C4

NOTE:  
THE LOCATION, SIZE AND SPACING OF  
FRAMING MEMBERS AND GIRDERS MAY BE  
ADJUSTED AS REQUIRED TO MEET THE  
STRUCTURAL REQUIREMENTS OF BUILDING  
DESIGN.



**BUILDING SECTION**  
NO SCALE

J. LARSON MARCH 2, 2018  
DRAWN BY: DATE:  
J. LARSON MARCH 2, 2018  
CHECKED BY: DATE:

REVISED BY: DATE:  
J. LARSON MARCH 2, 2018  
APPROVED BY: DATE:

APPROVED BY: DATE:  
APPROVED BY: DATE:



**Montana Fish & Wildlife & Parks**

160

**BUILDING SECTION**  
FREEZEOUT LAKE WMA COLD STORAGE BUILDING  
FWP #7179102




28 ANTLER AVENUE  
CLANCY, MT 59634  
406-443-6111  
jeff@larsonce.com

SHEET:


C5





## STORAGE BUILDING ELECTRICAL PLAN

1/8"=1'-0"



## REVISED RISER DIAGRAM

NO SCALE

PANEL	A	AMPS	100A	BUS	100A	MOUNT	SURFACE	NOTES	FED FROM 100A/2P
LOC.	BLDG	L-N V	240	NEUT	100A	FED	BOTTOM		BREAKER IN EXISTING
MFGR	SQUARE D	L-N V	120	M.C.B.	100A	WIDTH	20"		METER MAIN ON OFFICE
TYPE	WOOD	PHASE	1	TYPE	DEPT	DEPTH	5.75"		BUILDING
AIC	10K	WIRES	3	M.L.O.	NE MA		1		

REMARKS : BOLT-ON BREAKERS ONLY, HACR BREAKERS WHERE REQUIRED BY HVAC UNIT MANUFACTURER  
\*ALL CIRCUIT BREAKERS SHALL BE RATED 10,000 AIC AND LISTED FOR SERIES COMBINATION WITH THE CURRENT LIMITING MAIN FUSES OR CIRCUIT BREAKERS.

CKT NO.	BREAKER	WIRE	LOAD DESCRIPTION	REC	LTS	HTR	MTR	MISC	LOAD(VA)	USE	LOAD DESCRIPTION	WIRE	BREAKER	CKT NO.
1	20	1	#12						270					
3	20	1	#12						120					
5	20	1	G #12						360					
7	20	1	#12						850					
9	20	1	#12						360					
11	20	1	#12						850					
13	20	1	#12						360					
15	20	1	#12						850					
17	20	2	#12						180					
19									850					
21	50	2	#6						180					
23									3000					

TOTAL CONNECTED LOAD 6810 6600

BREAKER TYPES  
N = NORMAL  
S = SHUNT-TRIP  
G = GFCI

CONNECTED LOAD	DIV.	DEMAND
REC 1ST 10KVA	100%	1.3 KVA
REC REMAINING	50%	0.0 KVA
LIGHTING	0.8 KVA	0.0 KVA
RES HEAT	125%	0.0 KVA
MOTORS	125%	11.4 KVA
MISCELLANEOUS	100%	0.0 KVA
TOTAL DEMAND LOAD		13.4 KVA
DEMAND AMPS		55.9 AMPS

## LIGHT FIXTURE SCHEDULE


LTR.	SYMBOL	DESCRIPTION	MANUFACTURER	CATALOG NO.	LOCATION	MOUNTING	LAMPS CAT. NO.	NOTES
A		1'x4' SURFACE MTD, LENSED GASKETED FIXTURE LED LAMPING	LITHONIA	FEM-L48-6000LM LPACL-MD-40K	CEILING	SURFACE	45W LED	120V
B		EXTERIOR FLOOD LIGHT 2-HEADS WITH PHOTOCELL LED LAMPS	LITHONIA	OFLR-6LC 120-P-BZ	WALL	WALL 8' AFF	20W LED	120V

### NOTES:

1

## ELECTRICAL LEGEND

	PANEL OR LOAD CENTER		LIGHT FIXTURES, WALL MOUNTED
	HOME RUN TO PANEL, NO. OF ARROWS INDICATES NO. OF CIRCUITS.		SWITCH, SPST
	NO. OF HASH MARKS INDICATES NO. OF CONDUCTORS IN CONDUIT, NO HASH MARKS INDICATES TWO CONDUCTORS-GROUND CONDUCTORS ARE NOT INCLUDED IN WIRE COUNT.		OUTLET, DUPLEX
	LIGHT FIXTURE, CEILING MOUNT		OUTLET, GROUND FAULT INTERRUPTER
			SPECIAL CONNECTION
			GFI GROUND FAULT INTERRUPTER
			HP HORSE POWER



S. AMES MAR. 05, 2018  
DRAWN BY: DATE:  
S. AMES MAR. 06, 2018  
CHECKED BY: DATE:

REVISED BY: DATE:  
S. AMES MAR. 05, 2018  
APPROVED BY: DATE:

APPROVED BY: DATE:  
APPROVED BY: DATE:



Montana Fish & Wildlife & Parks

161

ELECTRICAL PLAN  
FREEZEOUT LAKE WMA COLD STORAGE BUILDING  
FWP #7179102

AMES  
ENGINEERING, LLC  
815 JADE STREET  
HELENA, MT 59602  
PHONE/FAX: (406) 458-0494  
E-MAIL: susanames@mt.net

SHEET: E1

## Electrical Specifications

Scope: All electrical work under this contract as shown on the plans and indicated in the specifications. Work shall be performed by a licensed and bonded contractor utilizing tradesmen skilled in the art and in accordance with acceptable practices. All work shall comply with local, state, and the National Electrical Code, latest edition.

**Permits:** The electrical contractor shall secure all permits in connection with his work.

Work Included: All lighting and power systems including fixtures, devices, boxes, conduit, disconnects, motor starters, etc. Provide and install all incidental items required for a complete and functioning system. Service equipment, motors, etc. to be located and installed as shown on the plan. Deviations shall be approved prior to installation by the architect and/or engineer.

Tests: Prior to tests or usage, all switches, panels, devices shall be in place. All branch circuits shall be free of faults or shorts. The complete installation and all components shall have a resistance between conductors and between conductors and ground as specified by the N.E.C.

**Ground:** There shall be continuity of ground throughout the system. System ground to comply with N.E.C. requirements.

**Materials:** All materials such as receptacles, switches, conduit, conductors, panelboards, devices, fixtures, etc. to be new and bear the U.L. label or to conform to applicable standards.

**Guarantee/Warranty:** Contractor guarantees that all work and plant will be free from defects of materials and workmanship for a period of one (1) year from the date of final acceptance. Contractor further agrees that he will replace or repair all defective equipment and installation that become defective during the term of the warranty. This does not include excessive abuse or damage inflicted by the owner and/or others.

Manufacturers Directions, Procedures and Operating Instructions: Manufacturers materials, and equipment applied, installed, connected, erected, used, cleaned, and conditioned as per manufacturers directions or recommendations prior to installation.

Installation: All equipment, circuitry, etc. shall be installed as follows or as specified otherwise. The electrical contractor shall verify all nameplate ratings of equipment to be connected and verify electrical compatibility and code compliance. Manufacturer's recommendations shall take precedence unless verified otherwise.

**Conductors and Cable:** All conductors shall be copper with a weather resistant thermoplastic cover. No branch circuit conductors shall be smaller than #12 unless for low voltage wiring.

**Motor Circuits:** Motors and circuitry to be installed and connected as indicated on the plan. All motors to be provided with a disconnecting means per the N.E.C. If fractional horsepower motors do not have an integral disconnecting means such as a plug or snap switch, electrical contractor to provide and install an acceptable disconnecting means. Equipment connected with flexible conduit with green jacketed ground wire within conduit-to-conduit system or equipment ground. Connect for correct rotation.

Conduits: PVC schedule 40 acceptable where routed underground.  
If PVC is used, provide ground wire. Compression couplings in wet locations and in concrete walls and floors. Romex and MC cable are not acceptable.

Outlet Boxes:

Fixture and Special Purpose 4" x 4" x 2 1/8"

Duplex, Switch and Telephone 3" x 2" x 2 3/4"

Special Purpose Outlet 4" x 4" x 2 1/8"

Wire and Cable: Type THHN or THWN for application or as noted otherwise.  
Color code in accord with the NEC.

Current Characteristics: 120/240V, 1 phase, 3W

Wiring Devices: Product: Leviton, P&S, Hubbell, and Slater acceptable. Switch and receptacle colors: selected by owner. Devices and finish plates to match in color - no exceptions.


1. Standard switches 20 amps, 277 volt with matching smooth plastic plate. Mount 44" to centerline.
- a. 1 pole Single pole toggle, 20A, Model No. CSB1-20
2. Duplex outlet Nema standard WD 1 and 6, 20 amps, 125 volts grounded Model No. BR20 complete with smooth matching plate. Mount centerline at 18".
3. GFCI receptacle, 20 amp, 125 volt - Model number 68991 with matching plate zinc weather resistant cover where indicated W.P.

**Equipment Connections:** Electrical contractor to coordinate all work where he is responsible for connecting equipment supplied by others. Verify equipment plug configurations and direct connect or install receptacle to match plug. Verify box mounting heights prior to rough in.

Disconnect and Schedule of Control Equipment: Product of General Electric, Square D, Cutler Hammer, and Westinghouse acceptable. Model, style, etc. as scheduled. Install fuses for disconnects if required and heaters for motor controllers as recommended by motor equipment supplier. Coordinate controls wiring as indicated on the schedule and make allowances there of.


PLUG AND RECEPTACLE SHALL BE HOUSED IN WATER-RESISTANT, SYNTHETIC RUBBER CAPABLE OF BURIAL IN THE GROUND OR INSTALLATION IN SUNLIGHT. EACH HOUSING SHALL PROVIDE A SECTION TO FORM A WATERTIGHT SEAL AROUND THE CABLE AND A SECTION TO PROVIDE A WATER-SEAL BETWEEN THE TWO HOUSINGS AT THE POINT OF DISCONNECTION. EACH KIT SHALL BE SUPPLIED WITH SUFFICIENT SILICONE COMPOUND TO LUBRICATE METAL PARTS AND THE RUBBER HOUSINGS FOR EASY ASSEMBLY.

WHERE INDICATED A COPPER PIN AND A COPPER RECEPTACLE BOTH OF AT LEAST 90% CONDUCTIVITY SHALL BE CRIMPED TO THE CABLE. THE RECEPTACLE SHALL ESTABLISH CONTACT PRESSURE WITH THE PIN THROUGH THE USE OF A COPPER BERYLLIUM SPRING AND SHALL BE EQUIPPED WITH A DISPOSABLE MOUNTING PIN. THE PIN SHALL BE OF AT LEAST HALF-HARD MATERIAL AND THE CRIMPING PORTION SHALL BE FULLY ANNEALED WHILE THE REST OF THE PIN IS MAINTAINED IN ITS ORIGINAL STATE OF HARDNESS. THE RECEPTACLE SHALL BE FULLY ANNEALED. THE PIN AND RECEPTACLE SHALL LOCK TOGETHER SO THE CONNECTION WILL BE MAINTAINED WHEN A MINIMUM FORCE OF 89 NEWTONS TENSION IS APPLIED TO THE ATTACHED CABLES.



## WATERTIGHT CONNECTION DETAIL

NO SCALE



S. AMES	MAR. 05, 2018
DRAWN BY:	DATE:
S. AMES	MAR. 05, 2018
CHECKED BY:	DATE:

REVISED BY:	DATE:
S. AMES	MAR. 05, 2018
APPROVED BY:	DATE:

APPROVED BY: \_\_\_\_\_ DATE: \_\_\_\_\_

APPROVED BY: \_\_\_\_\_ DATE: \_\_\_\_\_



**Montana Fish,  
Wildlife & Parks**

ELECTRICAL PLAN  
FREEZEOUT LAKE WMA COLD STORAGE BUILDING  
FWP #7179102

**AMES**  
**ENGINEERING, LLC**  
815 JADE STREET  
HELENA, MT 59602  
PHONE/FAX: (406) 458-0494  
E-MAIL: [susanhames@mt.net](mailto:susanhames@mt.net)

SHEET:

E2