	HVAC & CONTROL SYMBOLS										
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION								
M	MOTOR	T	DUCT THERMOSTAT								
	CENTRIFUGAL FAN	H	HUMIDISTAT, ROOM								
T	ROOM OR ZONE THERMOSTAT	Н	HUMIDISTAT, DUCT								
(SD)	SMOKE DETECTOR, DUCT	Р	PRESSURE SWITCH								
*/*/*	DAMPER, OPPOSED BLADE	Р т	TEMPERATURE TRANSMITTER (SENSOR)								
MD	MOTORIZED DAMPER ACTUATOR	PT/PS	PRESSURE TRANSMITTER OR SWITCH								
FD	FIRE DAMPER	SP	DIFFERENTIAL PRESSURE CONTROLLER								
SD	SMOKE DAMPER	BDD	BACKDRAFT DAMPER, GRAVITY								
FSD	COMBINATION FIRE/SMOKE DAMPER	BD	BALANCING DAMPER (CFM CONTROL)								
12"X10"	RECTANGULAR DUCT (REFER TO SYS)	8"Ø	ROUND DUCT-REFER TO SYSTEM SERVE								
12"X10"	LINED RECTANGULAR DUCT	8"Ø	ROUND LINED OR DOUBLE WALL DUCT								

#### DUCT CONSTRUCTION SPECIFICATION

- RECTANGULAR DUCT SHALL BE GALVANIZED G60 OR G90 GRADE SHEETMETAL FORMED AND FABRICATED IN ACCORDANCE WITH SMACNA HVAC DUCT CONSTRUCTION STANDARDS-METAL AND FLEXIBLE FOR PRESSURE CLASS OF 2" WG MINIMUM. 26 GAGE METAL MINIMUM.
- 2. ROUND DUCT SHALL BE GALVANIZED G60 OR G90 GRADE SHEETMETAL SPIRAL DUCTING FORMED IN ACCORDANCE WITH SMACNA HVAC DUCT CONSTRUCTION STANDARDS-METAL AND FLEXIBLE FOR PRESSURE CLASS OF 2" WG MINIMUM. DIE CAST OR WELDED ELBOWS AND FITTINGS MEETING THE SAME SPECIFICATION ALLOWED. AT CONTRACTOR OPTION, LONGITUDE LOCK SEAM (SNAPPY) DUCT AND ADJUSTABLE FITTINGS ARE ALLOWED ONLY ON RESTROOM EXHAUST. 26 GAGE METAL MINIMUM.
- 3. SEAL ALL DUCT SEAMS IN ACCORDANCE WITH SMACNA HVAC DUCT CONSTRUCTION STANDARDS-METAL AND FLEXIBLE TABLE 1-2 SEAL CLASS B, MINIMUM.
- 4. DUCT CONNECTOR SHALL BE STANDARD SLIP 'S' AND DRIVE CONNECTOR OF METAL GAGE NOT LESS THAN DUCT GAGE SPECIFIED IN #1. PROPRIETARY FLANGE CONNECTIONS SUCH AS WARD OR DUCT-MATE ARE ENCOURAGED.
- 5. SUPPORT ALL DUCTING IN ACCORDANCE WITH SMACNA HVAC DUCT CONSTRUCTION STANDARDS-METAL AND FLEXIBLE. NO EXCEPTIONS!
- 6. DUCT LINER SHALL BE 1" OWENS CORNING 'LINA-COOUSTIC' BRAND, OR EQUAL. INSTALL ACCORDING TO MFR.
- 7. INSULATE ALL EXTERIOR (OUTDOOR) DUCTING WITH RIGID 2" FIBERGLASS INSULATION WITH SEALED GALVANIZED CLADDING.
- 8. ALL RECTANGULAR ELBOWS TO CONTAIN SINGLE OR DOUBLE TURNING VEIN.

#### DUCT INSULATION/LINER REQUIREMENTS

INSULATED DUCTWORK INCLUDES (2" THICKNESS/R-5 VALUE):

• COMBUSTION AIR VENTS TO ALL UNIT HEATERS.

#### TEST & BALANCE INSTRUCTIONS:

BALANCER SHALL BE BIGHORN BALANCING, RGO, OR PRIOR APPROVED EQUAL. THE BALANCING CONTRACTOR SHALL PERFORM AIR AND WATER BALANCE IN ACCORDANCE WITH MINIMUM NEBB GUIDELINES AND REPORT THE FOLLOWING DATA:


- OPERATING AMPERAGE MEASURED UNDER FULL LOAD.
- MEASURED VOLTAGE AT EACH UNIT.
   ESP OF EACH AIR MOVING EQUIPMENT.
- TOTAL MEASURED AND ADJUSTED CFM RETURN, SUPPLY, OUTSIDE AIR, AND EXHAUST
- 5. INITIAL PRESSURE DROP ACROSS FILTERS.
- 6. GPM AND HEAD PUMPS.7. CFM DIFFUSERS.

C. CU-1 AND AC-1.

8. INITIAL AND FINAL OUTDOOR AIR CFM.

THE FOLLOWING PIECES OF EQUIPMENT SHALL RECEIVE TESTING & BALANCING TREATMENT:

A. EF-1 AND EF-2 (ADD ALTERNATE #1). B. UH-1, UH-2, AND UH-3.



#### BASIC MECHANICAL REQUIREMENTS

FURNISH ALL LABOR AND MATERIALS AND PERFORM ALL
OPERATIONS NECESSARY FOR THE INSTALLATION OF COMPLETE
AND OPERATING MECHANICAL SYSTEMS SUBJECT TO THE
CONDITIONS OF THE CONTRACT. PROVIDE SATISFACTORY
OPERATION OF ALL EQUIPMENT AND CONTROLS TO THE
ARCHITECT/ENGINEER UPON REQUEST.

ALL MATERIALS SHALL BE NEW. SUBSTITUTIONS SHALL BE APPROVED BY OWNER AND/OR ENGINEER.

VISIT THE PREMISES BEFORE SUBMITTING BID AS NO CHANGE ORDERS WILL BE ALLOWED FOR LACK OF KNOWLEDGE OF EXISTING CONDITIONS

COORDINATE AND ORDER THE PROGRESS OF WORK TO CONFORM TO THE PROJECT SCHEDULE AND THE PROGRESS OF THE WORK OF THE OTHER TRADES.

MECHANICAL DRAWINGS ARE DIAGRAMMATIC AND BECAUSE OF THE SMALL SCALE, IT IS NOT POSSIBLE TO INDICATE EVERY REQUIRED OFFSET, FITTING, ETC. VERIFY ALL SPACE REQUIREMENTS, COORDINATING WITH OTHER TRADES, AND INSTALL THE SYSTEMS IN THE SPACE PROVIDED WITHOUT EXTRA CHARGES TO THE OWNER.

PERFORM WORK IN ACCORDANCE WITH GOOD COMMERCIAL PRACTICE. THE GOOD APPEARANCE OF THE FINISHED WORK SHALL BE OF EQUAL IMPORTANCE WITH ITS MECHANICAL EFFICIENCY AND INTENT. THE OWNER MAY REJECT WORK IF WORKMANSHIP AND APPEARANCE ARE NOT SATISFACTORY.

INSTALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH THE MANUFACTURERS' RECOMMENDATIONS UNLESS SPECIFICALLY INDICATED OTHERWISE, OR WHERE LOCAL CODES OR REGULATIONS TAKE PRECEDENCE.

COMPLY WITH STATE AND LOCAL CODE REQUIREMENTS AND ORDINANCES. COMPLY WITH REQUIREMENTS OF THE UTILITY COMPANIES. IN THE CASE OF DIFFERENCES BETWEEN THESE REQUIREMENTS AND ORDINANCES, THE MOST STRINGENT SHALL GOVERN. CALL FOR INSPECTIONS REQUIRED BY LOCAL BUILDING INSPECTION AUTHORITY.

PLANS AND SPECIFICATIONS GO HAND IN HAND. WHAT IS REQUIRED IN ONE IS REQUIRED IN BOTH. WHERE CONFLICTS BETWEEN SPECIFICATIONS AND PLANS EXIST, THE MOST STRINGENT REQUIREMENTS SHALL APPLY.

MECHANICAL PLANS SUPERCEDE ARCHITECTURAL PLANS.
BACKGROUND FLOOR PLANS USED FOR MECHANICAL DRAWINGS
MAY SHOW DIFFERENT THAN THE FINAL ARCHITECTURAL LAYOUT.
REFER TO ARCHITECTURAL DRAWINGS FOR ACTUAL DIMENSIONS
AND LAYOUT PLACEMENTS FOR SPACE CONDITIONS.

MECHANICAL DETAILS MAY OR MAY NOT BE DIRECTLY REFERENCED. ALL DETAILS SHOWN ARE TO BE USED FOR BASIS OF INSTALLATION IN ALL CASES, IN COORDINATED EFFORT WITH MANUFACTURERS INSTALLATION RECOMMENDATIONS.

MECHANICAL SHEETS ARE NOT INTENDED TO SPECIFICALLY BE TRADE SPECIFIC TO MECHANICAL INSTALLATION WORK. ALL MECHANICAL AND ELECTRICAL TRADES ARE RESPONSIBLE FOR FAMILIARIZING THEMSELVES AND INCLUDING A COMPLETE PACKAGE WITHIN THEIR OFFER FOR A COMPLETE SYSTEM.

AT COMPLETION OF WORK, DELIVER COMPLETED PROJECT RECORD DOCUMENTS MARKED WITH FIELD CHANGES TO OWNER.

PROVIDE A WRITTEN WARRANTY TO THE OWNER COVERING THE ENTIRE MECHANICAL WORK TO BE FREE FROM DEFECTIVE MATERIALS, EQUIPMENT AND WORKMANSHIP FOR A PERIOD OF 1 YEAR AFTER DATE OF ACCEPTANCE.

CLEAN EXPOSED SURFACES OF FURNACES, HOT WATER HEATERS, PLUMBING FIXTURES AND OTHER EXPOSED ITEMS OF GREASE, DIRT OR OTHER FOREIGN MATERIAL. REMOVE RUBBISH AND DEBRIS RESULTING FROM THE OPERATIONS AND LEAVE EQUIPMENT SPACES CLEAN AND READY FOR USE.

MAINTAIN ALL CEILING, FLOOR AND WALL FIRE AND SMOKE PROTECTION RATINGS. SEAL ALL CONDUIT AND ENCLOSURE PENETRATIONS TO COMPLY WITH UL ASSEMBLY AND BUILDING CODE REQUIREMENTS. ALL SEALANTS AND CONSTRUCTIONS SHALL BE APPROVED BY OWNER PRIOR TO APPLICATION. ALL OPENINGS SHALL BE SEALED DAILY.

CONTRACT DRAWINGS FOR MECHANICAL WORK ARE IN PART DIAGRAMMATIC, INTENDED TO CONVEY THE SCOPE OF WORK AND INDICATE GENERAL ARRANGEMENT OF EQUIPMENT, CONDUITS, AND APPROXIMATE SIZES AND LOCATIONS OF EQUIPMENT AND OUTLETS. MECHANICAL/ELECTRICAL TRADES SHALL FOLLOW THESE DRAWINGS IN LAYING OUT THEIR WORK, CONSULT GENERAL CONSTRUCTION DRAWINGS TO FAMILIARIZE THEMSELVES WITH ALL CONDITIONS AFFECTING THEIR WORK, AND SHALL VERIFY SPACES IN WHICH THEIR WORK WILL BE INSTALLED. COORDINATE WORK WITH OTHER TRADES AND AS PROJECT CONDITIONS REASONABLY REQUIRE WITHOUT EXTRA COSTS TO OWNER.

HVAC SPECIFIC:
ALL DUCTWORK DIMENSIONS, AS SHOWN ON THE DRAWINGS, ARE INTERNAL CLEAR DIMENSIONS AND DUCT SIZE SHALL BE INCREASED TO COMPENSATE FOR DUCT LINING THICKNESS.

PROVIDE ALL 90 DEGREE SQUARE ELBOWS WITH SINGLE RADIUS TURNING VANES UNLESS OTHERWISE INDICATED.

COORDINATE DIFFUSER, REGISTER, AND GRILLE LOCATIONS WITH ARCHITECTURAL REFLECTED CEILING PLANS, LIGHTING, AND OTHER CEILING ITEMS AND MAKE DUCT MODIFICATIONS TO SUIT.

AT CONTRATORS OPTION, FLEXIBLE DUCT MAY BE USED TO CONNECT SUPPLY REGISTERS AND DIFFUSERS ON THIS PROJECT ONLY. RUNS OF FLEXIBLE DUCT SHALL NOT EXCEED 5 FEET, UNLESS SPECIFICALLY SHOWN ON DRAWING.

ALL DUCTWORK SHALL BE COORDINATED WITH ALL TRADES INVOLVED. OFFSETS IN DUCTS, INCLUDING DIVIDED DUCTS AND TRANSITIONS AROUND OBSTRUCTIONS, SHALL BE PROVIDED AT NO ADDITIONAL COST TO THE OWNER.

MECHANICAL SYSTEMS SHALL COMPLY WITH INTERNATIONAL MECHANICAL CODE VER 2012 AND INTERNATIONAL ENERGY CODE VER 2012.

PLUMBING/PIPING SPECIFIC:

PLUMBING/PIPING SYSTEMS SHALL COMPLY WITH INTERNATIONAL FUEL GAS CODE VER 2012 AND UNIFORM PLUMBING CODE VER 2012.

UTILITIES:
LOCATION OF UNDERGROUND UTILITIES ARE APPROXIMATE. IT IS
THE RESPONSIBILITY OF THE CONTRACTOR TO DETERMINE EXACT

LOCATIONS IN THE FIELD (NOT ALL UTILITIES ARE SHOWN).

REGULATORY AND CODE REQUIREMENTS:
APPLY FOR AND PAY FOR ALL PERMITS, FEES, LICENSES AND
INSPECTIONS. ALL WORK IS SUBJECT TO APPROVAL BY THE CODE
OFFICIAL AND ENGINEER. ALL CORRECTIONS SHALL BE MADE

## PLUMBING/PIPING SYMBOLS DESCRIPTION SYMBOL DESCRIPTION

WITHOUT EXTRA COSTS TO OWNER.

PIPE MATERIAL AND INSTALLATION REQUIREMENTS											
SERVICE OR SYSTEM	MATERIAL	PIPE SIZE	INSULATION THICKNES	SPIPE SIZE	PRESSURE TEST*	NOTES:					
DOMESTIC COLD WATER	TYPE L COPPER, VIEGA PEX MODEL V5001 (INSIDE WALLS AND CRAWLSPACE ONLY), PRO-PRESS	ALL	1/2" FIBERGLASS	ALL	100 PSI AIR-30 MIN	1,2					
DOMESTIC HOT WATER (100-180 DEG F)	TYPE L COPPER, VIEGA PEX MODEL V5002 (INSIDE WALLS AND CRAWLSPACE ONLY), PRO-PRESS	ALL	1" FIBERGLASS	ALL	100 PSI AIR-30 MIN	1,2					
NATURAL GAS	BLACK T&C WITH BMI FITTINGS WELDED STEEL SCH 40	<=2" >2"	NONE	N/A	40 PSI AIR-60 MIN	2					
SANITARY SEWER U/G	SCHEDULE 40 PVC DWV, HUBLESS CAST IRON	ALL	NONE	N/A	20 PSI AIR-60 MIN						
SANITARY SEWER A/G	SCHEDULE 40 PVC DWV, HUBLESS CAST IRON	ALL	NONE	N/A	20 PSI AIR-60 MIN	2					
CONDENSATE  NOTES:	SCHEDULE 40 PVC DWV (FLEXIBLE TUBING NOT ALLOWED)	ALL	NONE	N/A	VISUAL INSPECTION						

INSULATION TO BE OF HEAVY DENSITY BONDED FIBERGLASS WITH ALL SERVICE JACKET (WHITE). FITTING TO BE PVC ZESTON COVERS WITH FLEXIBLE INSULATION WRAP. SEAL ALL JOINTS WITH SEALANT. K VALUE NOT EXCEEDING 0.27 BTU PER IN/H\*FT^2\*DEG F.
SEISMIC BRACE ALL PIPE GREATER THAN 2-1/2" ID PER LOCAL CODE.

GENERAL NOTE ALL: SEAL ALL NON RATED STRUCTURE PIPE PENETRATIONS INCLUDING DRAFT STOPS WITH SILICON OR FIRE RATED EXPANDING FOAM. SEAL ALL RATED PIPE PENETRATIONS IN ACCORDANCE WITH CONTRACTOR SELECTED MFR FIRE CAULK SYSTEM (AND/OR FIRE COLLAR) AND MATCH RATING WITH SPECIFIC UL LISTING. PROVIDE ENGINEER AND INSPECTOR FOR AHJ WITH SHOP DRAWING OF RATED ASSEMBLY PRIOR TO INSTALLATION.

\* PROVIDE WRITTEN AND SIGNED REPORT BY CONTRACTOR FOR ALL SYSTEMS TESTED, TYPE OF TEST, DATE, PRESSURE, TIME START, TIME END, AND SYSTEM TESTED. SUBMIT TO ENGINEER IN IOM SUBMITTAL.

SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION
<b>─</b> ₩	GATE, BALL, OR FUEL SOV VALVE	<b>─-    </b>	UNION, THREADED OR FLANGED
	GLOBE VALVE	WH	WATER HAMMER ARRESTOR
——IŌI——	GAS COCK		FLOOR DRAIN
—–₁₹⊢—–	PLUG VALVE	•	FLOOR SINK
	SOLENOID VALVE	0	FLOOR CLEANOUT, INT. OR EXT.
PRV	PRESSURE REDUCING VALVE	CO	WALL CLEANOUT
	CHECK VALVE	,工	1/4 TURN BOILER DRAIN W/CAP
₽	PRESS./TEMP. RELIEF VALVE	-+	HOSE BIBB, INTERIOR OR EXTERIOR
₩ <u>₩</u> ₩	RPP BACKFLOW PREVENTOR	Д н н	90 DEGREE ELBOW (UP, DOWN, PLAN)
-W-Ŭ-W-	DOUBLE CHECK BACKFLOW PREV.	요 은 년	TEE FITTING (UP, DOWN, PLAN)
	WATER METER	户	WYE (PLAN VIEW)
<u> </u>	PRESSURE REDUCING VALVE	Y'	COMBINATION WYE & 1/8 BEND
- P	THERMOMETER WITH WELL	T	WYE (VERTICAL) WITH 1/4 BEND
9	PRESSURE GAGE WITH SHUTOFF	√ 1	LONG RADIUS SAN. SEWER FITTING
Р	PRESSURE SWITCH	LABV	AUTOMATIC BALANCING VALVE
$\bigcirc$	PUMP	MBV	MANUAL BALANCING VALVE
	CONTROL VALVE, 2-WAY		DIRECTION OF FLOW
——————————————————————————————————————	CONTROL VALVE, 3-WAY	<del></del>	STRAINER, CAST IRON OR BRONZE
	NG OR LP EQUIPMENT REGULATOR	<del></del>	STRAINER WITH BLOW DOWN & PLUG
	FLEXIBLE PIPE CONNECTOR	<b>─</b> ⊗─	EXPANSION VALVE
s	STEAM TRAP	_ <del>[</del>	AUTO AIR VENT, EXTEND TO DRAIN
$\bigcirc$	PUMP OR CIRCULATOR	Fs OR F	FLOW SWITCH



#### CALL BEFORE YOU DIG

## MEP ABBREVIATIONS

ABOVE FINISHED FLOOR ABOVE FINISHED GRADE AFG ABOVE GRADE B/G **BELOW GRADE** CONDENSATE DRAIN COND CHILLED (HYDRONIC) WATER RETURN CHILLED (HYDRONIC) WATER SUPPLY CWS DCW DOMESTIC (POTABLE) COLD WATER DHW DOMESTIC (POTABLE) HOT WATER DHWR DOMESTIC HOT WATER RETURN **ENTERING AIR ELECTRICAL CONTRACTOR EXHAUST** G-SAN **GREASE SANITARY SEWER** GENERAL CONTRACTOR HVAC CONTRACTOR HOT (HYDRONIC) WATER RETURN HWR HOT (HYDRONIC) WATER SUPPLY HWS HIGH PRESSURE IN JOIST SPACE LEAVING AIR PROPANE GAS MIXED AIR MECHANICAL CONTRACTOR MEDIUM PRESSURE MEDIUM PRESSURE NATURAL GAS MPG NATURAL GAS OUTSIDE/OUTDOOR AIR PLUMBING CONTRACTOR RETURN AIR RECT RECTANGULAR SUPPLY AIR SANITARY SEWER STORM WATER SEWER

#### GENERAL CONSTRUCTION NOTES

ALL WORK PERFORMED IN CONJUNCTION WITH THESE DRAWINGS SHALL MEET ALL CURRENT APPLICABLE BUILDING AND ENERGY CODES.

STM

SYS

TEMP

STEAM

SYSTEM

VENT

TERMPERATURE

ALL WORK PERFORMED IN CONJUNCTION WITH THESE DRAWINGS IS SUBJECT TO APPROVAL BY THE AUTHORITY HAVING JURISDICTION (CODE OFFICIAL).

ALL ROOF PENETRATIONS SHALL BE PATCHED AND SEALED, WITH WARRANTY FROM BUILDING ROOFING CONTRACTOR.

THIS SET OF DOCUMENTS IS INTENDED FOR AHJ
REVIEW AND SHALL BE CONSIDERED AS
CONSTRUCTION DOCUMENTS. IT SHALL BE THE SOLE
RESPONSIBILITY OF THE CONTRACTOR TO
COORDINATE ALL CONDITIONS, EXISTING AND/OR NEW,
OF THE SITE AS WELL AS LOCATIONS, QUANTITIES,
TYPE AND STYLE OF ALL PRODUCTS PROVIDED, WITH
OWNER, PRIOR TO ORDERING OR INSTALLING.

SHEET INDEX								
SHEET NUMBER	SHEET TITLE							
M 0.0	PROJECT REQUIREMENTS & SPECIFICATIONS							
M 0.1	MECHANICAL SCHEDULES & DETAILS							
M 1.0	MECHANICAL PLANS							
E 0.0	ELECTRICAL REQUIREMENTS & SPECIFICATIONS							
E 1.0	ELECTRICAL PLANS							

## Dawes Engineering & Design

**PERMIT SET** 

Helena, MT 59601

(406) 441-4000 p

THESE PLANS ARE INSTRUMENTS
OF PROFESSIONAL SERVICES AND
ARE PROTECTED BY COMMON
LAW, STATUTORY AND OTHER
RESERVED RIGHTS INCLUDING
COPYRIGHT. DRAWINGS MAY NOT
BE REPRODUCED OR USED FOR
ANY PURPOSE WITHOUT THE
WRITTEN CONSENT OF DAWES
ENGINEERING & DESIGN COMPANY.



MONTANA FWP - BIG SPRINGS FISH HATCHERY

2051 FISH HATCHERY ROAD LEWISTOWN, MT. 59457


PROJECT
REQUIREMENTS &
SPECIFICATIONS


REV #: REV DATE: 
REV # DATE

SHEET NUMBER

M O.O

109





ECTRICAL LEGEND
DESCRIPTION
DUPLEX OUTLET, STANDARD HEIGHT/COORD ELEV.
DOUBLE DUPLEX RECEPTACLE
GROUND FAULT CIRCUIT INTERRUPTER OUTLET
220 VOLT RECEPTACLE
WEATHER PROOF OUTLET WITH COVER W/ GFCI
DUPLEX OUTLET, ELEVATION CALLOUT
JUNCTION BOX
BRANCH CIRCUIT PANEL
FUSED DISCONNECT SWITCH
COMBINATION MOTOR STARTER / DISCONNECT
STARTER/CONTACTOR
THERMOSTAT
SWITCH, WIND UP TIMER
SWITCH, PILOT DUTY/CONTROL LEG CONTACTOR
SWITCH, SPST
SWITCH, SPDT
SWITCH, 3-WAY
SWITCH, 4-WAY
SWITCH, OCCUPANCY SENSOR-DUAL TECHNOLOGY
SWITCH, OCCUPANCY SENSOR-MOTION DETECTOR
OCCUPANCY SENSOR, CEILING
SWITCH, PHOTOCELL WITH REMOTE CONTROLLER
SWITCH, OCCUPANCY SENSOR-DUAL TECHNOLOGY
FIRE ALARM STROBE
FIRE ALARM HORN/STROBE
FIRE ALARM SMOKE DETECTOR
FIRE ALARM HEAT SENSOR
FIRE ALARM DUCT SMOKE DETECTOR
FIRE ALARM PULL STATION
FIRE ALARM DOOR HOLD
EXIT LIGHT FIXTURE
EXIT LIGHT FIXTURE WITH DIRECTIONAL ARROW
EMERGENCY LIGHT FIXTURE WITH EXIT SIGN
EMERGENCY LIGHT FIXTURE
TELEPHONE/DATA OUTLET (COMBINATION)
TELEPHONE OUTLET OR DATA OUTLET
CEILING LIGHT
WALL LIGHT
CIRCUIT HOMERUN
REPRESENTS EXISTING CONDITION

#### ELECTRICAL HARDWARE CONDUIT & RACEWAYS SHALL BE CONCEALED AND APPROVED FOR USE AND LOCATION. DRY LOCATIONS - GRC, IMC, EMT. UNDERGROUND GRC, PVC. FLEXIBLE CONDUIT - ALLOWED ONLY FOR CONNECTION OF EQUIPMENT AND LIMITED TO LENGTHS OF SIX FEET. GALVANIZED, LIQUID TIGHT. MC OR AC ALLOWED WHEN PROTECTED. PROVIDE SEPARATE EQUIPMENT GROUNDING CONDUCTOR IN CONDUIT. NM-B CABLE - NOT ALLOWED. DRY LOCATIONS - STEEL WITH COVERS. - CAST ALUMINUM. WET LOCATIONS SIZE PER NEC. COUPLINGS AND CONNECTORS: GRC - THREADED IMC - THREADED EMT - DRY-COMPRESSION OR SET SCREW, BOTH OF STEEL, WET-RAIN TIGHT PVC - CEMENT JOINT TYPE INDENTER TYPE CONNECTORS PROHIBITED. CABELING DEVICES AND PLATES: DUPLEX OUTLETS - HUI - HUBBELL #CR20 SERIES, 20 AMP (OR APPROVED EQUAL) GFCI OUTLETS - HUBBELL #GF20 SERIES, 20 AMP (OR APPROVED EQUAL) - HUBBELL #CS120 SERIES (OR APPROVED EQUAL) AC SWITCHES FOR 3 WAY OR 4 WAY USE EQUIVALENT DEVICE COLOR - COORDINATE COLOR W/ OWNER OR ARCHITECT

PLATES

STEEL

WOOD

OCCUPANCY SENSORS

SOLID MASONRY

ANCHORS: HOLLOW MASONRY - TOGGLE BOLT.

COMPLY WITH ADA REQUIREMENT.

- EXPANSION BOLT.

WOOD SCREWS.

- METAL MACHINE SCREWS, BOLTS.

MOUNTING HEIGHTS							
DESCRIPTION	HEIGHT UNLESS OTHERWISE NOTED						
THERMOSTAT, CONTROLLER	48"						
WALL SWITCH/ OCCUPANCY SENSOR	46"						
CONVENIENCE OUTLET	18"						
WALL SWITCHES	46"						
TELEPHONE/DATA/TV OUTLETS	18"						
FIRE ALARM MANUAL STATION	42"						
FIRE ALARM HORNS & STROBES	80"-96" AFF TO CENTER OF STROBE						
EXIT SIGN	CENTER, 4" ABOVE DOOR						
MANUAL MOTOR STARTER SWITCH	42"						
PANELBOARDS, CABINETS	72"						

UNLESS NOTED OTHERWISE. MATCH EXISTING MOUNTING HEIGHTS WHICH

- NYLON. COORDINATE COLOR W/ OWNER OR ARCHITECT

- HUBBELL #WS120W (OR APPROVED EQUAL)

#### BASIC ELECTRICAL REQUIREMENTS

FURNISH ALL LABOR AND MATERIALS AND PERFORM ALL OPERATIONS NECESSARY FOR THE INSTALLATION OF COMPLETE AND OPERATING ELECTRICAL SYSTEMS SUBJECT TO THE CONDITIONS OF THE CONTRACT. PROVIDE SATISFACTORY OPERATION OF ALL EQUIPMENT AND CONTROLS TO THE ARCHITECT/ENGINEER UPON REQUEST.

ALL MATERIALS SHALL BE NEW. SUBSTITUTIONS SHALL BE APPROVED BY OWNER AND/OR ENGINEER.

VISIT THE PREMISES BEFORE SUBMITTING BID AS NO CHANGE ORDERS WILL BE ALLOWED FOR LACK OF KNOWLEDGE OF EXISTING CONDITIONS.

COORDINATE AND ORDER THE PROGRESS OF WORK TO CONFORM TO THE PROJECT SCHEDULE AND THE PROGRESS OF THE WORK OF THE OTHER TRADES.

ELECTRICAL DRAWINGS ARE DIAGRAMMATIC AND BECAUSE OF THE SMALL SCALE, IT IS NOT POSSIBLE TO INDICATE EVERY REQUIRED OFFSET, FITTING, ETC. VERIFY ALL SPACE REQUIREMENTS, COORDINATING WITH OTHER TRADES, AND INSTALL THE SYSTEMS IN THE SPACE PROVIDED WITHOUT EXTRA CHARGES TO THE OWNER.

PERFORM WORK IN ACCORDANCE WITH GOOD COMMERCIAL PRACTICE. THE GOOD APPEARANCE OF THE FINISHED WORK SHALL BE OF EQUAL IMPORTANCE WITH ITS ELECTRICAL EFFICIENCY AND INTENT. THE OWNER MAY REJECT WORK IF WORKMANSHIP AND APPEARANCE ARE NOT SATISFACTORY.

INSTALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH THE MANUFACTURERS' RECOMMENDATIONS UNLESS SPECIFICALLY INDICATED OTHERWISE, OR WHERE LOCAL CODES OR REGULATIONS TAKE PRECEDENCE.

COMPLY WITH STATE AND LOCAL CODE REQUIREMENTS AND ORDINANCES. COMPLY WITH REQUIREMENTS OF THE UTILITY COMPANIES. IN THE CASE OF DIFFERENCES BETWEEN THESE REQUIREMENTS AND ORDINANCES, THE MOST STRINGENT SHALL GOVERN. CALL FOR INSPECTIONS REQUIRED BY LOCAL BUILDING INSPECTION AUTHORITY.

PLANS AND SPECIFICATIONS GO HAND IN HAND. WHAT IS REQUIRED IN ONE IS REQUIRED IN BOTH. WHERE CONFLICTS BETWEEN SPECIFICATIONS AND PLANS EXIST, THE MOST STRINGENT REQUIREMENTS SHALL APPLY.

ELECTRICAL PLANS SUPERCEDE ARCHITECTURAL PLANS. BACKGROUND FLOOR PLANS USED FOR ELECTRICAL DRAWINGS MAY SHOW DIFFERENT THAN THE FINAL ARCHITECTURAL LAYOUT. REFER TO ARCHITECTURAL DRAWINGS FOR ACTUAL DIMENSIONS AND LAYOUT PLACEMENTS FOR SPACE CONDITIONS.

ELECTRICAL DETAILS MAY OR MAY NOT BE DIRECTLY REFERENCED. ALL DETAILS SHOWN ARE TO BE USED FOR BASIS OF INSTALLATION IN ALL CASES, IN COORDINATED EFFORT WITH MANUFACTURERS INSTALLATION RECOMMENDATIONS.

ELECTRICAL SHEETS ARE NOT INTENDED TO SPECIFICALLY BE TRADE SPECIFIC TO ELECTRICAL INSTALLATION WORK. ALL MECHANICAL AND ELECTRICAL TRADES ARE RESPONSIBLE FOR FAMILIARIZING THEMSELVES AND INCLUDING A COMPLETE PACKAGE WITHIN THEIR OFFER FOR A COMPLETE SYSTEM.

112

AT COMPLETION OF WORK, DELIVER COMPLETED PROJECT RECORD DOCUMENTS MARKED WITH FIELD CHANGES TO OWNER.

PROVIDE A WRITTEN WARRANTY TO THE OWNER COVERING THE ENTIRE ELECTRICAL WORK TO BE FREE FROM DEFECTIVE MATERIALS, EQUIPMENT AND WORKMANSHIP FOR A PERIOD OF 1 YEAR AFTER DATE OF ACCEPTANCE.

CLEAN EXPOSED SURFACES OF LIGHT FIXTURES, SWITCHGEAR, AND OTHER EXPOSED ITEMS OF GREASE, DIRT OR OTHER FOREIGN MATERIAL. REMOVE RUBBISH AND DEBRIS RESULTING FROM THE OPERATIONS AND LEAVE EQUIPMENT SPACES CLEAN AND READY FOR USE.

MAINTAIN ALL CEILING, FLOOR AND WALL FIRE AND SMOKE PROTECTION RATINGS. SEAL ALL CONDUIT AND ENCLOSURE PENETRATIONS TO COMPLY WITH UL ASSEMBLY AND BUILDING CODE REQUIREMENTS. ALL SEALANTS AND CONSTRUCTIONS SHALL BE APPROVED BY OWNER PRIOR TO APPLICATION. ALL OPENINGS SHALL BE SEALED DAILY.

CONTRACT DRAWINGS FOR ELECTRICAL WORK ARE IN PART DIAGRAMMATIC, INTENDED TO CONVEY THE SCOPE OF WORK AND INDICATE GENERAL ARRANGEMENT OF EQUIPMENT, CONDUITS, AND APPROXIMATE SIZES AND LOCATIONS OF EQUIPMENT AND OUTLETS. MECHANICAL/ELECTRICAL TRADES SHALL FOLLOW THESE DRAWINGS IN LAYING OUT THEIR WORK, CONSULT GENERAL CONSTRUCTION DRAWINGS TO FAMILIARIZE THEMSELVES WITH ALL CONDITIONS AFFECTING THEIR WORK, AND SHALL VERIFY SPACES IN WHICH THEIR WORK WILL BE INSTALLED. COORDINATE WORK WITH OTHER TRADES AND AS PROJECT CONDITIONS REASONABLY REQUIRE WITHOUT EXTRA COSTS TO OWNER.

ELECTRICAL SPECIFIC: RACEWAYS SHALL BE LEFT WITH 30% FREE SPACE FOR FUTURE NEEDS.

SHARING OF NEUTRALS BETWEEN PHASES SHALL NOT BE ALLOWED.

SEPARATE GROUNDING CONDUCTORS SHALL BE PROVIDED IN ALL RACEWAYS.

CONDUCTORS SHALL BE COPPER. COLOR CODING SHALL BE NEC APPROVED AND AT MINIMUM SHALL BE AS FOLLOWS: 120/208 VOLT-BLACK, RED, BLUE FOR PHASE CONDUCTORS, WHITE FOR NEUTRAL CONDUCTORS. 277/480 VOLT-BROWN, ORANGE, YELLOW FOR PHASE CONDUCTORS, GRAY FOR NEUTRAL CONDUCTORS. GROUNDING CONDUCTORS SHALL BE GREEN.

ELECTRICAL SYSTEMS SHALL COMPLY WITH 2014 NATIONAL ELECTRICAL CODE AND BE INSTALLED BY LICENSED CONTRACTORS. LIGHTING SHALL COMPLY WITH THE 2012 IECC.

LOCATION OF UNDERGROUND UTILITIES ARE APPROXIMATE. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO DETERMINE EXACT

LOCATIONS IN THE FIELD (NOT ALL UTILITIES ARE SHOWN).

REGULATORY AND CODE REQUIREMENTS: APPLY FOR AND PAY FOR ALL PERMITS, FEES, LICENSES AND INSPECTIONS. ALL WORK IS SUBJECT TO APPROVAL BY THE CODE OFFICIAL AND ENGINEER. ALL CORRECTIONS SHALL BE MADE WITHOUT EXTRA COSTS TO OWNER.



#### CALL BEFORE YOU DIG

#### MEP ABBREVIATIONS

ABOVE FINISHED FLOOR AFG ABOVE FINISHED GRADE A/G B/G ABOVE GRADE **BELOW GRADE** COND CONDENSATE DRAIN CWR CHILLED (HYDRONIC) WATER RETURN CWS CHILLED (HYDRONIC) WATER SUPPLY DCW DOMESTIC (POTABLE) COLD WATER DHW DHWR DOMESTIC (POTABLE) HOT WATER DOMESTIC HOT WATER RETURN EA **ENTERING AIR** EC ELECTRICAL CONTRACTOR EX **EXHAUST** G-SAN GREASE SANITARY SEWER GC HC HWR HWS HP IJS GENERAL CONTRACTOR HVAC CONTRACTOR HOT (HYDRONIC) WATER RETURN HOT (HYDRONIC) WATER SUPPLY HIGH PRESSURE IN JOIST SPACE LEAVING AIR PROPANE GAS MIXED AIR MC MECHANICAL CONTRACTOR MEDIUM PRESSURE MPG MEDIUM PRESSURE NATURAL GAS NG NATURAL GAS OA PC RA OUTSIDE/OUTDOOR AIR PLUMBING CONTRACTOR RETURN AIR RECT RECTANGULAR SUPPLY AIR SAN SANITARY SEWER SS STORM WATER SEWER STM SYS SYSTEM

#### GENERAL CONSTRUCTION NOTES

TERMPERATURE

TEMP

ALL WORK PERFORMED IN CONJUNCTION WITH THESE DRAWINGS SHALL MEET ALL CURRENT APPLICABLE BUILDING AND ENERGY CODES.

ALL WORK PERFORMED IN CONJUNCTION WITH THESE DRAWINGS IS SUBJECT TO APPROVAL BY THE AUTHORITY HAVING JURISDICTION (CODE OFFICIAL).

ALL ROOF PENETRATIONS SHALL BE PATCHED AND SEALED, WITH WARRANTY FROM BUILDING ROOFING CONTRACTOR.

THIS SET OF DOCUMENTS IS INTENDED FOR AHJ REVIEW AND SHALL BE CONSIDERED AS CONSTRUCTION DOCUMENTS. IT SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE ALL CONDITIONS, EXISTING AND/OR NEW, OF THE SITE AS WELL AS LOCATIONS, QUANTITIES, TYPE AND STYLE OF ALL PRODUCTS PROVIDED, WITH OWNER, PRIOR TO ORDERING OR INSTALLING.

#### PERMIT SET

## Dawes Engineering & Design

46 Hibbard Way Helena, MT 59601

(406) 441-4000 p

THESE PLANS ARE INSTRUMENTS OF PROFESSIONAL SERVICES AND ARE PROTECTED BY COMMON LAW, STATUTORY AND OTHER RESERVED RIGHTS INCLUDING COPYRIGHT. DRAWINGS MAY NOT BE REPRODUCED OR USED FOR ANY PURPOSE WITHOUT THE WRITTEN CONSENT OF DAWES ENGINEERING & DESIGN COMPANY





MONTANA FWP - BIG SPRINGS FISH HATCHERY


2051 FISH HATCHERY ROAD LEWISTOWN, MT. 59457

DATE 08/20/18
DRAWN BY:
CHECKED BY: SHEET CONTENTS: REV #: REV DATE: **ELECTRICAL** REV# REQUIREMENTS & **SPECIFICATIONS** 

E 0.0







	GAS FIRED UNIT HEATER SCHEDULE											(UH\ #/	
EQUIPMEN NO.	T SERVICE	CFM	INPUT (BTU)	OUTPUT (BTU)	EFFIC- IENCY A.F.U.E.	RATE	GAS CONN. SIZE	VENT OUTLET SIZE	AMPS	ELECTRIC VPHCY.	MOTOF HP	MANUFACTURER & MODEL	OPTIONS- ACCESSORIES
UH-1	HEATING	3843	300K	249K	83%	-	3/4	6	11	115-1-60	1/2	REZNOR UDAS-300	1,2,3,4
UH-2	HEATING	3843	300K	249K	83%	-	3/4	6	11	115-1-60	1/2	REZNOR UDAS-300	1,2,3,4
UH-3	HEATING	1345	105K	87.15K	83%	-	1/2	4	3.9	115-1-60	1/20	REZNOR UDAS-100	1,2,3,4

- 1. ADD FACTORY VERTICAL COMBUSTION AIR/VENT KIT.
- 2. PROVIDE HONEYWELL T800 OR EQUAL.
- PROVIDE WITH 30° DOWNTURN NOZZLE.
   FAN IS TO RUN DURING OCCUPIED PERIODS 8AM TO 6PM EVERY DAY TO MOVE AIR INSIDE BUILDING FOR RADON MITIGATION.

DUCTLESS SPLIT AIR CONDITIONING SYSTEM SCHEDULE $\frac{CUVACV}{\#}$											
EQUIP	OED/IOE	COOLING/HEATING CAPACITY	0514	REFRIGERANT	DESIGN TEM	PERATURE (°F)		ELECTRICAL	MANUFACTURED & MORE	NOTEO	
NO.			CFM	REFRIGERANT	INDOOR	OUTDOOR MCA VOLTPHCY.		VOLTPHCY.	MANUFACTURER & MODEL	NOTES	
AC-1	HEAT PUMP	12,000/14,200	406	R410-A	70 DB	47 DB/43 WB	13	220-1-60	TOSHIBA RAS-12EKV-UL	1,2	
CU-1	HEAT PUMP	12,000/14,200	406	R410-A	70 DB	47 DB/43 WB	13	220-1-60	TOSHIBA RAS-12EAV2-UL	1,2,3	
NOTES	NOTE:										

1. PROVIDE WITH WIRED CONTROLLER TO BE MOUNTED ON WALL AS SHOWN IN PLANS.

REFRIGERANT PIPING TO BE INSULATED SEPARATELY.
 CONDENSING UNIT TO BE INSTALLED INDOORS AS SHOWN ON PLANS.

FAN SCHEDULE

| FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN SCHEDULE | FAN S

# PERMIT SET Dawes Engineering & Design

46 Hibbard Way Helena, MT 59601

59601 (406) 441-4000 p

THESE PLANS ARE INSTRUMENTS
OF PROFESSIONAL SERVICES AND
ARE PROTECTED BY COMMON
LAW, STATUTORY AND OTHER
RESERVED RIGHTS INCLUDING
COPYRIGHT. DRAWINGS MAY NOT
BE REPRODUCED OR USED FOR
ANY PURPOSE WITHOUT THE
WRITTEN CONSENT OF DAWES
ENGINEERING & DESIGN COMPANY.



MONTANA FWP - BIG SPRINGS FISH HATCHERY

2051 FISH HATCHERY ROAD LEWISTOWN, MT. 59457

