HELENA, MT 59601

406.841.4013

CONTACT: PAUL VALLE

ARCHITECT

FAURE HALVORSEN ARCHITECTS, PC

1425 WEST MAIN STREET, SUITE A

BOZEMAN, MT 59715 406.587.1204

PROJECT ARCHITECT: MATT FAURE

MECHANICAL / PLUMBING

3 RIVERS ENGINEERING 24 S WILSON AVE

BOZEMAN MT. 59715

406.582.8288

PROJECT ENGINEER: JOHN TETRAULT

GENERAL CONTRACTOR

TBD

GENERAL PROJECT NOTES

- Any ambiguities or discrepancies discovered by the use of these drawings shall immediately be reported to the Architect. Failure to cooperate by notice to the Architect prior to any construction relieves the Architect of all liability and responsibility for the consequences.
- Changes or deviations from the drawings made without the written consent of the Architect are unauthorized and shall relieve the Architect of all responsibility for the consequences.
- All construction and construction methods to be in accordance with 2012 IBC, 2012 UPC, (IAPMO), 2012 IFGC, 2012 NEC, 2012 IMC and applicable codes, governmental agencies, and local design criteria.
- All dimensions given are to face of stud or face of concrete (U.N.O.). General Contractor to verify all dimensions prior to construction. DO NOT SCALE
- General Contractor to verify all equipment rough-in dimensions and clearances with the manufactures prior to construction.
- The design, adequacy, and safety of erection bracing, shoring, temporary supports, etc. is the sole responsibility of the General Contractor and has not been considered by the Architect and Engineer. The General Contractor is responsible for the stability of the structure prior to the completion of all sheer walls, roof and floor diaphragms, and
- General contractor to provide all pertinent permits prior to construction.

GENERAL SITE PLAN NOTES

- Location of project is approximate. Owner representative will verify and approve final location with contractor and surveyor at the time of the project staking.
- 2. Location of proposed driveway is approximate. Owner representative will verify and approve final location with contractor at the time of project staking.
- Location of proposed water stub, sewer stub and utility stubs are approximate. Owner representative will verify and approve final location. Engineer will verify and approve final location with contractor and surveyor at the time of project staking.
- 4. All utilities are to be underground. 5. All special terrain features to be preserved.

SHEET LIST

Sheet Number	Sheet Name	
G 1.1	PROJECT INFORMATION	
A1.1	SITE PLAN	
D 2.1	MAIN LEVEL DEMO PLAN	
D2.2	ROOF DEMO PLAN	
A2.1	MAIN LEVEL FLOOR PLAN	
A2.2	ROOF PLAN	
A3.1	EXTERIOR BUILDING ELEVATIONS	
A3.2	EXTERIOR BUILDING ELEVATIONS	
A4.1	BUILDING SECTIONS	
A5.1	INTERIOR ELEVATIONS, STAIR DETAILS & SCHEDULES	
52 .1	CONCRETE PLAN	
52.2	ROOF FRAMING PLAN	
M1.1	MAIN LEVEL MECHANICAL DEMO PLAN	
M2.1	MAIN AND ROOF MECHANICAL PLAN	
P1.0	BELOW SLAB PLUMBING DEMO PLAN	
P1.1	MAIN LEVEL PLUMBING DEMO PLAN	
P2.1	BELOW SLAB PLUMBING PLAN	
P2.2	MAIN & ROOF PLUMBING PLAN	
E 1.1	MAIN LEVEL ELECTRICAL PLAN	
E2 .1	MAIN LEVEL ELECTRICAL	
E 3.1	ELECTRICAL SCHEDULES	

VICINITY MAP



PROJECT INFO

PROJECT TYPE: CONCESSIONS RENOVATION PROJECT LOCATION MHITEHALL, MONTANA OCCUPANCY GROUP: A-2 CONSTRUCTION TYPE: YB APPLICABLE CODES 2012 IBC ALLOWABLE AREA PER FLOOR: 6000 PROPOSED AREA AT GROUND FLOOR: 2383

ARCHITECTURAL SYMBOLS

DETAIL REFERE	<u>ince</u>	MATERIALS	
X AX.X	Detail no. Sheet Reference	CONCRETE	-
ELEVATION/SECTION REFERENCE		SAND	5 222223333
AX.X	— Detail no. — Sheet Reference	ROUGH LUMBER	
INTERIOR ELEV	ATION REFERENCE	FINISHED LUMBER	
1 (AX.X) 1	DETAIL NO.	CMU WALL	-
1 ROOM NAME \$		BRICK	<u> </u>
ROOM NAM	ROOM NAME	21.00.	
101)		RIGID INSULATION	
DOOR NUMBER		BATT INSULATION	
D101-1	ROOM NUMBER DOOR NUMBER	EARTH	
NORTH ARRON	REFERENCE	GRAVEL	
PLA NOR		FLYMOOD	\
NORTH NORTH		STEEL	\
REVISION NUME	B <u>er</u>	STONE VENEER	[[[[[[]]]]]]
MATERIAL REFERENCE		GYPSUM BOARD	\$ (270,700,000)
BUILDING SECTI	ON CUT	GLASS	F
Ī	\bigstar	ALUMINUM	* //// //// ///

GENERAL CONSTRUCTION NOTES

- Concrete foundation walls will extend a minimum of 6" above finish grade and will be treated with damp proofing on the exterior face from finish grade level to the bottom
- Concrete slabs on grade will be 4" thick (see structural) and placed over reflective blanket insulation over 6" crushed gravel base over 8 mil polyethylene vapor retarder (interior only U.N.O). Provide troweled finish at interior locations and colored stamped
- and color with broom finish at exterior locations where exposed. All slabs are sealed. Structural lumber exposed to weather will be pressure treated or of natural resistance to decay. Maintain minimum clearance between structural lumber and soil as
- defined by the International Residential Code and all other applicable codes. Sill plate will consist of treated 2x6 or 2x6 cedar and will be installed over fiberglass
- sill sealer. (U.N.O.) Exterior and structural partitions will be 2x6 @ 16" o.c. minimum.
- Exterior wall sheathing will continue 1" below the sill plate connection (U.N.O.) Exterior framed walls will have Benjamin Obdyke InvisiMrap installed over the sheathing. At each window and door opening, cut the housewrap flush with opening,
 - then cut housewrap back 2 inches at jamb and sill. Install HydroFlash at sill, corner patches, jamb flashing. Install per manf. spec. Provide insulation as follows:

.R-49 (min.) (U.N.O.)

- ..R-21 (min.) (U.N.O.) Exterior walls:. ..R-30 (min.) (U.N.O.) Floors over unheated space: Perimeter of slab on grade:.. ..R-15 @ 48" (min.) (U.N.O.) Door and window frames will be sealed with spray applied urethane foam insulation.
- fixtures, millwork, casework, etc. Backer board for ceramic tile will be 1/2" fiberglass reinforced cementitious board

Provide adequate blocking in wall for the attachment of all equipment, plumbing


Provide ice and water barrier over entire roof.

Roofs over heated space:

- Provide attic space ventilation as required by applicable codes. Coordinate type and location of vents with Architect prior to construction.
- Provide access doors to all attic spaces greater than 30" in height. Refer to Floor Plans for access locations.
- Provide tempered glass at hazardous locations including French glass doors and any other locations as defined by the International Residential Code and all other
- All stairs comply with IBC standards and requirements.
- Provide a passive radon mitigation system under slab, contractor to provide shop drawings for approval.
- Provide gutters over all pedestrian and vehicular eaves for snow and water protection. Put downspouts with heated drain leaders to daylight for drainage.


GENERAL DIMENSIONS

- ALL INTERIOR PARTITIONS ARE DIMENSIONED TO FACE OF STUD OR CONCRETE UNLESS NOTES OTHERWISE.
- THE TERM "EQUAL" OR "EQ." IS USED IN LIEU OF ACTUAL DIMENSIONS WHERE EQUAL SPACING OF ELEMENTS IS REQUIRED.
- THE TERM "CLEAR" IS USED TO DENOTE A MINIMUM DIMENSIONAL REQUIREMENT; HOMEVER THE DIMENSION COULD BE LARGER.
- WALLS CENTERED ON A COLUMN OR GRID LINE WILL NOT BE DIMENSIONED ON PLANS BUT WILL BE DRAWN AS INDICATED BELOW.




DOORS AND OPENINGS IN WALLS NOT CMU: . AT A RIGHT ANGLE ARE TO BE


INSTALLED 4 INCHES FROM SAID CONDITION. THIS CONDITION IS TYPICAL AND WILL NOT BE DIMENSIONED.




DOORS NOT LOCATED BY A WALL AT A RIGHT ANGLE WILL BE DIMENSIONED TO CENTER OR DOOR FRAME OPENING.




OPENINGS NOT LOCATED BY A WALL AT A RIGHT ANGLE WILL BE DIMENSIONED TO THE JAMB OF OPENING AND THE OPENING WILL BE DIMENSIONED.



D. DOORS OR OPENINGS LOCATED WITHIN A CMU WALL AT A RIGHT ANGLE TO AN ADJACENT WALL ARE TO BE INSTALLED 10 INCHES FROM SAID CONDITION.



DOORS OR OPENINGS LOCATED BETWEEN TWO WALLS WITH A DISTANCE OF LESS THAN 4 INCHES POSSIBLE FROM EITHER WALL ARE TO BE CENTERED BETWEEN WALLS. THIS CONDITION IS TYPICAL AND WILL NOT BE DIMENSIONED.



- DO NOT SCALE DRAWINGS FOR DIMENSIONS. DIMENSIONS ARE INDICATED IN
- 7. LOCATE FLOOR TRANSITIONS AT CENTERLINE OF ADJOINING DOORS UNLESS NOTED OTHERWISE.

ABBREVIATIONS ANCHOR BOLTS A.F.F. ABOVE FINISHED FLOOR ACOUSTICAL ADJ. ADJACENT A/C AIR CONDITIONING ALT. ALTERNATE ALUM. ALUMINUM APPD. APPROVED B.O. BOTTOM OF BSMT. BASEMENT BRG. BEARING BLK BLOCK BLKG. BLOCKING BD. BOARD BLDG. BUILDING SECTIONS C.J. CONTROL JOINT CLG. CEILING CLR. CLEAR (ANCE) COL. COLUMN CONC. CONCRETE CONCRETE MASONRY UNIT CONST. CONSTRUCTION DTL. DETAIL DWG. DRAWING EACH E.F. EACH FACE E.J. EXPANSION JOINT ELEC ELECTRIC (AL) EQ. EQUAL EXISTING EXIST. E.M. EACH MAY F.D. FLOOR DRAIN FIN. FINISH FLR FLOOR FLUORESCENT FLUR. FTG. FOOTING F.B.O. FURNISHED BY OTHERS GA. GAUGE G.C. GENERAL CONTRACTOR GYP. BD. GYPSUM BOARD GROUND FAULT INTERRUPTED HDR HEADER HVAC HEATING / VENT / AIR COND. H.C. HOLLOW CORE H.M. HOLLON METAL HR. HOUR INCL. INCLUDE (D) (ING) INSUL INSULATE (D) (ING) INT. INTERIOR JT. TMIOL MANUFACTURER MTL METAL MASONRY OPENING MAX. MAXIMUM MECH. MECHANICAL MED. MEDIUM MILLIMETER (S) MIN. MINIMUM NOM. NOMINAL NO. NUMBER N.I.C. NOT IN CONTRACT N.T.S. NOT TO SCALE 0.0. ON CENTER 0.D. OUTSIDE DIAMETER PVMT. PAVEMENT PLATE PL. PLYMD. PLYWOOD PVC POLYVINYL CHLORIDE P.S.F. POUNDS PER SQ. FOOT P.S.I. POUNDS PER SQ. INCH PRESSURE TREATED RADIUS REFERENCE REQUIRED REINFORCE (ING) (MENT) ROUGH OPENING ROOF DRAIN R.S. ROUGH SAWN SIM. SIMILAR **S.C.** SOLID CORE SPEC. SPECIFICATION (S) SPEAKER SQUARE SYSTEM THICK (NESS) T&G TONGUE & GROOVE T.O.S. TOP OF STEEL TOP OF WALL T.O.M. TPL TRIPLE TYP. TYPICAL INTERNATIONAL BUILDING CODE I.B.C. UNLESS NOTED OTHERWISE

REF. REQ'D REINF. R.O. R.D.

SPKR. SQ. SYS. THK.


U.N.O. Y.C.T. VINYL COMPOSITION TILE

VAULTED CEILING YLT. V.T.R. VENT THROUGH ROOF V.B. VAPOR BARRIER MATER CLOSET

M.C. M.P. WATER PROOF (ING) M.M.F. MELDED WIRE FABRIC MIDTH, MIDE M

MITH W/ W/0 MITHOUT





 \mathbf{M} \mathbb{Z}^{N} ON





MDO/MDF PANEL

ASPHAL"










NOTE: COORDINATE THE AMOUNT OF DEMOLITION WORK REQUIRED WITH THE NEW CONSTRUCTION WORK AND IMPROVEMENTS SHOWN ELSEWHERE IN THIS SET OF DOCUMENTS.

DEMOLITION LEGEND		
	DEMOLITION	
	EXISTING	
	SLAB DEMO	





238

	KEY NOTES - DEMOLITION PLAN		
SYM.	DESCRIPTION		
1	REMOVE STAIRS & DECK COMPLETE, INCLUDING FOUNDATION COMPONENTS.		
2	CUT & REMOVE FRAMING COMPLETE. PROVIDE STRUCTURAL SHORING AS REQUIRED.		
3	REMOVE EXISTING MINDOM, TRIM, AND HARDWARE COMPLETE.		
4	REMOVE EXISTING SIDING AND ANY EXTERIOR TRIM.		
5	REMOVE EXISTING CABINETS & PLUMBING.		
6	REMOVE APPLIANCE/FIXTURE COMPLETE		
7	CUT & REMOVE FRAMING FOR OPENING. SEE DIMENSIONS		
8	CUT & REMOVE EXISTING ROOF STRUCTURE AND ROOFING MATERIALS AS INDICATED COMPLETE		
(q)	REMOVE EXISTING DOOR & FRAME COMPLETE		
10	REMOVE EXISTING PLUMBING. SEE MECH.		
11	CUT SLAB @ EXISTING BUILDING LINE AS SHOWN AND REMOVE		

NOTE: COORDINATE THE AMOUNT OF DEMOLITION WORK REQUIRED WITH THE NEW CONSTRUCTION WORK AND IMPROVEMENTS SHOWN ELSEWHERE IN THIS SET OF DOCUMENTS.

DEMOLITION LEGEND		
	DEMOLITION	
	EXISTING	
	SLAB DEMO	









1. ALL KITCHEN EQUIPMENT TO BE PROVIDED BY OWNER, EXCEPT EXHAUST HOOD, HOOD FIRE SUPPRESSION, VENTILATOR, AND MAKE UP AIR SYSTEM. SEE MECHANICAL FOR KITCHEN HOOD, EXHAUST, AND MAKE UP AIR SYSTEM.

2. EXHAUST HOOD, EXHAUST FAN, SUPPLY PLENUM, MAKE UP AIR \$ FAN TO BE SUPPLIED AND INSTALLED BY CONTRACTOR.


3. SHADE INDICATED ITEMS TO BE INCLUDED IN THE CONTRACT. ALL OTHER ITEMS ARE PROVIDED BY OWNER. AND INDICATED ONLY FOR COORDINATION.







NEW ROOF PLAN




EXTERIOR BUILDING
ELEVATIONS

EXISTING NEW CONST.

- 2X8 CEDAR TRIM BOARD PAINT TO MATCH CEDAR BOARD AND BATTEN SIDING TO MATCH EXISTING. PAINT TO MATCH. - WOOD RAILING - FLUSH METAL INSULATED DOOR

1 WEST ELEVATION

1/4" = 1'-0"



2 SOUTH ELEVATION

1/4" = 1'-0"