



# MONTANA FISH, WILDLIFE & PARKS

## ADDENDUM NO. 1

---

TO: ALL BIDDERS OF RECORD

PROJECT: Fort Logan FAS & Smith River WMA Road Repairs

FWP PROJECT #: 20-12

DATE: March 6, 2020

FROM: Darcy Yakoweshen, Montana FWP Project Manager

**Acknowledge receipt of this addendum by inserting its number and date in the Proposal Form and on the Bid Envelope. Failure to do so may subject bidder to disqualification.**

This Addendum forms a part of the Contract Documents. Clarification and/or modifications area as follows:

**Remove**

The material for the project, 1-1/2" Crushed Rock and 1" Crushed Road Mix, shall come from the Mikesell Gravel Pit (Bryan Mikesell 547-4133).

**Add**

The material for this project shall not be limited to any one pit. The contractor is responsible to provide material that meets with the specifications.

**Remove**

Contractor shall use 1 1/2" Crushed Rock.

**Add**

Contractor shall use Pit Run in place of 1-1/2" Crushed Rock throughout the specifications.

**Pit Run Gravel Requirements**

<u>Sieve Opening</u>	<u>% Passing</u>
3 inch	100
No.4	25-60
No.200	12 Max

**Add**

Native Seed Blend shall consist of:

<u>Grass Species</u>	<u>% PLS Count</u>	<u>lbs./acre</u>
● Streambank Wheatgrass	40%	Broadcast Rate (16 lbs./acre)
● Western Wheatgrass	20%	
● Sheep Fescue	15% - 20%	
● Blue Grama	15% - 20%	
● -others-	+/-10%	

**END OF ADDENDUM NO. 1**